Contract No.: W912DQ-15-D-3013 Task Order No.: W912DQ18F3001

U. S. Army Corps of Engineers Kansas City District

Design Analysis Report Final Design (100%) Building Demolition

Wolff-Alport Chemical Company Superfund Site Ridgewood, Queens, New York

September 24, 2018



Table of Contents



2.10 Utility Disconnection and Abandonment	2-5
2.11 Clearing	2-6
2.12 Asbestos Abatement and Mercury Lamp and Thermostat Removal	2-6
2.13 Demolition	2-7
2.14 Waste Characterization, Handling and Off-site Disposal	2-8
2.14.1 Demolition Debris to be Disposed of as Radioactive Waste	2-8
2.14.2 Recycling	
2.14.3 Transportation	2-10
2.15 Traffic Control and Haul Routes	2-11
2.16 Backfilling	2-12
2.17 Site Restoration	2-12
2.18 Green Remediation	2-13
2.18.1 Incorporation of Clean Diesel Fuel and Technology	2-13
2.18.2 Material Reuse, Reduction, and Recycling	2-14
2.18.3 Sustainable Practices	2-14
2.19 Demobilization	2-14
2.20 Cost Estimate	2-14
Section 2 Construction Quality Assurance/Quality Control	2.1
Section 3 Construction Quality Assurance/Quality Control 3.1 Construction QA/QC Organization	
3.2 Construction QA/QC Organization	
3.2.1 Review of Technical Submittals	
3.2.2 Field Inspection and Testing of Materials, Equipment, and Installation	
3.2.2.1 Pre-Final Inspection	
3.2.2.2 Final Inspection	
•	
Section 4 Regulations, Standards, and Construction Codes	
4.1 General Regulations	
4.2 Health and Safety	
4.3 Chemical/Radiological Quality Management Plan	
4.4 Demolition/Backfill	
4.5 Transportation and Disposal	
4.6 Construction Codes, Standards and Regulations	
4.6.1 General Construction	4-6
Section 5 Required Permits and Approvals	5-1
5.1 Introduction	5-1
5.2 New York City Department of Transportation	5-1
5.2.1 Occupation of Sidewalks and Roads	5-1
5.3 New York City Department of Buildings	5-1
5.4 New York City Department of Environmental Protection	5-2
5.4.1 Water and Sewer Line Disconnection	5-2
5.4.2 Asbestos Abatement	5-2
Section 6 Health and Safety Program	6-1
6.1 Site Description and Contamination Characterization	
6.2 Hazard Assessment and Risk Analysis	
6.3 Staff Organization, Qualifications, and Responsibilities	



6.4 Training	6-2
6.4 Training6.5 Personal Protective Equipment	6-3
6.6 Medical Surveillance	6-3
6.7 Exposure Monitoring/Air Sampling Program	
6.8 Heat/Cold Stress Monitoring	6-4
6.9 Standard Operating Procedures, Engineering Controls, and Work Practices	6-4
6.10 Site Control Measures	6-5
6.11 Personal Hygiene and Decontamination	
6.12 Equipment Decontamination	6-5
6.13 Emergency Equipment and First Aid Requirements	
6.14 Emergency Response and Contingency Procedures	6-5
6.15 Accident Prevention	
6.16 Logs, Reports, and Recordkeeping	6-6
Section 7 List of Technical Specifications	7-1
Section 8 List of Design Drawings	8-1
Section 9 References	9-1

List of Tables

- Table 1-1 Building Radiological Gamma Spectroscopy Results
- Table 1-2 Remediation Goals
- Table 2-1 Asbestos-Containing Materials and Quantities
- Table 2-2 Inventory List of Materials Containing Mercury
- Table 2-3 Waste Disposal Options Categories
- Table 5-1 Permit Lists

List of Figures

Figure 1-1	Site Location Map
Figure 1-2	Site Plan
Figure 1-3a	Building Gamma Survey – Interior Wall
Figure 1-3b	Building Gamma Survey – Ceiling
Figure 1-3c	Building Gamma Survey – Roof
Figure 1-4	Site Topography and Drainage
Figure 1-5	General RA Construction Schedule
Figure 2-1	Waste Characterization and Disposal Flow Chart



Appendices

Appendix A Radiological Scanning and Sampling Results Appendix B Revised Hazardous Building Materials Survey Appendix C March 2017 Structural Inspection Report Appendix D **Building Demolition Material Calculations** Appendix E **Backfill Volume Calculation**

Appendix F **Permit Applications**



Acronyms

 $\begin{array}{ll} \mu g/kg & \text{micrograms per kilogram} \\ \mu g/L & \text{micrograms per liter} \\ \mu R/hr & \text{microRoentgens per hour} \end{array}$

Ac-228 actinium-228

ACM Asbestos-containing material
AEC Atomic Energy Commission
ALARA as low as reasonably achievable

ANSI American National Standards Institute

APP Accident prevention plan

ARTS Asbestos Reporting and Tracking System
ASSE American Society of Safety Engineers
ASTM American Society for Testing and Materials
ATSDR Agency for Toxic Substances and Disease Registry

A 15DK Agency for Toxic Substances and Dis

BEC Bureau of Environmental Control

bgs below ground surface
C&D construction and disposal
CAMP community air monitoring plan
CDM Smith CDM Federal Programs Corporation

CFR Code of Federal Regulations cis-1,2-DCE cis-1,2-dichloroethene cm² square centimeter

CQC contractor quality control

CVOC chlorinated volatile organic compound
DER Division of Environmental Remediation
DOD United States Department of Defense

DOT United States Department of Transportation

dpm disintegrations per minute EM Engineering Manual

EPA U.S. Environmental Protection Agency

ER Engineering Regulation

FAR Federal Acquisition Regulations

H&S health and safety

HTRW hazardous, toxic, and radioactive waste

ISOCS In Situ Object Counting Systems

LBP lead-based paint

LLC limited liability corporation

NIOSH National Institute for Occupational Safety and Health

NRC United States Nuclear Regulatory Commission

NYC New York City

NYCAC New York City Administrative Code

NYCDDC New York Department of Design and Construction

NYCDEP New York City Department of Environmental Protection



NYCDOB New York City Department of Buildings

NYCDOHMH New York City Department of Health and Mental Hygiene

NYCDOT New York City Department of Transportation NYCRR New York Codes, Rules, and Regulations

NYSDEC New York State Department of Environmental Conservation

NYSDOH New York State Department of Health

OSHA Occupational Safety and Health Administration

PCB polychlorinated biphenyl

PCE tetrachloroethene
pCi/g picocuries per gram
pCi/L picocuries per liter

PPE personal protective equipment

QA quality assurance
QC quality control
RA remedial action
Ra-226 radium-226

RAO remedial action objective RCNY Rules of the City of New York

RD remedial design
RG remediation goal
RI remedial investigation
ROD Record of Decision

SHM safety and health manager SSHP site safety and health plan

site Wolff-Alport Chemical Company Superfund Site

TCE trichloroethene
Th-232 thorium-232
U-238 uranium-238

UFP-QAPP Uniform Federal Policy Quality Assurance Project Plan

USACE United States Army Corps of Engineers

UST underground storage tank WAC waste acceptance criteria

WACC Wolff-Alport Chemical Company



Section 1

Introduction

1.1 Project Overview

This report presents the design analysis prepared by CDM Federal Programs Corporation (CDM Smith) to achieve the requirements set forth in the U.S. Environmental Protection Agency's (EPA) September 2017 Record of Decision (ROD) (EPA 2017) addressing contaminated building materials at the Wolff-Alport Chemical Company (WACC) Superfund Site (the site) located in Ridgewood, Queens, New York. The report was prepared for the United States Army Corps of Engineers (USACE), Kansas City District, Contract No. W912DQ-15-D-3013, Task Order No. W912DQ18F3001.

1.2 Project Organization

The purpose of this design analysis report is to present the technical basis for the design of the building demolition proposed by CDM Smith to achieve the remedial action objectives (RAOs) specified in the ROD related to the building demolition.

This report contains the following sections.

- Section 1: Introduction This section presents the site history and identifies the purpose and scope of this design analysis report. It also presents the overall strategy for project delivery.
- Section 2: Remedial Design Summary This section provides a summary of the remedial design (RD). Major design and construction components, including site preparation, stormwater and erosion control, traffic control, building demolition, waste characterization, backfilling, waste transportation and disposal, and sitewide restoration, are detailed in this section.
- Section 3: Construction Quality Assurance/Quality Control This section provides a summary of the quality assurance (QA) and quality control (QC) organization and the processes and standards that are applicable to site construction.
- Section 4: Construction Codes, Standards, and Regulations This section provides a summary of the construction codes, standards, and regulations that are required to be followed during the remedial activities.
- Section 5: Required Permits and Approvals This section provides a summary of the required permits and approvals that have been identified for the construction of the remedial activities.
- **Section 6: Health and Safety Program** This section provides a summary of the health and safety (H&S) requirements on-site during the remedial activities.



- Section 7: List of Technical Specifications This section provides a list of the specification sections included in the Contract Documents. These are provided under a separate cover.
- Section 8: List of Design Drawings This section provides a list of the Contract Drawings for the design.
- **Section 9: References** References cited in the report are provided in this section.

Tables, figures, and appendices are also included in the report. These materials provide additional information, summarize relevant data, and serve as the basis for design decisions. The following items are specifically noted.

- Design calculations Demolition debris calculations and engineering assumptions are included in the appendices.
- RD drawings The RD drawings for the remedial action (RA) are included under a separate cover. This report refers to the Contract Drawings, which include a site plan, site preparation plan, building demolition plan, site restoration plan, and civil details.

1.3 Summary of Background Information

1.3.1 Site Name, Location, and Description

The site comprises an area of radiological contamination at 1127 Irving Avenue in Ridgewood, Queens, New York on the border of Bushwick, Brooklyn. The site includes the former WACC property, a roughly triangular area of approximately 0.75 acre that is now subdivided into several commercial properties as well as adjacent areas, including streets, sidewalks, commercial and residential properties, and the sewer system where contaminants have migrated or have the potential to migrate in the future. A site location map is provided as Figure 1-1. Figure 1-2 shows the general area of the site.

The former WACC property is bound by Irving Avenue to the southwest, Cooper Avenue to the northwest, and a commercial property to the east. At present, the property is covered with contiguous structures, except along its eastern edge in an area formerly used as a rail spur. The neighborhoods surrounding the former WACC property contain light industry, commercial businesses, residences, a school, and a daycare center. An active rail line passes within 125 feet to the southeast of the property.

The former WACC property (Figure 1-2) consists of several parcels on Block 3725 which, as shown on the tax map of Queens County, include the following buildings:

Lot	Address	Description
31	NA	The former rail spur adjacent to the WACC buildings. It is fenced, covered with gravel and used as an automobile storage/parking area by the Primo Auto Body. The non-fenced portion of the former rail spur, which is not adjacent to the WACC buildings, is partially vegetated.



Lot	Address	Description
33	1133-1139 Irving Avenue	A 1-story masonry warehouse owned by Irving Unique Development, Limited Liability Corporation (LLC) and is currently unoccupied.
42	1129 Irving Avenue	A 1-story masonry building, subdivided and occupied by TerraNova Construction and Primo Auto Body. The TerraNova building is primarily used for construction but also has an office that is frequently occupied. The building housing the Primo Auto Body shop is active, with 5-10 employees typically occupying the building during the work day.
44	1127 Irving Avenue	A 1-story masonry building housing the Celtic Bike Shop, a motorcycle repair business. The building is active, with 2-5 employees typically occupying the building during the work day. This building was previously occupied by Primo Auto Body.
46	1125 Irving Avenue	A 2-story masonry and frame building housing the Jarabacoa delicatessen/grocery, office space, and three residential apartments on the second floor. A second attached one-story masonry building houses Primo Flat Fix and a former mini-all terrain vehicle shop.
48	1514 Cooper Avenue	A 1-story masonry building housing the K&M auto repair shop and office space. The building is actively used.

The sidewalk and street along Irving Avenue adjacent to the WACC buildings are typically filled with vehicles being serviced by the auto businesses. The intersection of Irving Avenue and Moffat Street (i.e., the southern corner of the WACC property) is an active area for trailer parking and unloading.

The current land use of the WACC property is primarily commercial and residential. The predominant land use in the surrounding area is residential (characterized by attached houses and apartment buildings), and the neighborhood is near areas of Brooklyn and Queens that have been under intense redevelopment pressure (primarily residential) over the past 10 years.

1.3.2 Site History

WACC operated at the property from the 1920s until 1954, importing monazite sand via rail and extracting rare earth metals from the material. Monazite sand contains approximately 6 to 8% percent or more of thorium and 0.1 to 0.3% of uranium. The acid treatment process used by WACC converted the phosphate and metal component of the monazite to aqueous species, rendering the rare earth materials extractable while dissolving the thorium and uranium in an acid, such as sulfuric and nitric acid, generating waste process liquors and tailings. This process concentrated thorium-232 (Th-232), uranium-238 (U-238), and their progeny, all of which are radioactive, in the process liquors.

During its operation, WACC occupied three structures that currently comprise Lots 42 and 44. WACC's operation included two yard areas: one between the buildings on Lot 42 and the other on the eastern end of the property at the northern end of Moffat Street. These areas were reportedly used as staging areas for monazite sands or waste tailings containing Th-232 and U-238. The waste tailings were likely spread or buried on the property. WACC likely disposed of the liquid process wastes into the sewer. According to the U.S. Department of Energy, the Atomic Energy



Commission (AEC) ordered WACC to halt sewer disposal of thorium waste in the fall of 1947. Thereafter, thorium was precipitated as thorium oxalate sludge and later sold to AEC.

1.3.3 Summary of Historical Investigations and Remedial Actions

Scoping-level radiological surveys performed by New York State Department of Environmental Conservation (NYSDEC), New York City Department of Health and Mental Hygiene (NYCDOHMH), and EPA in 2007 found radiological impacts throughout the WACC property and the nearby sewer. Follow-up investigations by the New York City Department of Design and Construction (NYCDDC) in 2009 and 2010 found waste tailings consisting of black or gray ash-like material containing elevated Th-232 concentrations beneath the WACC property buildings, adjacent sidewalks, and asphalt surfaces of Irving Avenue and Moffat Street and in the surface soils of the former rail spur (Louis Berger and Associates 2010). During the NYCDDC investigation, elevated levels of thoron and radon gas were detected in the deli basement.

EPA conducted a search for single gas entry points in buildings at the WACC property and in the daycare center and school located nearby during 2010, 2011, and 2012 (EPA 2013). No gas entry points were identified in TerraNova, Primo Auto Body, or Celtic Bike Shop (EPA 2013). No indications of elevated levels of thoron were found in the first and second floors of the Jarabacoa deli. However, the average thoron concentration in the basement of the deli was found to be 13.5 picocuries per liter (pCi/L) from 2.5 hour long combined measurements collected using a RAD7 instrument. The average background thoron concentration in air in the area adjacent to the site was found to be 0.1 pCi/L (Weston Solutions 2013). The screening criteria for thoron in outdoor air developed for the RI was 0.1 pCi/L. All results at the daycare and school were found to be within the normal range of background, except a single location in a school basement crawl space where radon and thoron concentrations were found to be approximately 17.9 and 24.4 pCi/L, respectively. Radon and thoron gas were determined to be emanating from a hole in the concrete floor of the crawl space. The hole was sealed with a concrete plug, and subsequent testing found radon and thoron concentrations had dropped to within normal background ranges.

In February 2012, the Agency for Toxic Substances and Disease Registry (ATSDR) issued a Health Consultation (ATSDR 2012) that noted that exposure to the residual radioactive contamination at the site may pose a health threat under certain long-term exposure scenarios. Based on the ATSDR document, EPA prepared a removal site evaluation for the site in August 2012 to determine whether an immediate response action (i.e., a removal action) was necessary. In September 2012, EPA collected gamma radiation exposure rate measurements and thoron and radon concentration measurements on and around the perimeter of the suspected source area and at background locations. The gamma radiation exposure rate measurements identified hot spots inside the on-site buildings, along the former rail spur, and along the sidewalks and streets adjacent to the former facility and elevated radon concentrations in two of the former WACC property businesses.

In July 2013, EPA, New York State Department of Health (NYSDOH), and NYCDOHMH conducted a radiological assessment of the neighborhood within a 1/2-mile radius of the site (NYSDOH et al. 2014). The data collected during this assessment indicated that there is no unacceptable exposure to the surrounding community from radiological contaminants located at the site.



In 2014, ATSDR performed a follow-up health consultation to evaluate new data collected in a time study of workers, better characterization of the exposure data, improved radon and thoron analysis, and a study of materials that can be used as adequate radiation shielding (ATSDR 2014). The follow-up health consultation concluded the following: (1) radiation exposure levels, adjusted for time spent on tasks without appropriate shielding, exceed ATSDR-established recommended levels; (2) the results of the shielding study showed that, with appropriate shielding in place, the radiation exposures can be greatly reduced significantly; and (3) levels of radon in some locations exceed the recommended EPA limit for residential areas and the applicable limits of Occupational Safety and Health Administration (OSHA).

Based on the 2012 and 2014 ATSDR health consultation, EPA conducted a removal action between October 2012 and April 2014 (Weston Solutions Inc. 2016), which consisted of a gamma radiation assessment and radon sampling at the site; installation of a radon mitigation system in one former WACC property building where radon concentrations exceeded EPA's guidance level of 4 pCi/L; and installation of lead, steel, and concrete shielding in certain areas of the site. Gamma exposure rates in areas where shielding was placed were reduced between 60 and 95% based on a comparison of pre- and post-shielding gamma radiation surveys. Shielding is shown on the Contract Drawings.

1.3.4 Remedial Investigation

The site was included on the National Priorities List on May 12, 2014. EPA conducted field investigations from September 2015 to March 2017 and completed the remedial investigation (RI) and feasibility study reports in July 2017 (CDM Smith 2017a and 2017b).

The nature and extent of contamination in site media developed during the RI was assessed by comparing sample results to the screening criteria developed during the RI (CDM Smith 2017a). The monazite sands brought to the property for processing contained Th-232 and U-238. The processes at Wolff-Alport concentrated and released Th-232 and U-238 into the environment. However, because the minimum detectable activity using gamma spectroscopy for U-238 is high, gamma spectroscopy results are not used as a first line indicator for U-238. Therefore, radium-226 (Ra-226) is used to indicate U-238 levels, assuming the two isotopes are in equilibrium because Ra-226 is the decay progeny of U-238. Therefore, Th-232 in combination with Ra-226 are used to determine the nature and extent of contamination associated with WACC, and the primary contaminants of concern at the site are the radioactive isotopes Th-232 and Ra-226. The following sections present a discussion of the WACC property contamination.

1.3.4.1 Building Materials

Gamma surveys to measure gamma radiation were performed inside the buildings at the WACC property, including Lot 33 (warehouse), Lot 42 (Terra Nova and Primo Auto Body), Lot 44 (Celtic Bike Shop), Lot 46 (Jarabacoa Deli and Primo Flat Fix), and Lot 48 (K&M Auto Repair), to obtain gamma radiation counts per minute for the building surfaces. The gamma count rates provide an indication of the presence of elevated areas of radioactivity. This survey method is useful in identifying locations likely to have contaminants embedded or on the surface of building materials. Gamma counts from wall, ceiling, and roof surveys in ranges of multiples of background are presented on Figures 1-3a, 1-3b, and 1-3c, respectively.



Locations to conduct additional alpha/beta measurements, wipe sampling, and building material core sampling were selected based on the results of the gamma surveys conducted throughout the WACC buildings. The alpha/beta results were compared to the acceptance criterion for Th-232 from United States Nuclear Regulatory Commission's (NRC's) Regulatory Guide 1.86 (1974) on decommissioning release limits, 1,000 disintegrations per minute (dpm)/square centimeter (cm²), to determine what areas contained elevated alpha.

Direct alpha/beta measurements were greater than 1,000 dpm/cm² at three locations: Lot 46 along the eastern wall near the south corner in the Jarabacoa Deli basement, Lot 44 in the Celtic Bike Shop, and Lot 42 in the Primo Auto Body shop. All wipe samples collected at these locations showed no removable contamination. The lack of removable contamination provides assurance that workers are not inhaling or ingesting contaminant particulates when brushing up against/contacting the brick surfaces.

At each location selected for direct alpha/beta measurements, samples of the building materials were collected and sent to a subcontract laboratory for gamma spectroscopy analysis to determine the radionuclide present and their respective concentrations within the sampled material. Sample locations are shown on Figure 1-3a, and sample results are presented on Table 1-1.

The results show that contamination remains in the building structures at the WACC property, primarily in the buildings that previously operated the kiln/vat in which monazite sands processing took place (Lots 42 and 44), in the basement of the deli (Lot 46), and to a lesser extent, in the warehouse on Lot 33 constructed above the former yard area. Contaminants are primarily embedded in the building structure with the highest concentration of Th-232 at 415.2 picocuries per gram (pCi/g) and Ra-226 at 44.2 pCi/g on a sample of brick from Lot 44. The brick sample collected from Lot 33 contained Th-232 concentrations slightly above the screening criterion (1.2 pCi/g), with a concentration of 1.7 pCi/g. Radiological sampling and scanning results and drawings from the RI are included in Appendix A

Asbestos-containing material (ACM), lead-based paint (LBP), and other suspect hazardous materials were also found in the WACC building structures and were comparable to a building of its age. A hazardous building material survey report is included in Appendix B.

1.3.4.2 Soils

The soil RI investigation included gamma scan surveys, soil boring downhole gamma scans, and soil sampling to delineate the impacted soils at the WACC property and potentially impacted nearby properties. Soil sampling was conducted for non-radiological parameters to determine if the site had other contamination. The soil contamination discussion included herein includes only those soils that the RA Contractor may encounter.

1.3.4.2.1 Below WACC Buildings

Radiological contamination under the WACC property buildings was encountered during previous investigations and the RI investigation. The RI screening criteria for Th-232 and Ra-226 was 1.2 and 0.9 pCi/g, respectively. Surficial contamination (0 to 2 feet below ground surface [bgs]) was found below the building on Lot 33 with a maximum Th-232 concentration of 77.4 pCi/g. The associated Ra-226 concentration for this sample was 20.7 pCi/g.



Deep contamination was found below the buildings on Lot 42 (Primo Auto Body) and Lot 44 (Celtic Bike Shop). The deep contamination extends to a depth of 28 feet bgs under Lot 44 and down to 24 feet bgs under Lot 42. The highest Th-232 concentrations observed during the RI were found in this area, with maximum concentrations of 760 and 533.8 pCi/g found below Lot 42 at 6 to 8 feet bgs and 10 to 12 feet bgs, respectively. The associated Ra-226 concentrations for these samples were 1.5 and 2.4 pCi/g, respectively.

Concentrations of benzo(a)pyrene and polychlorinated biphenyls (PCBs) (Aroclor 1260) were found above their respective screening criterion of 16 and 240 micrograms per kilogram ($\mu g/kg$), respectively. Several metals were also found above their screening criteria but were mostly comparable to background, indicating that the metals are likely associated with the urban fill or naturally occurring in glacial soils.

1.3.4.2.2 Former Rail Spur Area and Streets

Surficial radiological contamination was observed in the former rail spur area and in the southeastern corner of Lot 31/northern area of 350 Moffat Street (area adjacent to the Irving Avenue/Moffat Street intersection). Soil borings advanced in the southern portion of Lot 31 adjacent to the Irving Avenue/Moffat Street intersection showed elevated levels of Th-232 in surficial soil samples. The maximum concentration was 19.3 pCi/g.

Irving Avenue east of the Irving Avenue/Moffat Street intersection likely contains deep contamination associated with disposal of contaminated process liquors in the sewer line in this area that may have leaked to the surrounding soils. One sample collected during the RI had a Th-232 concentration of 5 pCi/g and a Ra-226 concentration of 1.2 pCi/g. Two previous sample locations contained deeper contamination from 16 to 20 feet bgs.

The Irving Avenue/Moffat Street intersection had the highest gamma scan readings outside of the WACC property. Deeper contamination down to 8 feet bgs was observed at the intersection and the northern portion of Moffat Street at a concentration of 3.3 pCi/g of Th-232 and 2.3 pCi/g of Ra-226. Soil samples from a soil boring advanced in the middle of the intersection of the two streets (SB-50) found 209.9 pCi/g of Th-232 and 38.7 pCi/g of Ra-226 in the top 1 foot of soil.

Levels of contamination on Moffat Street moving south away from the WACC property generally decreased. Elevated concentrations of Th-232 and Ra-226 were observed in mostly surficial samples collected from 0 to 2 feet bgs. Two soil borings located in gamma reading hotspots had elevated surficial Th-232 at 28.55 and 59.4 pCi/g and Ra-226 at 5.5 and 11.1 pCi/g, respectively. Soil observations at these locations showed potential waste tailings in the top 1 foot of soil. Approximately 40 feet south from the hotspot on Moffat Street, gamma readings drop to just above or within background levels.

1.3.4.2.3 308 Cooper Street

A gamma walk-over survey at 308 Cooper Street showed most of the activity at this property is only slightly above background levels, except the northeastern corner of the property, which had readings at least twice background levels. Results from a boring in the eastern corner of this property showed Th-232 and Ra-226 at maximum concentrations of 6.4 and 1.7 pCi/g, respectively, in the surficial soil sample.



1.3.4.2.4 338-348 and 350 Moffat Street

Gamma readings at this property were mostly within background levels. Soil samples collected from borings through the floors of the property buildings showed slightly elevated concentrations but less than two times the background of both Th-232 and Ra-226 from 0 to 10 feet bgs. The maximum concentrations of Th-232 and Ra-226 were 2.4 and 1.8 pCi/g, respectively.

Results for soil samples collected outside the building footprint found slightly elevated Th-232 concentrations but less than two times the screening criterion in a majority of the soil samples. However, toward the northeast corner of the building adjacent to the southern corner of Lot 31, soil gamma readings were elevated, with counts greater than four times background. A soil sample collected from 0 to 2 feet bgs in this area contained Th-232 at 4.9 pCi/g and Ra-226 at 3.2 pCi/g.

1.3.4.3 Sewer

The RI sewer investigation found significant radionuclide contamination present in the combined sewer system originating at the WACC property. Gamma count measurements are significantly elevated in the manholes south of the WACC buildings on Irving Avenue where process liquors containing thorium were likely discharged. The elevated gamma counts (>20 times background) continue in the sewer line and manholes on Irving Avenue for approximately two blocks. Radionuclide contamination within the pipes and the manholes is present in sediments and construction materials in the sewer manholes near the WACC property. The maximum radionuclide concentrations in sewer materials were found in the manhole located near the intersection of Irving Avenue and Cooper Avenue, with Th-232 at 2,536.2 pCi/g and Ra-226 at 163.1 pCi/g. The maximum Th-232 concentration in sewer sediments was observed in the manhole located south of the WACC property on Irving Avenue, with Th-232 at 1,218.1 pCi/g and Ra-226 at 45.9 pCi/g.

Gamma scan levels were found to generally drop to four times background at the intersection of Irving Avenue and Schaeffer Street and drop to background at the intersection of Irving Avenue and Eldert Street, with sporadic occurrences of gamma levels above four times background continuing in the sewer along Halsey Street to Wyckoff Avenue.

Radionuclide contamination appeared limited to the interior of the sewers because soil borings installed adjacent to the sewer lines found only limited radionuclide contamination. A data gap does remain because the bedding material below the sewers may be contaminated, as the fiberscope survey confirmed that there are breaks in the pipeline along Irving Avenue.

Sediment radionuclide concentrations at the Newtown Creek outfall were elevated, with a maximum concentration of 56 pCi/g of Th-232 from 5 to 6 feet bgs. Samples with elevated concentrations were limited to the area immediately adjacent to the outfall discharge.

1.3.4.4 Groundwater

The data collected indicated that the groundwater at the WACC site is not impacted by radionuclides.

Chlorinated volatile organic compounds (CVOCs), including tetrachloroethene (PCE), trichloroethene (TCE), and cis-1,2-dichloroethene (cis-1,2-DCE), exceeded screening criteria in the groundwater at each of the six monitoring wells, including an upgradient well. The screening



criteria for cis-1,2-DCE and PCE was 5 micrograms per liter (μ g/L) and was based on the NYSDEC standards and guidance values for Class GA groundwater. The screening criterion for TCE was 0.49 μ g/L and was based on the EPA Regional Screening Levels for tap water. Concentrations for cis-1,2-DCE ranged from 0.41 to 25 μ g/L. Concentrations for TCE ranged from 0.95 to 9 μ g/L. Concentrations for PCE ranged from 72 to 960 μ g/L. The RI concluded that CVOCs in groundwater at the site are likely from an upgradient source.

1.3.4.5 Exposure rate

Gamma exposure rate surveys conducted during the RI confirmed the results from the previous gamma exposure rate surveys conducted within the WACC buildings, on sidewalks, and on the streets near the WACC property. Exposure rates remain above background levels throughout each of these areas but were within the background range outside of a few blocks from the WACC property. The maximum gamma exposure rates observed were collected on the roadway of Irving Avenue, one near the sidewalk curb and one in the middle of the street, south of the WACC property at 220 and 338 microRoentgens per hour (μ R/hr).

1.3.4.6 School and Daycare

RI sampling performed at the school and daycare did not indicate contamination due to the WACC processes as the data generated was all below or slightly above the RI screening criteria. Results included:

- School Results of long-term radon and thoron sampling were below the RI screening criteria. Soil results for Th-232 and Ra-226 from samples collected below the school were below background concentrations for soil.
- Daycare Short-term radon concentrations collected at the daycare were either below or within 0.2 pCi/L of the screening criteria. The 7-day continuous air surveys for radon were below the RI screening criterion, and the 5-day continuous air surveys for thoron were slightly above the RI screening criterion. Soil results for samples collected from underneath the daycare were below background concentrations for soil.

Gamma exposure rates were also collected from within the school and daycare and were all within or below the background observed for the neighborhood.

1.3.5 Physical Characteristics of the Site

1.3.5.1 Topography and Drainage

The WACC property is at an elevation of approximately 70 feet above mean sea level, and the ground surface in the area generally slopes gently to the southwest. The eastern edge of the site is adjacent to an elevated train line parallel to Moffat Street. The ground surface rises sharply toward the train line and continues to rise to the cemetery east of the site to elevations as high as 160 feet above mean sea level. The cemetery areas are elevated as they are in glacial terminal moraine deposits.

The site is in a highly urbanized area where infiltration of precipitation is largely restricted due to the high percentage of ground surface covered by pavement and buildings. The large cemetery just east of the site is mostly unpaved and allows more infiltration of precipitation than



surrounding areas. Storm water in the majority of the site area is directed into catch basins that connect to a combined sewer system (shown on Figure 1-4). The WACC property is located at the head of a branch of the sewer system. The sewer flows away from the property to the west down Irving Avenue before turning on Halsey Street and joining larger sewers on Wyckoff Avenue. During large storms, these sewers discharge directly into the East Branch of Newtown Creek, which is approximately 1.9 miles from the WACC property.

1.3.5.2 Site-Specific Geology

The site is located along the western edge of Queens County on the Brooklyn border. Drilling advanced into the upper portion of the aquifer in this area and encountered two types of unconsolidated material: fill and Upper Glacial Aquifer deposits (till and outwash).

Fill

Fill near the WACC property is typically 5 to 15 feet thick and generally characterized by the presence of man-made materials (brick, coal, various building materials) intermixed with silt, sands, and gravels. The distinction between fill and the underlying glacial material was difficult when man-made debris was not present in the soil. This is representative of regrading of native materials within the area.

Much of the upper layers of the fill in borings at the WACC property and in some borings to the south on Moffat Street was a black, gray, and/or white cinder or ash-like material. This material is likely waste tailings described in previous reports and was found between 0 and 4 feet bgs near the WACC property and between 0 and 6 feet bgs along Moffat Street. This material corresponds well with intervals of elevated downhole gamma readings collected at the borings.

Upper Glacial Aquifer Deposits

Soil borings at the site generally indicate the presence of Upper Glacial Aquifer soils extending from the bottom of fill (0 to 15 feet bgs) to beyond the deepest boring performed at the site (75 feet bgs). The upper portion of the glacial deposits (down to approximately 25 to 37 feet bgs) is made up of glacial till, which is yellowish brown dense silty sand and gravel. The material underlying the glacial till is glacial outwash, slightly more uniform and coarse in texture than the till and extends from the bottom of the till to at least 75 feet bgs (total depth of exploration at the site).

Based on ground surface topography and the top of geologic surface contour maps of the various units (discussed above) created by Soren (1978), the interpreted total thickness of the Upper Glacial Aquifer soils in the site area is about 170 feet. The Magothy Formation is absent at the site, and the Upper Glacial Aquifer is underlain by the Gardiners Clay (approximately 50 feet thick), which is in turn underlain by the Raritan Clay (approximately 130 feet thick). The Lloyd aquifer is approximately 40 feet thick, and the bedrock surface is expected to be encountered at a depth of about 390 feet bgs, although some sources have estimated this depth to be closer to 450 feet bgs.

1.4 Cultural Resource Survey

Richard Grubb & Associates, Inc performed a Phase 1A Literature Search and Archaeological Sensitivity Assessment for the WACC property on April 5, 2018 to examine the current conditions of the project area and identify any areas of archaeological potential. The results of the Phase 1A survey indicate that the Area of Potential Effects possesses low archaeological sensitivity for both



prehistoric and historical archaeological resources. No further work is recommended (Richard Grubb and Associates 2018).

1.5 Summary of Site Contamination

Buildings

Radionuclide contamination remains in the building structures at the WACC property, primarily in the buildings that previously operated as the kiln/vat in which monazite sand processing took place and the storage yard where sands were loaded into the kiln-vat (Lots 42 and 44), in the basement of the deli (Lot 46), and to a lesser extent, in the warehouse on Lot 33 that was constructed above a former yard area.

ACM, LBP, and other suspect hazardous materials were found in the WACC building structures.

Soils

Under the WACC buildings, radiological contamination extends down to a depth of 28 feet bgs under Lot 44, the former kiln/vat building, and down to 24 feet bgs under Lot 42, the former yard where the monazite sands were loaded into the kiln/vat building for processing.

There is widespread surficial radiological contamination related to storage or filling of tailings or monazite sands and/or surface runoff/erosion from those areas. Surficial contamination was observed in the former rail spur area, at the intersection of Irving Avenue and Moffat Street, the northern portion of Moffat Street and the eastern portion of Irving Avenue, and in the southeastern corner of Lot 31/northern part of 350 Moffat (area adjacent to the Moffat/Irving intersection).

PAH contamination was found throughout the shallow soils at the WACC property. PAHs found as deep as 7 feet bgs may be related to former underground storage tanks (USTs) or use of the area to store demolished cars. Similar concentrations were also found at the nearby property, 308 Cooper Street. Elevated concentrations of PCBs were found at the WACC property. PCBs in the shallow soils may also be related to USTs or a sump below the building in Lot 33. Arsenic and iron concentrations were similar at all depths within the urban fill below the site and within the range of background levels, indicating the metals are likely associated with urban fill.

Sewer

Radionuclide contamination within the combined sewer system is present near the WACC property in sediments/sludge and materials comprising the sewer pipes and manholes. Radionuclide contamination is significantly elevated in the manholes on Irving Avenue adjacent to the WACC buildings where process liquors containing high concentrations of radionuclides were likely discharged. The elevated gamma levels (>20 times background) continue in the sewer line and manholes on Irving Avenue for approximately two blocks to Decatur Street.

Gamma counts within the combined sewer system generally drop to four times background at the intersection of Irving Avenue and Schaeffer Street and drop to background at the intersection of Irving Avenue and Eldert Street, with sporadic occurrences of gamma levels above four times background continuing in the sewer along Halsey Street to Wyckoff Avenue.



Groundwater

CVOCs, including PCE, TCE, and cis-1,2-DCE, are above the NYSDEC standards and guidance values for Class GA groundwater. The groundwater is not impacted by radionuclides.

Exposure Rate

Exposure rates remain above background levels within the WACC buildings, on sidewalks, and on the streets near the WACC property but were within the background range outside of a few blocks from the WACC property. The maximum gamma exposure rates observed were collected on Irving Avenue south of the WACC property at 220 $\mu R/hr$ near the sidewalk curb and 338 $\mu R/hr$ in the middle of the street. These readings were taken at waist height or approximately 3 feet above the ground surface.

Air

Air sampling conducted prior to radiation mitigation activities in 2012 and 2013 (installation of a radon mitigation system followed by radiation shielding) found the highest levels of air contamination at Lots 31, 42, 44, and 46 where the majority of the WACC processing activities took place. The highest concentration of thoron in air was detected on Lot 31 in outdoor air. Concentrations of radon previously detected at the WACC property decreased following radon mitigation activities completed at Lots 42 and 44. The maximum radon concentration following the mitigation activities was observed in the TerraNova portion of Lot 42 at a concentration of 1.5 pCi/L. However, radon levels in the three buildings greater than the background radon concentration (0.5 pCi/L) were still observed. Radon results at the Jarabacoa deli ranged from 1.1 to 3.5 pCi/L.

1.6 ROD Requirements

1.6.1 Remedial Action Objectives

Remedial action objectives (RAOs) set forth in the ROD are specific objectives to protect human health and the environment. These objectives were based on applicable or relevant and appropriate requirements and site-specific risk-based levels.

The RAOs for the site are:

- Reduce or eliminate human exposure via inhalation of radon and thoron, incidental ingestion, dermal adsorption, and external exposure to radiological contamination (Ra-226 and Th-232) that may be present within the former WACC property buildings to levels protective of current and anticipated future use by preventing exposure to contaminant levels above remediation goals (RGs);
- Reduce or eliminate the human exposure threat via inhalation, incidental ingestion, dermal adsorption, and external exposure to contaminated Site soils and solids (i.e., sewer pipe and sediments/sludge in sewers) to levels protective of current and anticipated future land use by preventing exposure to benzo(a)pyrene, Aroclor-1260, Ra-226, and Th-232 concentrations above RGs; and
- Prevent/minimize the migration of site contaminants off-site through surface runoff, dust particulate migration, and combined sewer overflow discharge.



Table 1-2 lists the RGs for the site.

In achieving the RAOs for the site, EPA will also rely on an "as low as reasonably achievable" (ALARA) (10 Code of Federal Regulations [CFR] 20.1003) principle. An ALARA approach will be implemented during the remediation of the Site.

1.6.2 Selected Remedy

The major components of the ROD-selected remedy related to this RD are:

- All tenants of the buildings on the former WACC property will be permanently relocated.
 Tenant relocation is not included in this design and is being performed separately by EPA and USACE.
- All the buildings on the former WACC property will be demolished.
- All demolition debris will be transported and disposed of offsite.

1.7 Overall Strategy for Project Delivery

1.7.1 Performance-Based Design Components

According to the scope of work, this RD includes several performance-based design components for which detailed designs will be developed and proposed by the RA Contractor. The Contract Documents (contract specifications and contract drawings) were prepared to provide minimum design requirements for these components. These minimum requirements were developed based on industry standards and technical and present-worth cost considerations that are specific to conditions at the WACC property.

The performance-based design includes the following components.

- Utility disconnection, including disconnection of water, sewer, natural gas, and overhead electric lines
- Structural stabilization of basement walls on Lot 46
- Building demolition, including sequencing and method
- Waste characterization

For these design components, CDM Smith has developed recommendations that are presented in Section 2. However, it is the responsibility of the RA Contractor to design, propose, and implement these components of the remediation.

1.7.2 Procurement Method/Contract Strategy

The Contract Documents will be used by USACE to obtain the services of a Contractor, either through a pre-placed contract mechanism or through the solicitation of proposals.



1.7.3 Implementation Schedule

A representative RA construction schedule illustrating the general time requirements for completion of work is presented in **Figure 1-5**

1.7.4 Review of Project Requirements

CDM Smith has reviewed and incorporated all applicable project requirements into the design. USACE and EPA evaluated conformance with the project requirements during the design kickoff meeting on February 27, 2018. USACE, EPA, and NYSDEC, NYSDOH, New York City Department of Environmental Protection (NYCDEP), NYCDDC. New York City Department of Transportation (NYCDOT), Department of Energy, and ATSDR had independently evaluated conformance with the project requirements as part of the review comments process, which occurred following the 95% design submission. Review comments were resolved and incorporated by CDM Smith into the final (100%) design submittal.

During the RA construction, additional reviews will be required by USACE as part of the construction QA/QC program to verify that the RA Contractor executes this RD in accordance with the design documents.



Section 2

Remedial Design Summary

This section provides a summary of this RD presented in the Contract Documents, including the major design assumptions and rationale that were used to develop the key construction components of the project.

2.1 Overview

The objectives of this RD are to describe and detail the required procedures to enable USACE to procure an RA contractor to implement the selected remedy as specified in the ROD.

The major design components include the following items:

- Furnishing temporary facilities, equipment decontamination area, and site security
- Site preparation, including clearing, removal of any remaining debris after tenant relocation, monitoring well decommissioning, and disconnection of utilities providing services to the buildings to be demolished
- Demolition of all on-site buildings to the top of floor slab except for the two-story building on Lot 46, which will be demolished, leaving only the basement walls and floor
- Waste characterization and off-site transportation and disposal
- Backfilling basement and sumps to ground surface, as needed
- Site restoration, including installation of an exclusion fencing on the WACC property

2.2 Pre-Mobilization Activities

As part of pre-mobilization activities, the RA Contractor will be required to submit the following plans to the Contracting Officer for approval.

- Accident prevention plan (APP), which will include the site safety and health plan, activity
 hazard analyses, and lead compliance plan as appendices to address all occupational safety
 and health hazards associated with the remedial action work.
- Uniform Federal Policy Quality Assurance Project Plan (UFP-QAPP), which will describe all chemical and radiological parameter measurements for the remedial action with sufficient detail to obtain data to meet the project data quality objectives.
- Community air monitoring plan (CAMP), which will establish the protocols necessary for the anticipation, recognition, evaluation, and control of emissions associated with each task performed depending upon site-specific conditions. The CAMP will include provisions for continuous (24/7) monitoring of the site perimeter during activities that could re-suspend particulate matter into the air.



- Contractor quality control plan, which includes the procedures the RA Contractor will follow to implement the requirements of the contract clause titled "Inspection of Construction."
- Security plan, which describes the procedures the RA Contractor will follow for site access to be implemented.
- Traffic control plan, which will include the proposed traffic control details for the maintenance of traffic and access around the site.
- Erosion control and stormwater management plan, which will describe the measures the RA Contractor will implement to prevent runoff from the site entering and polluting the storm sewers and downgradient water bodies.
- Environmental protection plan, which will present a comprehensive overview of known or potential environmental issues that the RA Contractor must address during construction.
- Site preparation plan, which will address in detail all the work to be completed as part of site preparation, including construction of temporary facilities and temporary fencing, installation of erosion control and stormwater management, debris removal, monitoring well decommissioning, disconnection of utilities, and clearing.
- Demolition plan, which will include a detailed description of methods and equipment to be used for each operation to be performed as part of demolition and the sequence of operations, providing contingencies for changes that may be required during work based on safety requirements or unexpected conditions encountered.
- Waste management and transportation plan, which will include details on how wastes will be managed, waste minimization methods, handling of demolition debris, approach to recycling, waste characterization methods, proposed landfill and recycling facilities for waste disposal and their information, waste classification and waste volume estimates, letters of commitment from the proposed waste haulers and disposal facilities, methods and equipment to be used to ensure accurate weight measurements of waste material, waste manifesting procedures, information on transfer facilities if proposed to be used, and proposed truck routes.
- Asbestos abatement and disposal plan, which will include specific health and safety procedures to be employed for asbestos work; outline of sequencing of asbestos-related work; procedures to be employed as part of pre-removal, abatement, and post-removal activities; waste storage and disposal; typical work site information; planning air monitoring strategies; methods to control the spread of ACM wastes and airborne fibers; proposed waste handling; and storage materials, equipment, and procedures.
- Lamp and thermostat removal plan, which will include work procedures to be used in the removal, packaging, and storage of mercury-containing lamps and thermostats.



 Lamp and thermostat disposal plan, which will include estimated quantities of wastes to be generated, disposed of, and recycled; disposal facility information; and qualifications of personnel who will perform the work.

2.3 Contractor Mobilization

Access to the WACC property will be coordinated through EPA. The RA Contractor will mobilize all temporary facilities, equipment, and materials to a support zone, as approved by the Contracting Officer. The support zone will house the EPA, USACE, and Contractor's on-site personnel. A security shed will also be located within the support zone.

2.4 Temporary Facilities/Staging Area

The RA Contractor will be responsible for providing temporary safe access and facilities for construction personnel at the site. It is anticipated that three trailers—one for the RA Contractor, one for EPA/USACE, and one for supplies/equipment storage—will be utilized during the remediation. The RA Contractor will provide temporary fencing, as needed, in accordance with New York City Department of Building (NYCDOB) regulations. The RA Contractor is responsible for all utility hook-ups. The utility company contacts, at the time of the design, are listed on Contract Drawing Sheet G-1.

2.5 Site Security

The RA Contractor will be required to secure the WACC property to prevent unauthorized entry during the remedial construction. The WACC property is currently secured with a 6-foot and 8-foot high chain-link fence to prevent public access. Site security will be provided to:

- Deter, restrict, and/or control financial losses to the Government and the RA Contractor.
 This includes prevention or detection of theft, vandalism, sabotage, and arson.
- Keep unauthorized people from entering the Site, receiving injuries, and removing equipment or hazardous substances.
- Keep unauthorized people from taking action on the Site that might exacerbate the environmental problem or interfere with its remediation.

Site security personnel will be required on-site outside of work hours during weekdays and 24 hours a day during weekends, holidays, and days when no activities are in progress. Security will be established upon the RA Contractor's mobilization to the site. Site security personnel will provide control of all persons, equipment, and vehicles entering and leaving the site. Site security personnel will require all personnel and visitors to sign in and out and will maintain a log of all site access.

2.6 Community Air Monitoring

The RA Contractor will be responsible for providing all equipment, materials, and personnel necessary to monitor and quantify dust and radioactivity levels at the WACC property perimeter fence line during the demolition and transportation and disposal activities. The RA Contractor will prepare a CAMP in accordance with Specification Section 01 35 55, Clean Air Act (40 CFR 50),



and Division of Environmental Remediation (DER) 10 to manage airborne dust and contaminants generated during remedial construction activities. The CAMP will include the application of 10 CFR 61, Appendix E Th-232 limits and 10 CFR 20.1101(d) requirements to maintain public exposures ALARA by limiting air concentrations to 6.2E-16 microcuries per cubic centimeter [equivalent to 10 millirem annual effective dose equivalent]. The CAMP will establish, in detail, the protocols necessary for the anticipation, recognition, evaluation, and control of emissions associated with each task performed based on site-specific conditions. In addition, fence-line gamma radiation levels will be monitored by limiting the gamma exposure to 5 uR/hr above the initial exposure rate level as described in Specification Section 01 35 29, Table 01 35 29-2.

The remedial construction will be performed in a manner such that ambient air quality objectives at the WACC property perimeter are achieved in accordance with the action levels for respirable dust and alpha radiation presented in Specification Section 01 35 55, Table 01 35 55-1. All air monitoring activities will be conducted continuously (24/7) when site activities have the potential for resuspending particulate matter into the air. In addition to air monitoring, the RA Contractor will be required to furnish and maintain a portable meteorological station for the continuous observation and recording of wind speed, wind direction, ambient air temperature, atmospheric pressure, atmospheric humidity, solar insolation, and atmospheric precipitation.

2.7 Monitoring Well Decommissioning

On-site wells MW-01, MW-02, MW-03, MW-04, and MW-05 will be decommissioned in accordance with NYSDEC CP-43, "Groundwater Monitoring Well Decommissioning Policy," and Contract Documents by a New York state-registered well driller. The driller will grout wells to the top of casing in accordance with Section 2.1 of CP-43, but the upper 5 feet of well casing will be left in-place and removed in the next phase of remediation at the site as part of contaminated soil excavation activities. The RA Contractor will submit the NYSDEC Water Well Abandonment and Decommissioning Report for each well to NYSDEC and provide copies to USACE. Water generated during well decommissioning will be collected, characterized, and disposed of off-site according to its chemical characteristics. Based on data collected during the RI, it is assumed that decontamination water will be disposed of as nonhazardous waste "

2.8 Equipment Decontamination Facilities

The RA Contractor will construct a decontamination pad for decontamination of equipment and vehicles in accordance with the contract specifications. All equipment/vehicles that come in contact with contaminated materials will be decontaminated prior to leaving the WACC property in the Contaminant Reduction Zone. All decontamination water will be collected, characterized and disposed of off-site according to its chemical characteristics. Based on data collected during the RI, it is assumed that decontamination water will be disposed of as nonhazardous waste.

2.9 Stormwater, Soil Erosion, and Sediment Control

The WACC property is approximately 0.75 acre in size, and soil excavation will be limited to disconnection and abandonment of underground utilities during the RA; therefore, meeting the substantive requirements of the General State Pollution Discharge Elimination System permit for construction activities will not be required.



The RA Contractor will develop an erosion control and stormwater management plan, incorporating best management practices. The plan will be submitted to the Contracting Officer prior to the start of construction activities.

Erosion and stormwater control measures will be implemented prior to initiation of the RA. The RA Contractor will be required to maintain temporary erosion and stormwater control features throughout the duration of the RA.

2.10 Utility Disconnection and Abandonment

The RA Contractor will be responsible for utility disconnection before building demolition. Utilities include water, sewer, natural gas, and electric. The approximate locations of subsurface utilities and overhead electrical lines are shown on Contract Drawing Sheet C-2.

All soil excavated during utility disconnection will be backfilled into the excavation. Road cuts will be repaired in accordance with NYCDOT requirements.

Water and Sewer Lines

A New York City (NYC)-licensed master plumber will apply for a permit and disconnect the water and sewer service lines. Per NYC water service disconnection regulations, the water service line connection to the water main must be permanently destroyed. However, to minimize excavation of contaminated soil and removal of lead/steel shielding from sidewalk, the water service line disconnection will be completed at the water main with a concrete plug. Sewer line disconnection will be completed at the curb with a concrete plug. Both water and sewer line disconnection will require excavation below the road/sidewalk. All remnants of the subsurface utility service lines to the buildings will be removed during the next phase of remediation at the site as part of contaminated soil excavation activities.

Two water service lines on Irving Avenue were identified during the RI, one to Lot 44 and the other to Lot 33. The Irving Avenue water main is an 8-inch lined cast iron pipe constructed in 1947. The type of water line connection to the water main is currently unknown. Although not identified during the RI, it is assumed that several water service line connections to Lot 46 and Lot 48 exist from the 48-inch cast iron pipe constructed in 1892 on Cooper Avenue. Based on the age of the existing abandoned buildings, it is assumed that the water main connections may be a lead joint wet connection with a lead pipe service line. All lead removal work will be completed in accordance with the RA Contractor's lead compliance plan.

The RI did not identify which sewer service lines were serving the buildings; however, it is assumed that there are connections to the sewer main to Lots 44 and 42 on Irving Avenue and to Lots 46 and 48 on Cooper Avenue. The RA Contractor will verify sewer service line connection locations.

Natural Gas Lines

The RA Contractor will coordinate disconnection of natural gas lines with the utility company, Con Edison.



Electric Lines

The RA Contractor will coordinate disconnection of electric lines with the utility company, Con Edison. All overhead electric lines connected to the buildings from the main pole will be removed.

Excavated materials or components requiring disposal will be containerized and the containers re-located onto the work site, characterized as specified in Section 2.14, and stored with other containers awaiting transport for disposal and shipped for disposal when shipping manifests have been completed and approved.

2.11 Clearing

The RA Contractor will clear trees between Lots 33 and 42 after demolition of building on Lot 33. Trees will be cut flush to the ground surface. Grubbing of stumps and roots will not be performed. The stumps and roots will be removed during the excavation of contaminated soil, which will occur under a separate RA contract.

Prior to clearing, the RA Contractor will collect two wood core samples from the trunk of a tree at 1 foot above ground as specified in Specification Section 02 40 10 to determine if the trees contain radiological contamination at concentrations that would prevent recycling or disposal as a Subtitle D waste. The wood core samples will be analyzed for Ra-226 and Th-232.

2.12 Asbestos Abatement and Mercury Lamp and Thermostat Removal

A hazardous building materials survey was performed for the property buildings in 2015 to determine presence of ACM, LBP, PCBs, and various mercury-, chlorofluorocarbon-, or tritium-containing materials. At the time of the survey, access to the second floor of the building on Lot 46 was not provided. The report is provided in Appendix B.

The survey found known ACM; assumed ACM (in inaccessible areas that prevented sampling); LBP; and suspected mercury lamps through the building structures. ACM tar was used in the construction of the buildings and found and/or assumed to be in wire insulation and electrical panels, roofing materials, window caulking, and interior construction materials. A summary of the ACM and quantities is presented in Table 2-1.

LBP was found in the buildings on Lot 42, Lot 46, and Lot 48. Light ballasts were labeled as not containing PCBs. Mercury was assumed to be present in all fluorescent light bulbs and wall thermostats throughout, which included fluorescent light bulbs, light ballasts, and wall thermostats. An inventory of items containing mercury is presented in Table 2-2.

Under the Lead Renovation, Repair, and Painting Rule, EPA does not require that contractors performing total demolition of a structure be lead-safe certified by EPA. Additionally, under EPA's Proposed Rule on the Management and Disposal of Lead-Based Paint Debris (EPA 1998), LBP debris does not require toxicity characteristic leaching procedure testing and may be disposed of in a construction and disposal (C&D) landfill. Accordingly, LBP abatement will not be performed prior to demolition. However, LBP was found on recyclable nonporous materials (metal shelves, door cases, steel columns), which cannot be recycled with the LBP. All nonporous material will be abated for LBP at the site prior to recycling.



Lamps and thermostats containing mercury will be removed prior to building demolition in accordance with the RA Contractor's approved lamp and thermostat removal plan and Specification Section 02 84 16. All lamps and thermostats containing mercury will be disposed of offsite at approved landfill.

Asbestos abatement will be performed prior to the initiation of demolition activities in accordance with New York State Rule for Asbestos, Part 56-11.4 and Specification Section 02 82 13. Asbestos abatement is required to be completed before NYCDOB will issue a work permit for demolition. Asbestos abatement will be performed by a New York-licensed asbestos contractor. Air monitoring will be conducted during asbestos abatement. Removal of lamps containing mercury will also be performed prior to initiation of demolition activities. All lamps and thermostats containing mercury will be disposed of off-site at an approved landfill.

2.13 Demolition

The RA Contractor will perform demolition as shown on the Contract Drawings and as described herein. Building demolition will be performed after asbestos abatement and hazardous building material (i.e., lamps and thermostats containing mercury) removal. The RA Contractor will demolish and remove the existing one-story buildings on Lots 33, 42, 44, 46 (Flat Fix), and 48 to the top of building slabs. The two-story building with basement on Lot 46 (deli) will be demolished, leaving only the perimeter basement walls and floor in place. The interior basement wood-framed wall separating the two rooms will be demolished. Bolts secured to concrete slabs or pavement and all metal columns and supports will be cut flush to the slab/pavement surface to leave slabs and pavement intact. Prior to demolition of the two-story building on Lot 46, the RA Contractor will either provide support or backfill the basement to protect the perimeter basement walls from collapsing during demolition.

Building information is provided in Contract Drawing Sheet C-3 and is obtained from a structural inspection performed in February 2017 (Appendix C) with the objective of determining the feasibility of over excavating additional contaminated soil within the building footprint to provide additional shielding. Detailed structural information for the buildings was not obtained during this property visit.

The following is a recommended demolition sequence:

- Demolish the buildings on Lot 33
- Clear trees as discussed in Section 2.11
- Demolish the buildings on Lot 48 and Lot 46
- Demolish the building on Lot 42, Building B, as indicated on the Contract Drawing
- Demolish the remaining buildings

The common wall between Lots 42 and 44, (as part of the original kiln/vat room) known to have radioactivity level greater than 50 pCi/g, will be segregated from other building materials and stored separately for waste characterization and disposal. In addition, nonporous material (e.g.,



structural steel, scrap metal) will be segregated from demolition debris for LBP removal (if necessary), decontamination, alpha/beta radiation scanning, and wipe sampling as described in Section 2.15.3. Nonporous material meeting the alpha/beta release criteria will be sent to an approved recycling facility.

2.14 Waste Characterization, Handling and Off-site Disposal

Waste handling, including classification, segregation, and off-site disposal, is a major component of the site remediation. Based on existing investigation data, demolition debris can be classified as either radioactive waste, nonhazardous solid waste, or recyclable material based on characterization results.

As part of the 95% RD cost estimate (CDM Smith 2018), the two disposal options listed below were evaluated alongside detailed in-situ and ex-situ waste characterization methods that could be used to segregate unimpacted material (non-hazardous waste) from radioactively contaminated material. As part of this evaluation, materials with radioactivity levels below the upper tolerance levels for background in solids developed during the RI (1.2 pCi/g for Th-232 and 0.9 pCi/g for Ra-226) were considered unimpacted material.

- Option 1 This option considers all building demolition materials, except nonporous salvageable material, to be radioactive waste.
- Option 2 This option considers all building demolition materials, except nonporous material, to be one of two waste types—nonhazardous or radioactive —based on the waste characterization results and disposal facility acceptance criteria.

The Government evaluated the disposal options as a part of the 95% RD review and selected Option 1 as the preferred waste disposal option. The basis for selecting Option 1 is listed below:

- There was not a significant cost difference between two options.
- Rigorous waste characterization will not be required to segregate non-hazardous material.
- Option 1 has a shorter construction duration.

2.14.1 Demolition Debris to be Disposed of as Radioactive Waste

All demolition debris, excluding nonporous salvageable material, will be disposed of as radioactive waste. Nonporous material will be recycled. Radioactive waste can be disposed of at an NRC-licensed or NRC agreement state-licensed facility, such as EnergySolutions Clive Operations and Waste Control Specialists, LLC, or at a non-NRC-licensed/Subtitle C landfill that accepts radioactive waste such as U.S. Ecology in Grandview, Idaho.

The RA Contractor will identify potential waste disposal and recycling facilities and use the disposal facility's waste acceptance criteria (WAC) to develop characterization protocols meeting the respective WACs. For large container (25 cubic yards or greater) hauling, the average load concentration is not expected to exceed the disposal limits of the radioactive waste disposal facility's WAC.



A waste profile form will be completed, submitted, and approved by the radioactive waste disposal facility prior to any shipment to their facility. U.S. Ecology does not specifically require a waste analysis by an independent laboratory; however, it is recommended that historical data or analysis performed by the RA Contractor be submitted with the waste profile forms. This analysis will apply to all future loads shipped for disposal at the U.S. Ecology facility.

U.S. Ecology will review the waste profile form and perform a MicroShield analysis to determine the likely dose rate associated with the load. U.S. Ecology will utilize that dose rate to determine if each incoming load meets the original accepted profile. Consequently, the RA Contractor will also use that dose rate as a release limit or action level before releasing containers for shipment. The Th-232 and U-238 activity levels will be used to determine the proper United States Department of Transportation (DOT) shipping classification.

Due to the manner in which U.S. Ecology accepts waste loads at the Grandview disposal facility, the RA Contractor would have the alternative of: (1) using the maximum expected concentrations to determine the DOT designation and complete the manifest, labeling, and placarding accordingly, or (2) using an In Situ Object Counting Systems (ISOCS), or equivalent, to determine each load's contents and apply the appropriate DOT designation to each individual load. The first alternative is preferred because it is the less expensive option in terms of labor and materials. If alternative 1 is used, the time needed to perform an ISOCS analysis and subsequent review and approval of the data will be eliminated.

ISOCS for analysis of container contents

At a minimum, ISOCS "shots" of each container will consist of the following:

- 1. Mounting of a shielded ISOCS on a forklift for movement around the exterior of the container.
- 1. The ISOCS will be used at a minimum of four locations (with eight recommended) around the container to analyze the container contents. For eight locations analysis, the sides are divided into three segments, and midpoints of each of those segments are analyzed. Additionally, an analysis is made at each end of the container. For four locations analysis, the midpoint of each side and end is analyzed.
- 2. Analysis will take a minimum of 4 minutes at each location to quantify the radioactivity of the container material.

The RA Contractor's analytical algorithm will consider the density of the load, the air space, thickness and type of container material, and the position of each analyzed location. The ISOCS measurements will provide concentration results for actinium-228 (Ac-228) and Ra-226. Because it is assumed that Ac-228 is in proximate equilibrium with its respective decay chain parent (Th-232), the activity of Ac-228 is assigned to Th-232.

QA (confirmation) samples will be collected from approximately 20% of the loads to be shipped and analyzed by an independent laboratory to confirm the ISOCS analysis methodology or as required by the disposal facility. Those samples will be collected via methods described in American Society for Testing and Materials (ASTM) D6044, Standard Guide for Representative



Sampling for Management of Waste and Contaminated Media, and in accordance with the RA Contractor's approved UFP-QAPP.

During clearing activities, characterization samples will be collected of the vegetation to determine levels of radioactivity. Those samples will determine if vegetation will be disposed of as radioactive waste or recycled. CDM Smith assumes that the material will be sent off-site for recycling.

CDM Smith estimates that 976 tons of radioactive building materials will require disposal and 437 tons of nonporous material (i.e., structural steel, scrap metal, and glass,) could be recycled at an approved recycling facility. A calculation of the estimated quantities of demolition debris is presented in Appendix D. Table 2-3 presents the different waste types to be generated from the RA activities.

2.14.2 Recycling

It is expected that nonporous material (i.e., structural steel, scrap metal, and glass) will be recycled. LBP abatement will be performed on nonporous materials containing LBP to recycle the materials. If radioactive contamination is present on nonporous materials, the contamination would mostly likely only be surficial. In those cases, the RA Contractor would use the provisions in NUREG 1575, the Multi-Agency Radiation Survey and Assessment of Materials and Equipment manual (MARSAME) to develop a Waste Management and Transportation Plan to allow for clearance of the material for recycling. The plan will likely involve the following process:

- 1. Scan of the material.
- 2. If the scan does not show elevated surface activity, wipes of the surface will be taken at the frequency specified in the RA Contractor's Waste Management and Transportation Plan. It is expected that a minimum of 10% of the surface will be wiped.
- 3. If the scan shows elevated activities, a wipe will be collected at those locations to determine if the contamination is removable and the level of that removable contamination.
- 4. If the contamination is removable, the material will be decontaminated.
 - a. Following decontamination, another scan will be performed, and a wipe will be collected to verify decontamination.
- 5. If the contamination is not removable, the nonporous material will be disposed of as radioactive waste.

2.14.3 Transportation

The RA Contractor is expected to meet all DOT requirements, including those within Title 49, Subtitle B, Chapter I, Subchapter A. No waste will be transported off the site until review and determination has been made as to its acceptability for disposal at the chosen waste disposal facility and its DOT shipping classification status.

All trucks leaving the site will be surveyed and inspected prior to release from the site. At a minimum, the inspection must meet the criteria specified on DD Form 626, Motor Vehicle



Inspection (Transporting Hazardous Materials), or contractor equivalent. If the shipment is designated as low specific activity (LSA-I) based on the characterization data, placards will need to be affixed to the front, back, and sides of the container. If the material is exempt, the placards are not required.

Surveys will consist of the following:

- Wipe tests of the exterior of the container in accordance with DOT standards: The wipes are 300 cm² (rather than the traditional 100 cm² wipes used in radiological-licensed operations). The wipe results are compared to the allowable limits in 49 CFR 173.443. The limits are effectively 240 dpm/100 cm² removable alpha and 2,400 dpm/100 cm² removable beta.
- External radiation surveys of the truck and container using a Ludlum 19 μ R meter or meter with equivalent range: The surveys will be completed at distance of 1 foot from the truck and container surface. Normally, the survey results would be compared with the limits in 49 CFR 173.441, but in this case, the exposure rate of concern would be that developed by U.S. Ecology for their waste acceptance profile of the WACC material. It is likely this exposure rate value will be between 100 and 200 μ R/h and approximately one order of magnitude less than the radioactive hazardous material designation limits identified in 49 CFR 173.441.

The shipping manifest will be reviewed to ensure the entries meet the shipping paper requirements of 49 CFR 173 and match the radionuclide values assigned to the container's load. A copy of the final truck/container survey will accompany the shipping papers.

In several cases, the container load may have radionuclide concentrations less than the 49 CFR 173 radioactive hazardous material designation limits and as such are exempt from inspection, survey, and hazardous material shipping papers. A bill of lading will still be required, and the information on that lading will be approximate to that of a shipping paper, except the hazardous material designations will not be listed.

2.15 Traffic Control and Haul Routes

Because the work will be performed adjacent to a street and sidewalk, the RA Contractor will provide control and protection of traffic in accordance with the New York City Traffic Rules and Regulations. Traffic control to be implemented includes the use of barriers, signals, signs, flag people, or other devices, equipment, or personnel at the entrance and exit of the WACC property.

All material will be hauled off-site for disposal. The RA Contractor will use the NYC Truck Route Network (NYCDOT Traffic Rules, Title 34, Chapter 4 Rules of the City of New York), which includes designated roadways to be used for local and through truck traffic. Cooper Avenue/Cooper Street located adjacent to the west side of the WACC property is a designated local truck route. This route leads to Atlantic Avenue, which is a designated through-truck route. The operator of the truck is restricted to drive only on Atlantic Avenue until reaching the Brooklyn-Queens Expressway or the Van Wyck Expressway and exiting Brooklyn (Kings County). The truck operator can only drive on a non-designated street for the purpose of arriving at the WACC property (i.e., driving on Irving Avenue or Moffat Street).



2.16 Backfilling

WACC property areas below grade, including the basement at Lot 46 and the sump in Lot 33, will be backfilled to the surrounding grade elevation to prevent open pools of water forming in these two areas and to remove the hazard of an open hole. Backfill will also be placed to prevent erosion and runoff of soil and exposure to the contaminated soil in between the concrete slabs on Lot 33 and Lot 42 and areas of exposed soil in the former rail spur area. Backfill material will be crushed stone less than 2 inches in size.

Crushed stone and sand brought to the site will be free of frozen material, rubbish, or other unsuitable materials. Crushed stone and sand will be tested to ensure it is free from chemical contamination as defined in DER-10, Residential Soil Cleanup Objectives, and radiological contamination as defined in Specification Section 01 35 45. Approximately 591 cubic yards of crushed stone will be required to backfill basement, sump, and other open or disturbed areas (Appendix E). Based on the approximate crushed stone volume, it is anticipated that one sample will be collected and sent to an off-site laboratory for analysis. No backfill will be brought to the site without written approval from the Contracting Officer.

Before backfilling the basement, geotextile will be placed on the floor and walls of the basement of Lot 46 to separate the contaminated floor/wall from clean crushed stone, which is to be used as a backfill for the next phase of remediation at the site. Compacted crushed stone will be mounded to provide positive surface drainage. Geotextile material will be placed over the crushed stone and a 4-inch layer of sand placed on the geotextile to prevent damage to the geomembrane. Geomembrane will be placed over the sand layer on the mounded stone and covered with a minimum of 4 inches of sand to protect the top of the geomembrane. The geomembrane will be secured at the edges of the backfill area to prevent the geomembrane from being moved by the wind. A 3-inch layer of crushed stone will then be placed over the sand layer.

The geotextile material will generally meet the requirements for a nonwoven monofilament geotextile with a high permeability to allow drainage through the geotextile and basement floor. The geomembrane material will generally meet the requirements for an impermeable high-density polyethylene membrane.

2.17 Site Restoration

The RA Contractor will perform final site restoration as shown on Contract Drawing Sheet C-4. Site restoration will include the following activities:

- Installation of an exclusion fence around the perimeter of the WACC property
- Filling the basement on Lot 46 (including the sump hole) and the sump hole in Lot 33 with crushed stone as discussed in Section 2.17
- Repairing the concrete sidewalk where concrete steps and the cellar door entrance for the Lot 46 building were located
- Filling any holes in the concrete slabs and asphalt pavement remaining on the property with crushed stone



- Placing and grading crushed stone over any areas of exposed soil that may have been displaced due to equipment traffic during remedial construction activities
- Paving roadways along Irving and Cooper Avenues, as necessary, that may have been damaged due to heavy equipment movement or during utility disconnection

The exclusion fence will meet the requirements of the NYCDOB construction code for fencing and will consist of an 8-foot-tall chain link fence. The fence will utilize the two existing gates. Warning signs will be posted on the fence.

Concrete sidewalk repair will meet NYCDOT requirements and consist of 4-inch-thick concrete sidewalk with a 6-inch compacted aggregate base.

2.18 Green Remediation

Green remediation is the practice of considering all environmental effects of the implementation of a remedy and incorporating options to maximize the net environmental benefit of cleanup actions. EPA strives for cleanup programs that:

- Use natural resources and energy efficiently
- Reduce negative impacts on the environment
- Minimize or eliminate pollution at its source
- Reduce waste and reuse materials to the maximum extent possible

The RA Contractor will be required to incorporate green remediation practices into the remedial design and construction whenever feasible in accordance with the EPA Region 2 "Clean & Green" Policy, issued on March 17, 2009 and its update issued on March 11, 2010. Green remediation strategies will be implemented to reduce direct and indirect greenhouse gas and other emissions, increase energy efficiency, conserve and efficiently manage resources and materials, reduce waste, and increase reuse of materials.

CDM Smith performed a preliminary evaluation of green remediation practices applicable to this work assignment. Applicable green practices that will be required to be implemented by the RA Contractor during construction activities are included in Specification Section 01 81 30 and described below. The RA Contractor will be required to supply documentation and records supporting the green remediation practices implemented (i.e., disposal certificates, utility receipts) in accordance with the RD specifications.

2.18.1 Incorporation of Clean Diesel Fuel and Technology

The majority of fuel that will be used during construction activities is associated with heavy construction equipment that will be used for demolition, loading, and backfill work. The RA Contractor and subcontractors will be required to certify that only ultra-low sulfur diesel is used on the project, which will improve the quality of the vehicle exhaust. In addition, vehicle idling will not be allowed for longer than 5 minutes.



2.18.2 Material Reuse, Reduction, and Recycling

Material reuse, reduction, and recycling minimizes impacts on natural resources and reduces the production of waste. Waste reduction minimizes environmental impacts by limiting the amount of land required for waste disposal and minimizing consumption of fossil fuels and generation of air emissions associated with transport of the waste. Material reuse, reduction, and recycling practices at the site will include the items detailed below.

- Demolished nonporous building materials (e.g., steel, scrap metal, lead pipe) will be decontaminated and recycled at an approved recycling facility.
- One hundred percent of the copy papers, file folders, and paper office supplies will be required to come from recycled sources. Required recovered materials content will be as recommended by EPA's Comprehensive Procurement Guidelines.

2.18.3 Sustainable Practices

Sustainable site practices minimize degradation of ecosystems and promote good stormwater management. The sustainable practices listed below are associated with the site activities.

- All construction activities will be performed on a previously developed site. No destruction
 of habitat will be required to complete the remedial construction activities.
- No new impervious material will be generated as part of site activities, which can contribute to localized flooding.
- Soil erosion and sediment control measures will be implemented for the duration of site construction. Silt fences will be installed along WACC property boundaries to reduce the amount of sediment leaving the property, which could adversely impact the storm sewers and downgradient water bodies.
- Dust control will be implemented during demolition activities to prevent adverse impacts to air quality.

2.19 Demobilization

After final inspection is completed, the RA Contractor will initiate demobilization activities. This will include, but is not limited to, removal of all trailers, equipment, materials, and personal protective equipment (PPE).

2.20 Cost Estimate

The 95% and revised 95% design cost estimates were submitted on June 27 and August 8, 2018, respectively for review by USACE-Kansas City District. The Final Construction Cost Estimate will be submitted under a separate cover to USACE-Kansas City District. The construction cost estimate will be prepared using Micro-Computer Aided Cost Estimating System, Second Generation (MII), Version 4.4. The submittal will include associated backup detailing the cost assumptions used for the cost estimate.



Section 3

Construction Quality Assurance/Quality Control

This section describes the procedures that will be implemented to provide QA/QC during site preparation, demolition, waste characterization, transportation and disposal, and site restoration. The intent of the construction QA/QC is to ensure that all work is completed in accordance with the requirements in the Contract Documents (drawings and specifications) prepared during the RD. Information has been included herein to summarize the various QA/QC measures contained in the contract specifications and to identify the manner in which these QA/QC measures will be implemented and monitored during the course of construction.

3.1 Construction QA/QC Organization

It is the responsibility of all involved parties to ensure that quality is maintained throughout the construction duration. USACE will have the overall responsibility for construction QA/QC. The RA Contractor will be responsible for implementing QC procedures in accordance with the QA program. The RA Contractor also will be required to submit a detailed contractor quality control plan.

The USACE Contracting Officer will be responsible for the following activities:

- Conduct progress meetings on a periodic basis during remediation to address the status of
 project construction, schedule changes, test results, observations and findings, issues of
 noncompliance, change orders, and upcoming activities. The frequency of these meetings
 depends on the environmental significance of site activities and the level of oversight
 required.
- Monitor the construction QA program to ensure that appropriate technical review is completed by qualified representatives.
- Maintain continuous communication with the EPA Remedial Project Manager.

Responsibilities of the Contracting Officer's QA/QC representative are outlined below:

- Review all design documentation, including the design drawings and specifications, shop drawings, plans, and other submittals from the RA Contractor.
- Review (as required) modifications to the design drawings and specifications as they occur during construction.
- Provide assistance in determining whether the construction has been completed in general conformance with the drawings and specifications.
- Maintain contact with the remedial construction and operations contractor, herein referred to as the "RA Contractor," regarding conformance with the QA/QC requirements.



- Provide assistance to the Contracting Officer's resident engineering representative in the review and interpretation of field and laboratory testing results.
- Review all field and laboratory QA/QC testing and inspection results for conformance with the specifications and RD report. Provide an interpretation of data to determine areas that are in conformance and those that are in nonconformance with these documents. Determine areas that require reworking and/or repair.
- Perform periodic site visits to review construction progress and QA/QC procedures.
- Ensure that the Contracting Officer's resident engineering representative is notified of any noted deficiencies in QC testing results or procedures.
- Coordinate with the RA Contractor and all lower-tier subcontractors to ensure compliance with the QA/QC requirements.
- Maintain a continuous record of any changes or modifications to the design drawings and specifications.

USACE will provide resident engineering and field inspection representatives who have knowledge of and experience with the construction activities on-site. The inspection representatives will assist the resident engineering representative with the responsibilities outlined below.

- Record any on-site activities that could result in noncompliance with the design documents and report these activities to the Contracting Officer's QA/QC representative.
- Document field and laboratory testing as required by the specifications.
- Observe construction materials delivered to the site, such as backfill and geotextile, to determine general conformance with material specifications.
- Observe and record procedures used for site preparation, demolition, waste characterization, transportation and disposal, and site restoration, and record any deficiencies in these activities.
- Prepare daily construction logs and a daily quality control report.
- Serve as the daily contact person and maintain routine contact with the Contracting Officer and the RA Contractor regarding conformance with QC measures.

The RA Contractor will identify a Contractor Quality Control (CQC) Manager who will be responsible for overall management of CQC and have the authority to act in CQC matters for all features of work. The CQC Manager will have the roles outlined below.

- Maintain an on-site supervisory presence during construction, with no duties other than QC.
- Maintain a continuous line of communication with the Contracting Officer's QA/QC representative to identify and discuss field issues as they arise.



- Use the USACE-furnished quality control system software to record, maintain, and submit information throughout the contract period.
- Provide technical submittals to confirm that the contract specifications are being met.
- Ensure that the QA/QC requirements of the specifications (e.g., testing, inspection) are being met.
- Identify potential design/construction issues as early as possible to avoid impact to the project performance and/or construction schedule.

3.2 Construction QA/QC Activities

The Contract Documents play an important role in the implementation and monitoring of QA/QC activities. The contents of these documents establish the QA/QC elements of activities occurring before, during, and after the construction. Specific to QA/QC, the specifications may, depending on the given component of construction, specify any or all the following items.

- Performance standards or operating conditions to assist the RA Contractor in the selection and purchase of equipment
- Required construction materials
- Applicable codes, standards, and specifications to govern material and workmanship quality
- Information to be submitted for technical review
- Coordination of work activities for all elements of construction
- Manufacturer or field testing requirements
- Performance guarantees
- Workmanship/equipment warranties

The specifications provide the framework for QA/QC measures by identifying the appropriate equipment and materials to be utilized, indicating acceptable construction practices, requiring on-site and off-site testing, and specifying performance and workmanship warranties. To gauge compliance with the requirements of the Contract Documents, three phases of control (preparatory, initial, and follow-up) are performed for each definable feature of work, and QA/QC activities, such as review of technical submittals and material/equipment testing and inspection, are performed. These activities are further discussed below.

3.2.1 Review of Technical Submittals

For certain elements of construction, the specifications require the RA Contractor to prepare technical documents and submit this information to the Contracting Officer for review. The objective of these requirements is to monitor the RA Contractor's understanding of the design and prevent any misinterpretation of the specifications that may otherwise impact the design



objectives or construction schedule. The submittal of technical documents encompasses many elements of construction activity. Required submittals may include planning documents, product specifications, certifications, and test results.

The technical submittal review process is an essential activity for monitoring QA/QC before construction begins. The submittal of technical documents signifies that all quantities, dimensions, field construction criteria, materials, model numbers, and other pertinent information have been determined and verified by the RA Contractor. It also ensures that the RA Contractor incorporates the specifications and the design drawings into the construction activities.

The Contracting Officer's resident engineering representative will review the technical documents to determine general compliance with the design drawings and specifications. Submitted data are reviewed and assigned a rating as outlined below.

- "A Approved as submitted" if no objections are observed or comments made.
- "B Approved, except as noted. Resubmission not required" if minor objections, comments, or additions are made but resubmittal is not considered necessary.
- "C Approved, except as noted. Resubmission required" if the objections, comments or additions are extensive. The RA Contractor would be required to resubmit the items after correction.
- "D Will be returned by separate correspondence."
- "E Disapproved (see attached)" if the submittal under consideration is not acceptable or when the data submitted are not sufficiently complete to establish compliance with the design drawings and specifications.
- "F Receipt Acknowledged" all submittal listed "For Information Only" will require this code.
- "FX Receipt Acknowledged, does not comply as noted with contract requirements;" all submittals listed "For Information Only" requiring re-submittal will require this code.

3.2.2 Field Inspection and Testing of Materials, Equipment, and Installation

In addition to the technical data required by the RA Contractor prior to construction activities, several requirements exist in the contract specifications for specific testing and inspection of equipment and materials. This testing and/or inspection will be required on-site once the component or material has been installed or placed. Testing of select material and equipment provides additional assurance that the component has been properly manufactured, installed, and/or coordinated with other components of construction. Documentation of testing/inspection required by the contract specifications includes, but is not limited to, the following items.

- Inspection of material upon delivery and prior to installation
- Sieve, chemical, and radiological analysis of imported materials
- Calibration of field testing instrumentation



 Inspection of site works, including fencing, soil erosion and sediment controls, basement walls support, backfill, and final site restoration

Testing and inspection requirements in the contract specifications are discussed further in the following sections. The completion inspections below will be conducted at two stages during remedial action. The first set of completion inspections will be conducted after all pre-demolition site construction work is complete, including construction of erosion and stormwater controls and temporary fencing and facilities. The second set of inspections will be conducted after the site restoration activities are completed and prior to demobilization.

3.2.2.1 Pre-Final Inspection

The pre-final inspection will be performed by EPA, USACE, and the RA Contractor. This inspection will be performed over the course of a 1-day period and will include a visual inspection of the work completed at the site to demonstrate that the project has met design criteria detailed in the contract specifications.

For this inspection, a list of incomplete work items ("Pre-Final Punch List") will be developed by the Contracting Officer and submitted to the RA Contractor. The RA Contractor is responsible for making all repairs, replacements, and/or adjustments to meet the required performance criteria. Any major incomplete work items identified by the Contracting Officer will be addressed immediately. If necessary, follow-up inspections will be performed to verify completion of major work items.

3.2.2.2 Final Inspection

The final inspection will be conducted the EPA, USACE, and the RA Contractor after all punch list items identified during the pre-final inspection have been addressed. The inspection will include a visual inspection of all work. Any incomplete work items identified by the Contracting Officer will be corrected by the RA Contractor immediately.



This page intentionally left blank.



Section 4

Regulations, Standards, and Construction Codes

All RD and RA activities will comply with all federal, state, and local government regulations. The following regulatory requirements will be taken into consideration during the design and remediation activities of the project.

4.1 General Regulations

General regulations to be taken into consideration include:

- Comprehensive Environmental Response, Compensation, and Liability Act
- OSHA
- Clean Water Act
- Clean Air Act
- National Environmental Policy Act
- RCRA

4.2 Health and Safety

Health and safety requirements to be taken into consideration include:

American Conference of Governmental Industrial Hygienists

 Threshold limit values for Chemical Substances and Physical Agents and Biological Exposure Indices

American National Standards Institute (ANSI) and American Society of Safety Engineers (ASSE)

	ANSI/ASSE A10.6	Safety and Health Program Requirements for Demolition Operations
•	ANSI Z41.1	Men's Safety Toe Footwear
•	ANSI Z87.1	Practice for Occupational and Educational Eye and Face Protection
•	ANSI Z88.2	Standard Practice for Respiratory Protection
•	ANSI Z89.1	Safety Requirements for Industrial Head Protection
•	ANSI Z358.1	Emergency Eyewash and Shower Equipment
	ANSI Z590.3	Prevention through Design



OSHA

- 29 CFR 1904 Recording and Reporting Occupational Injuries and Illnesses
- 29 CFR 1910 Occupational Safety and Health Standards (General Industry)
 - Section 38 Employee Emergency Plans and Fire Prevention Plans
 - Section 95 Noise
 - Section 120 Hazardous Waste Operations and Emergency Response
 - Section 132 General Requirements
 - Section 133 Eye and Face Protection
 - Section 134 Respiratory Protection
 - Section 135 Head Protection
 - Section 136 Foot Protection
 - Section 137 Electrical Protective Equipment
 - Section 146 Permit Required Confined Spaces
 - Section 147 The Control of Hazardous Energy
 - Section 1000 Air Contaminants
 - Section 1096 Ionizing Radiation
 - Subpart I Personal Protection Equipment
- 29 CFR 1926 Safety and Health Regulation for Construction (Construction Industry)
 - Section 21 Safety Training and Education
 - Section 59 Hazard Communication
 - Section 65 Hazardous Waste Operations and Emergency Response
 - Section 602 Material Handling Equipment
 - Subpart P Excavation
 - Subpart F Fire Protection and Prevention
 - Subpart E Personal Protective and Life Saving Equipment
- 49 CFR 171 General Information, Regulations, and Definitions



 49 CFR 172 Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements

49 CFR 173
 Shippers – General Requirements for Shipments and Packagings

EPA

- Safety and Health Requirements Manual
- National Ambient Air Quality Standards
- Ambient Monitoring Guidelines for Prevention of Significant Deterioration

National Institute for Occupational Safety and Health (NIOSH)

- Publication No. 85-115 Occupational Safety and Health Guidance Manual for Hazardous Waste Site Activities
- Publication No. 2001-145 NIOSH Pocket Guide to Chemical Hazards
- Manual of Analytical Methods

USACE

- Engineering Manual (EM) 385-1-1, Safety and Health Requirements Manual
- EM 385-1-80, Radiation Protection Manual
- Engineering Regulation (ER) 385-1-80, Ionizing Radiation Protection
- ER 385-1-92, Safety and Occupational Health Requirements for Hazardous, Toxic and Radioactive Waste (HTRW) Activities
- EM 1110-35-1, Management Guidelines for Working with Radioactive and Mixed Waste

New York City Administrative Code (NYCAC)

24 NYCAC 1 Air Pollution Control

New York Codes, Rules, and Regulations (NYCRR)

•	12 NYCRR 38	New York State Department of Labor Ionizing Radiation Protection
•	10 NYCRR 16	New York State Department of Health Ionizing Radiation
•	10 NYCRR 73	New York State Department of Health regulations for the training of workers in the asbestos abatement industry and regulations concerning asbestos safety training providers



York City Building Code

Chapter 33 Safeguards during Construction or Demolition

Others

- Federal Acquisition Regulations (FAR) Accident Prevention FAR Clause 52.236.13
- Other state and local regulations pertaining to health and safety

4.3 Chemical/Radiological Quality Management Plan

USACE

- EM-200-1-6, Chemical Quality Assurance for HTRW projects
- ER 1110-1-263, Engineering and Design Chemical and Radiological Data Quality Management for Hazardous, Toxic, Radioactive Waste Remedial Activities

U.S. Department of Defense (DOD)

DOD Quality Systems Manual for Environmental Laboratories

EPA

- EPA SW-846 Test Methods for Evaluating Solid Waste: Physical/Chemical Method (Update IV)
- EPA 505-B-04-900A Intergovernmental Data Quality Task Force, Uniform Federal Policy for Quality Assurance Project Plans Part 1 for Evaluating, Assessing, and Documenting Environmental Data Collection and Use Programs
- EPA 505-B-04-900B Intergovernmental Data Quality Task Force, Uniform Federal Policy for Quality Assurance Project Plans Part 2B for Quality Assurance/Quality Control Compendium: Minimum QA/QC Activities
- EPA 505-B-04-900C Intergovernmental Data Quality Task Force, Uniform Federal Policy for Quality Assurance Project Plans Part 2A for Workbook for UFP for QAPP
- EPA 402-B-04-100A, Multi-Agency Radiological Laboratory Analytical Protocols (MARLAP)
 Manual

CFR

40 CFR 261 Identification and Listing of Hazardous Waste

4.4 Demolition/Backfill

OSHA

 OSHA 2207, Subpart T, Subsection 1926.850, Construction Industry, Construction Standards, U.S. Department of Labor



 OSHA 2207, Subpart P, Subsection 1926.650 through 1926.652, Construction Industry, Construction Standards, U.S. Department of Labor

NYCAC

24 NYCAC 2 Noise Control

NYSDEC

DER-10 Technical Guidance for Site Investigation and Remediation

NYCRR

10 NYCRR 375 Environmental Remediation Programs

12 NYCRR 56
 New York State Department of Labor regulations relating to the

hazards to public safety and health during the removal, encapsulation, enclosure, repair, or the disturbance of friable and non-friable asbestos, or any handling of asbestos material that may result in the

release of asbestos fiber

 NYCRR Title X, Part 67-2 New York State regulations for environmental assessment and abatement of lead

NYCDEP

 15 Rules if the City of New York (RCNY) 1 Asbestos Control Program: Asbestos Rules and Regulations

New York City Housing Preservation and Development

Local Law 1 of 2004 Childhood Lead Poisoning Prevention Act

CFR

40 CFR 261 Identification and Listing of Hazardous Waste

40 CFR 763 Regulations related to the National Emission Standards for Asbestos

<u>Other</u>

Noise Pollution Code, EPA Ordinance 89-38

4.5 Transportation and Disposal

CFR

40 CFR 262 Regulations for Hazardous Waste Generators

40 CFR 263 Regulations for Hazardous Waste Transporters

49 CFR 172 Hazardous Materials Table, Special Provisions, Hazardous Materials



Communications, Emergency Response Information, and Training
Requirements

49 CFR 173
 Shippers – General Requirements for Shipments and Packaging

49 CFR 302 Designation, Reportable Quantities, and Notification

NYCRR

- 6 NYCRR Part 360 Solid Waste Management Facilities General Requirements
- 6 NYCRR Part 364 Waste Transporter Permits regulations including waste transportation, transport permits, and asbestos transportation tracking

4.6 Construction Codes, Standards and Regulations

4.6.1 General Construction

- ASTM. Applicable ASTM standards will be referred to in the project's civil/structural specifications.
- NYCDOB Building Code
- NYCDOT Department of Transportation
- NYCDOT Standard Highway Specifications



Section 5

Required Permits and Approvals

The permit equivalencies and approvals identified as being required for remedial activities at the WACC property are summarized below. Permit equivalents will be filed with the City of New York. Electrical and gas service disconnection is noted in Section 2 of this document.

5.1 Introduction

The following permit equivalencies and approvals have been identified as being required for this phase of the RA work at the WACC property. A brief description of each permit equivalency or approval is provided below. Table 5-1 provides a list of agencies, the required permit equivalencies/approvals, and websites for application forms, requirements and guidance documents. Appendix F provides the permit applications.

5.2 New York City Department of Transportation

5.2.1 Occupation of Sidewalks and Roads

Permits for work in sidewalks and to access utilities in public streets as well as staging, storing equipment, or placing a fence on sidewalks/roadways/right of ways require a permit. Application for permits under NYCDOT authority can be applied for online. Insurance requirements are noted on the website (http://www.nycstreets.net/public/signin/index). Work zone traffic protection plans would be provided in support of the application material submitted. Permits are issued for 90-day duration and must be renewed for the duration of the work.

5.3 New York City Department of Buildings

Application submitted to the NYCDOB may include any or all the following application forms:

- PW1: Plan/Work Application
- PW1B: Schedule B Plumbing, Sprinkler, Standpipe
- PW2: Work Permit Application
- PW3: Cost Affidavit
- PW4: Application for Certification of Compliance Equipment
- TR1: Technical Report Statement of Responsibility
- B Form 2A: Application for Inspection Prior to Demolition
- BEST Appointment Request Form
- DS1: Demolition Submittal Certification Form



PW7: Certification of Occupancy/Letter of Completion Folder Review Request

NYCDOB application forms are electronically filed using eFiling or DOB NOW: Build. Both filing sites are located on the NYCDOB home page. Users must register to access this feature. Instructions are provided on the NYCDOB website. Insurance requirements apply to the RA Contractor who is granted the work, demolition, or plumbing permit.

Supporting plans must meet NYCDOB requirements for size, border, and content. The use of an expeditor may prove useful for obtaining approval in a timely manner.

5.4 New York City Department of Environmental Protection 5.4.1 Water and Sewer Line Disconnection

The required forms must be completed by a NYC licensed plumber. The NYCDOT permit (Section 5.2) to allow for work to be done on the sidewalk and within the roadway must be approved prior to the issuance of the disconnection permits as the sidewalk and street must be opened to disconnect the service lines.

5.4.2 Asbestos Abatement

As the asbestos investigation conducted for the buildings to be demolished estimated more than 10 square feet or 25 linear feet of ACM will be disturbed by the building demolition activities, the work is considered an 'Asbestos Project,' requiring access to the Asbestos Reporting and Tracking System (ARTS) and completing Form ACP7. All asbestos activity permits are filed online through the ARTS eFile system (https://a826-

web01.nyc.gov/acpefile/Login.aspx?ReturnUrl=%2facpefile%2fACP7Home.aspx). Pre-abatement investigation is required to be completed by an NYCDEP-certified inspector. Certification by NYCDEP-Bureau of Environmental Control (BEC) of completion of abatement work is required prior to NYCDOB issuance of a work permit. A variance may be applied for using ACP9. The abatement work is to be completed prior to the demolition or other work within a structure. A variance to this requirement may be applied for online using ARTS at the same time ACP7 is submitted. A meeting to review the variance request is held at NYCDEP's office in Long Island City. The need for the development of a work place safety plan may be required by NYCDEP-BEC as a condition of an asbestos work permit.



Section 6

Health and Safety Program

6.1 Site Description and Contamination Characterization

A site description, including location, approximate size, past uses, and summary of contamination characterization data are included in Section 1.

6.2 Hazard Assessment and Risk Analysis

CDM Smith employed a systematic method to assess hazards, risks, and mitigating controls applicable to this RD, as well as potential HTRW cleanup activities. There are several chemical and physical hazards that are associated with the remedial activities to be performed at the WACC property. To ensure that these hazards are adequately evaluated, the RA Contractor will be required to develop an APP, which will include a site safety and health plan (SSHP). The APP will be submitted to USACE for approval prior to the beginning of the field activities. The APP/SSHP will be developed and implemented by the RA Contractor's Safety and Health Manager (SHM) in accordance with EM 385-1-1, ER 385-1-92, and all relevant OSHA requirements, as indicated in Specification Section 01 35 29. The APP and SSHP should not repeat language or requirements. The document must be usable in the field so should be as concise as possible and repeated language and requirements lead to confusion and a document too large to be usable.

Potential exposures to workers involved with the remedial activities can be summarized as follows:

- Direct contact with contaminated soil, groundwater, and biological agents
- Direct exposure to gamma emissions from building and soil radiological contaminants
- Inhalation of radioactive particulates or thoron/radon and their respective decay progeny
- Inhalation or ingestion of metal, asbestos, and organic particulates
- Construction safety issues such as fall protection; slips, trips and falls; equipment; machinery; heat and cold stress; and hearing protection

In addition to describing how exposure levels will be maintained below the maximum permissible concentrations (as prescribed by OSHA), the APP/SSHP will also address the health and safety hazards associated with each site task and operation to be performed during the RA. The following are anticipated tasks/operations:

- Mobilization
- Site preparation (temporary fencing, well decommissioning, construction of staging area,)
- Disconnection and abandonment of underground utilities



- Excavation support system of deli basement walls, if necessary
- Lamps and thermostats removal
- Asbestos abatement
- Building demolition and segregation
- Tree clearing
- Off-site transportation and disposal of demolition debris
- Backfilling of areas below ground surface
- Site restoration
- Decontamination of tools and equipment
- Demobilization

6.3 Staff Organization, Qualifications, and Responsibilities

The plans and specifications will require that a SHM, meeting the qualification and experience requirements detailed in Specification Section 01 35 29, develop, implement, and oversee the RA Contractor's H&S program and the APP/SSHP. The SHM will be required to sign and date the APP/SSHP. An experienced Site Safety and Health Officer will be required to implement and enforce the H&S program and the APP/SSHP elements during the remedial activities. At least two people certified in First Aid/cardiopulmonary resuscitation will be on-site during RA activities. A certified occupational physician will be required to be available for monitoring medical surveillance protocols and review of all examination/test results. The occupational physician performing the exam will be informed of the types of contaminants and their respective levels for the site work.

6.4 Training

All personnel performing on-site work activities will be required to complete the applicable training in compliance with 29 CFR 1910, 29 CFR 1926, 29 CFR 1910.1200 (Hazard Communication), 49 CFR Subpart H, and EM 385-1-1. At a minimum, the following will be required training for all general site workers:

- Forty hours of HTRW health and safety training off-site.
- Eight hours of refresher training annually.
- Three days of actual field experience under the direct supervision of a trained, experienced supervisor.
- Eight hours supervisor's course for all on-site supervisors covering at least the following topics:



- The employer's H&S program
- PPE program
- Spill containment program
- Health hazard monitoring techniques
- Site-specific training covering all elements in the APP/SSHP, including radiation safety training, will be provided to workers before on-site work begins. Site-specific training will be updated as site circumstances warrant.

Individuals involved with shipping hazardous materials and/or hazardous waste will be required to have received the appropriate DOT training as specified in 49 CFR subpart H.

Individuals involved in asbestos abatement will be required to have received the appropriate training and be licensed as specified in 15 RCNY 1. Individuals involved in lead abatement will be required to have received the appropriate training and be licensed as specified in Local Law 1 of 2004.

6.5 Personal Protective Equipment

The RA Contractor will be required to submit a written PPE program in accordance with the requirements of EM 385-1-1, Section 5. The program will provide a detailed description of the minimum PPE required, including the specific materials of construction for each site-specific task/operation based on the hazard/risk analysis performed. Levels of protection will be relevant to site-specific conditions, including potential heat stress and associated PPE safety hazards. The program will also describe the procedures to determine its effectiveness and procedures for onsite fit-testing of respirators and proper cleaning, maintenance, inspection, and storage of all PPE. The RA Contractor will be required to identify the levels of protection required for each site activity in the APP/SSHP. The RA Contractor will perform continuous air monitoring during the demolition and loading of all contaminated materials. The RA Contractor will be required to detail actions necessary for increasing and decreasing levels of protection in the APP/SSHP. It is anticipated that all field activities where contaminants will be disturbed and come into contact with parts of the body other than hands and feet, will be performed in Modified Level D PPE.

6.6 Medical Surveillance

All on-site personnel will be required to participate in a medical surveillance program overseen by a licensed physician certified in occupational medicine. The medical surveillance program will comply with OSHA standards 29 CFR 1910.120 (f) and 29 CFR 1926.65 (f) and the requirements contained in ER 385-1-92. The occupational physician performing the exam will be informed of the types of contaminants and their respective levels for the site work. The RA Contractor will be required to maintain a medical opinion written by the attending physician describing the fitness of individuals to perform site activities. Certification of personnel participation in the medical surveillance program will be included in the APP/SSHP. All personnel medical records will be maintained in accordance with 29 CFR 1910.1020.



6.7 Exposure Monitoring/Air Sampling Program

The RA Contractor will be required to detail the specifics of the program designed to quantify airborne dust, gamma exposure, airborne radioactivity, radioactive particulates, and noise. This program will rely on both direct instrument reading air monitoring and air sampling. The program will be able to assess potential employee exposure in active work areas. The program will describe action levels and include corrective actions. Requirements for evaluation, recordkeeping, and reporting will be consistent with those outlined in ER 385-1-92, Section 9 and EM 385-1-1, Section 6. The exposure monitoring and air sampling program is detailed in Specification Section 01 35 29.

The RA Contractor will also be responsible for monitoring airborne dust and contaminants generated by site activities at the WACC property perimeter fence line as discussed in Section 2.6. The RA Contractor will prepare a CAMP in accordance with Specification Section 01 35 55, Clean Air Act (40 CFR 50), National Emissions Standards for Hazardous Air Pollutants (40 CFR 61), and DER-10 prior to the onset of remedial construction activities. Air concentrations of radionuclides will be continuously monitored at the site perimeter in accordance with the approved CAMP.

6.8 Heat/Cold Stress Monitoring

Details of the heat and cold stress monitoring program will be described in the RA Contractor's APP/SSHP. Monitoring will be based on ambient temperatures, humidity, wind speed, solar radiation, duration and intensity of work, and PPE ensembles. The RA Contractor will be required to comply with the protocols, schedules, and requirements of EM 385-1-1, Section 06.J.

6.9 Standard Operating Procedures, Engineering Controls, and Work Practices

Standard operating procedures, such as site rules/prohibitions, work permit requirements, material handling procedures, drum/container handling procedures, demolition safety, guarding of machinery and equipment, electrical protection, lockout/tagout, fall protection, hazard communication, illumination, sanitation, engineering controls, signs and labels, and contaminated or hazardous material handling and storage, where applicable, will be detailed in the APP/SSHP.

For utility excavation and disconnection, barriers will be established around the excavation area to prevent non-worker entry. A security presence or non-permanent fencing will be established if the excavation must remain open after normal work hours. Excavated materials will be staged within the barricaded/secured area.

Standard trench safety controls required by OSHA will be applied for any excavation work with depths greater than 4 feet. Monitoring of airborne and direct gamma levels during the excavation process will be performed to ensure potential radiological doses for both workers and members of the public remain below design objectives. Dust suppression controls to limit airborne exposure during excavation will be implemented. Personnel and equipment surveys will be conducted to ensure personnel and equipment are free of contamination prior to exiting excavation control area.



6.10 Site Control Measures

Site control measures, such as details regarding work zone delineation, communications, site security, and general site access, will be included in the APP/SSHP. Site delineation and designation will be based on the contamination characterization data and the hazard/risk analysis performed in accordance with ER 385-1-92.

6.11 Personal Hygiene and Decontamination

The specifications detail the necessary facilities and procedures for personal hygiene and decontamination of site personnel. The APP/SSHP will address methods for waste minimization and decontamination of site personnel.

6.12 Equipment Decontamination

The RA Contractor will be required to detail facilities and procedures with respect to decontamination in accordance with EM 385-1-1 and Specification Section 01 35 29.

6.13 Emergency Equipment and First Aid Requirements

At a minimum, occupational physician-approved first aid equipment and supplies, including emergency eyewash and showers, emergency-use respirators, spill control materials and equipment, and fire extinguishers, will be included with the APP/SSHP consistent with the requirements of EM 385-1-1, Section 3. Emergency equipment required to be on-site will have the capacity to respond to project-specific emergencies.

6.14 Emergency Response and Contingency Procedures

The RA Contractor will be required to develop and implement an emergency response plan that complies with the requirements of Specification Section 01 35 29, 29 CFR 1910.120, 29 CFR 1926.65, and EM 385-1-1.

6.15 Accident Prevention

The APP/SSHP will also provide an activity hazard analysis for each project activity. This analysis will explain the hazards associated with each activity and what will be done to mitigate any accident potential. The RA Contractor will be required to conduct daily safety and health inspections to ensure the effectiveness of the APP/SSHP and determine if operations are being conducted in accordance with the APP/SSHP, USACE and OSHA regulations, and contract requirements.

In the event of an accident/incident, the RA Contractor will be required to report to the appropriate authority in accordance with EM 385-1-1. This requirement is included in Specification Section 01 35 29. Within 5 working days of any reportable accident, the RA Contractor will complete and submit the required accident reports.



6.16 Logs, Reports, and Recordkeeping

Details of training records maintenance, daily safety inspection logs, equipment maintenance logs, employee/visitor register, medical opinions, and exposure monitoring logs will be included in the APP/SSHP and will comply with the requirements of ER 385-1-92, Section 9, and EM 385-1-1, Section 33.



Section 7

List of Technical Specifications

Section No. Title

DIVISION 01 - GENERAL REQUIREMENTS

01 11 00	Summary of Work
01 12 00	Pre-Construction and Pre-Work Conferences
01 20 00	Measurement and Payment
01 30 10	Administration Requirements
01 31 19	Project Progress Meetings
01 32 01	Project Schedule
01 32 33	Project Photographs
01 32 34	Videotaping
01 33 00	Submittal Procedures
01 35 29	Health, Safety, and Emergency Response Procedures
01 35 45	Chemical/Radiological Data Quality Control
01 35 55	Community Air Monitoring
01 45 00	Resident Management System Contractor Mode (RMS CM)
01 45 16	Contractor Quality Control
01 50 00	Temporary Construction Facilities and Controls
01 50 10	Security
01 55 26	Traffic Control
01 57 13	Erosion Control and Stormwater Management
01 57 19	Environmental Protection
01 58 13	Signs/Temporary Project Signage
01 78 39	Project Record Documents
01 78 00	Project Closeout
01 81 30	Green Remediation Requirements

DIVISION 02 - EXISTING CONDITIONS

02 40 10	Site Preparation
02 41 00	Demolition
02 81 00	Transportation and Disposal of Materials
02 82 13	Asbestos Abatement
02 84 16	Handling of Lamps and Thermostats Containing Mercury

DIVISION 31 - EARTHWORK

31 00 00 Site Restoration

DIVISION 32 - EXTERIOR IMPROVEMENTS

32 31 13 Fencing



This page intentionally left blank.



Section 8

List of Design Drawings

Sheet No.	Title
<u>General</u>	
G-1	General Notes, Drawing Index, Legend and Symbols
<u>Civil</u>	
C-1	Site Plan
C-2	Site Preparation Plan
C-3	Building Demolition Plan
C-4	Site Restoration
CD-1	Civil Details I



This page intentionally left blank



Section 9

References

Agency for Toxic Substances and Disease Registry (ATSDR). 2014. *Health Consultation*. Former Wolff-Alport Chemical Corporation Site. 1125-1139 Irving Avenue, Queens, New York. January 23.

ATSDR. 2012. *Health Consultation*. Former Wolff-Alport Chemical Corporation Site. 1125-1139 Irving Avenue, Queens, New York. February 29.

CDM Smith. 2017a. *Final Remedial Investigation Report*. Wolff-Alport Chemical Company Superfund Site. Remedial Investigation/Feasibility Study. Ridgewood, Queens, New York. July 3.

CDM Smith. 2017b. *Final Feasibility Study Report*. Wolff-Alport Chemical Company Superfund Site. Remedial Investigation/Feasibility Study. Ridgewood, Queens, New York. July 20.

CDM Smith. 2018. Draft Final Design (95%) Cost Estimate. Wolff-Alport Chemical Company Superfund Site. Remedial Investigation/Feasibility Study. Ridgewood, Queens, New York. June 27.

Department of Defense, Department of Energy, U.S. Environmental Protection Agency (EPA), and Nuclear Regulatory Commission. 2009. *Multi-Agency Radiation Survey and Assessment of Materials and Equipment Manual (MARSAME)*. NUREG-1575, Supp. 1. EPA 402-R-09-001. DOE/HS-0004. January.

Louis Berger and Associates. 2010. *Radiological Scoping Survey for Wolff-Alport Chemical Corporation Site*, 1125-1139 Irving Avenue, Queens, New York 11385. August 23.

New York State Department of Health, New York City Department of Health and Mental Hygiene, and EPA. 2014. *Multi-Agency Former Wolff Alport Chemical Company Neighborhood Radiological Assessment*, July 29-August 5, 2013. March 12.

Nuclear Regulatory Committee. 1974. *Regulatory Guide 1.86*. Termination of Operating Licenses for Nuclear Reactors. June.

Richard Grubb and Associates. 2018. Phase IA Literature Search and Archaeological Sensitivity Assessment, Wolff-Alport Chemical Company Superfund Site Remediation, 1125-1139 Irving Avenue, Ridgewood, Borough of Queens, Queens County, New York. May 2018.

Soren, J. 1978. *Subsurface geology and paleogeography of Queens County, Long Island, NY*: US Geological Survey Water Resources Investigations Open File Report 77-34, 17 p.

United States Environmental Protection Agency (EPA). 2017. – *Record of Decision: Wolff-Alport Chemical Company Superfund Site*, Ridgewood, Queens County, New York. September.

EPA. 2013. Results of measurements associated with the search for radon/thoron potential gas entry points performed in TerraNova company, Primo company buildings located at 1127-1133



Irving Avenue, Public School 384 located at 272 Moffat Street and in building located at 1125 Irving Avenue in Queens and Brooklyn, NY. August 1.

EPA. 1998. Proposed Rule on the Management and Disposal of Lead-Based Paint Debris. 40 CFR Part 745. December 18.

Weston Solutions Inc. 2016. *Radiation Assessment and Action Report*, Former Wolff-Alport Chemical Company Site, Ridgewood, Queens County, New York. January.

Weston Solutions Inc. 2013. Draft Inter-Agency Radiological Perimeter Survey: U.S> Environmental Protection Agency, Region II, New York State Department of Health, and New York City Department of Health and Mental Hygiene – Wolff Alport Site, Revision 1.



Tables

Table 1-1 Building Materials Radiological Gamma Spectroscopy Results Wolff-Alport Chemical Company Site Ridgewood, Queens, New York

						Potassium-40			Radium-226				Thorium-232		
Location	Sample ID	Sample Date	Parent Sample*	Result	CSU (+/-2 s)	MDA	Q	Result	CSU (+/-2 s)	MDA	Q	Result	CSU (+/-2 s)	MDA	Q
Solids Screening Criteria					0.919				1.220						
Building N	laterials														
LOT33	BRICK-02-LOT33	12/17/2015		23.743	3.068	0.976		3.86	1.593	1.67	J	1.754	0.384	0.183	,
LOT33	BRICK-902-LOT33	12/17/2015	BRICK-02-LOT33	22.182	3.137	0.874		3.85	2.149	2.46	J	1.76	0.35	0.352	2
LOT33	CIND-01-LOT33	12/17/2015		2.18	1.14	1.79	J	2.726	1.59	1.86	J	0.579	0.215	0.372	<u>'</u> J
LOT42	BRICK-09-LOT42	12/18/2015		33.469	6.481	4.41	J	21.09	10.986	13.5	J	152.66	9.698	1.6	;
LOT42	CONC-07-LOT42	12/17/2015		12.978	2.782	2.18	J	8.217	6.701	8.15	J	57.643	4.018	0.758	3
LOT42	CONC-08-LOT42	12/18/2015		3.917	0.608	0.191		0.349	0.602	0.705	UJ	0.45	0.115	0.077	$\overline{\Box}$
LOT44	BRICK-06-LOT44	12/17/2015		32.95	6.769	9.2	J	44.219	16.906	21.1	J	415.17	25.721	2.73	3
LOT46	BRICK-03-LOT46	12/17/2015		9.781	1.986	1.93	J	6.619	2.855	3.73	J	7.784	0.813	0.332	<u>'</u> J
LOT46	IBEAM-05-LOT46	12/17/2015		0.479	0.302	0.469		0.413	0.498	0.723	UJ	0.099	0.075	0.125	U
LOT46	WOOD-04-LOT46	12/17/2015		2.85	0.975	0.613	R	0.147	0.987	1.15	R	0.505	0.178	0.216	R

Notes:

All units in picoCurie per gram (pCi/g).

CSU (+/- s) = combined standard uncertainty (2 sigma)

MDA - minimum detectable activity

Q - qualifier

U - not detected

J - estimated value

R - rejected

Highlighted cell and bold format indicates that concentration exceeded screening criteria.



^{*} Parent sample ID listed for duplicate samples.

Table 1-2 Remediation Goals Wolff-Alport Chemical Company Superfund Site Ridgewood, Queens, New York

Contaminants of Concern	Remediation Goal	Specifically Applied Principles
Solids		
PCBs	1 mg/kg	
Benzo(a)pyrene	1 mg/kg	
Ra-226 ¹	1 pCi/g ²	ALARA
Th-232	4 pCi/g ²	ALARA
Indoor Air		
Combined Radon-222 and Radon-220 measured indoors	4 pCi/g ²	ALARA
Combined decay products of Radon-222 and Radon-220 measured indoors	0.02 working level	ALARA

Notes:

- 1. Ra-226 is used to indicate U-238 levels.
- 2. Including natural background.
- 3. Some devices measure radiation from radon decay products, rather than radiation coming directly from radon. Measurements from these devices are often expressed as "Working Level."



Table 2-1 Asbestos-Containing Materials and Quantities Wolff-Alport Chemical Company Superfund Site Ridgewood, Queens, New York

Lot Number	Asbestos-Containing Material	Quantity
	Tar on cinderblock wall	4,000 SF
	Abandoned panel board backing paper	12 SF
	Tar on front edge trim below roof	100 SF
33	Assumed ACM electrical panels	26 SF
	Assumed ACM electrical wire insulation	1,500 SF
	Roof membrane/flashing/pitch pocket tar/drain flashing	13,400 SF
	Flashing on roof fans/gooseneck flashing	40 SF
	Roof membrane	7,800 SF
42	Roof flashing/parapet wall tar/flashing	1,720 SF
42	Coping stone tar	150 SF
	Vent stack tar/flashing	40 SF
	Roof membrane	2,500 SF
44	Roof flashing/parapet wall tar/flashing	500 SF
44	Vent stack tar/flashing	10 SF
	Tar on beams	20 SF
	Tar/Paint on gate	30 SF
	Roof membrane	1,000 SF
	Roof flashing/parapet wall tar/flashing	520 SF
	Tar on beams	40 SF
46	Assumed asbestos-containing roofing materials	1,500 SF
	Assumed asbestos-containing window caulking materials	12 LF
	Assumed asbestos-containing surfacing materials throughout interior	3,000 SF
	Assumed asbestos-containing thermal insulation materials throughout interior	120 LF
	Assumed asbestos-containing miscellaneous materials throughout interior	2,000 SF
	Roof membrane	90 SF
	Roof flashing	40 SF
	Tar on walls	10 SF
48	Tar/Purple paint on wall	320 SF
40	Roof membrane	1,000 SF
	Parapet wall tar/roof flashing	520 SF
	Coping stone tar	10 SF
	Vent stack tar/flashing	10 SF

Notes:

SF - square feet

LF - linear foot

ACM was assumed to be present in areas unable to be sampled.



Table 2-2
Inventory List of Materials Containing Mercury
Wolff-Alport Chemical Company Superfund Site
Ridgewood, Queens, New York

Lot Number	Hazardous Material ¹	Quantity (Each)
33	Suspect mercury-containing fluorescent light bulbs - 4 feet	68
33	Electric wall thermostats - 6 inches	4
42	Suspect mercury-containing fluorescent light bulbs - 4 feet	80
42	Fluorescent light ballasts ²	40
44	Suspect mercury-containing fluorescent light bulbs - 2 feet	6
44	Suspect mercury-containing fluorescent light bulbs - 4 feet	10
16	Suspect mercury-containing fluorescent light bulbs - 2 feet	36
46	Suspect mercury-containing fluorescent light bulbs - 4 feet	10
48	48 Suspect mercury-containing fluorescent light bulbs - 4 feet	

Notes:



 $^{^{\}mathrm{1}}$ Each fluorescent light bulb and thermostat presumed to contain mercury.

² Two ballasts were presumed to be associated with each fluorescent light fixture.

Table 2-3 Waste Disposal Categories Wolff-Alport Chemical Company Superfund Site Ridgewood, Queens, New York

Activity	Waste Description	Disposal		
	Cleared vegetation	Recycling facility		
Site preparation	Miscellaneous debris - nonporous	Recycling facility		
	Miscellaneous debris - porous	C&D facility		
Asbestos Abatement and Mercury-	Asbestos	Approved asbestos/Subtitle D landfill		
Containing Materials	Mercury-containing materials	Recycling facility		
Matau	Decontamination water	Nowhard and the state of the state of		
Water	Well decommissioning water	Nonhazardous - treatment facility		
	Nonporous materials not meeting the alpha/beta release criteria and porous demolition debris	Radioactive waste facility		
Demolition	Nonporous material meeting the alpha/beta release criteria	Recycling facility		




Table 5-1 Summary of Permits and Approvals Wolff-Alport Chemical Company Site Ridgewood, Queens, New York


Permit/Approval	Authority	Contact Name/Number
Street or Sidewalk	New York City Department of Transportation	Director of Project Managers, OCMC-Streets - Duane Barra (212) 839-9630
Construction Permit		Director of Project Managers, OCMC-Streets - Gary Smalls (212) 839-9583
Construction Permit		Director of Construction Coordination, OCMC-Streets - Vacant (212) 839-7129
		Queens Borough Office
Work Permit	New York City Department of	Borough Commissioner: (718) 286-7670
Work Fermit	Buildings	Borough Director: (718) 286-7630
		Customer Service: (718) 286-7620
	New York City Department of	artsfeedback@dep.nvc.gov
Asbestos Activity Forms	· · ·	https://a826-web01.nyc.gov/acpefile/Login.aspx?ReturnUrl=%2facpefile%2fACP7Home.aspx
Permit for Tap, Plug, Wet		
Connection, Repair/Relay of		WCDC Cupport at 719 505 2009 or word@dop ava gov
Water Service line	Find the second section in the second	WSPS Support at 718-595-3088 or wsps@dep.nyc.gov
Plug Single/Multiple Premise(s)		https://a826-amr.nyc.gov/mydepaccount/
Sewer House Connection(s)		





Figures

















Figure 1-5 General RA Construction Schedule Wolff-Alport Chemical Company Site Ridgewood, Queens, New York




days = working days

Task

Milestone ♦ Summary

Summary

File: Wolff-RA Schedule Date: Wed 9/5/18







Appendix A


Appendix A

Radiological Scanning and Sampling Results











>25,000 (>10x background)

CDM Smith








Table 4-14 Building and Sewer Materials Radiological Gamma Spectroscopy Results Wolff-Alport Chemical Company Site Ridgewood, NY

				Potassium-4	10			Radium-22	6			Thorium-23	2	
Location	Sample Date	Parent Sample*	Result	CSU (+/-2 s)	MDA	Q	Result	CSU (+/-2 s)	MDA	Q	Result	CSU (+/-2 s)	MDA	Q
Solids Scr	eening Criteria							0.919				1.220		
Building I	Materials													
LOT33	12/17/2015		23.743	3.068	0.976		3.86	1.593	1.67	J	1.754	0.384	0.183	
LOT33	12/17/2015	BRICK-02-LOT33	22.182	3.137	0.874		3.85	2.149	2.46	J	1.76	0.35	0.352	
LOT33	12/17/2015		2.18	1.14	1.79	J	2.726	1.59	1.86	J	0.579	0.215	0.372	J
LOT42	12/18/2015		33.469	6.481	4.41	J	21.09	10.986	13.5	J	152.66	9.698	1.6	
LOT42	12/17/2015		12.978	2.782	2.18	J	8.217	6.701	8.15	J	57.643	4.018	0.758	
LOT42	12/18/2015		3.917	0.608	0.191		0.349	0.602	0.705	UJ	0.45	0.115	0.077	
LOT44	12/17/2015		32.95	6.769	9.2	J	44.219	16.906	21.1	J	415.17	25.721	2.73	
LOT46	12/17/2015		9.781	1.986	1.93	J	6.619	2.855	3.73	J	7.784	0.813	0.332	J
LOT46	12/17/2015		0.479	0.302	0.469		0.413	0.498	0.723	UJ	0.099	0.075	0.125	U
LOT46	12/17/2015		2.85	0.975	0.613	R	0.147	0.987	1.15	R	0.505	0.178	0.216	R
Sewer Ma	aterials													
I-2	11/18/2015		184.87	20.203	22.6	R	76.423	38.146	44.9	J	2206.4	136.66	8.11	
I-4	11/18/2015		215.93	24.123	26.9	R	163.12	51.598	57.8	J	2536.2	155.41	10.2	
I-4	11/18/2015		6.553	1.662	1.58		2.106	1.877	3.11	C	4.423	0.624	0.185	
I-5	11/18/2015		6.876	1.31	0.396		1.117	2.253	2.63	UJ	4.67	0.494	0.208	
I-6	11/18/2015		16.45	2.735	0.956		2.686	2.131	2.59	J	1.044	0.289	0.314	
I-6	11/18/2015		6	1.397	1.09		0.347	1.113	2.02	UJ	0.698	0.213	0.366	
I-6	11/18/2015	CONC-I6	8.959	1.766	0.764		0.803	1.05	1.88	C	0.785	0.245	0.378	
I-7	11/18/2015		7.137	1.363	1.06		1.003	1.317	2.23	UJ	2.275	0.345	0.197	
I-8	11/18/2015		8.33	1.493	0.417		1.31	1.305	1.5	UJ	0.922	0.252	0.397	
Sewer Se	diments													
I-2	11/18/2015		72.749	15.332	20.7	J	69.801	6.939	4.254	J	1079.9	73.029	7.8	J
I-2	11/18/2015		90.381	11.434	13.6	J	45.938	4.762	3.809	J	1218.1	76.238	4.69	J
I-7	11/18/2015		21.624	4.044	2.99	J	6.153	0.837	0.892		116.72	7.319	1.25	J

Notes:

All units in picoCurie per gram (pCi/g).

CSU (+/- s) = combined standard uncertainty (2 sigma)

MDA - minimum detectable activity

Q - qualifier

U - not detected

J - estimated value

R - rejected

Highlighted cell and bold format indicates that concentration exceeded screening criteria.



^{*} Parent sample ID listed for duplicate samples.

Table 4-19 Building Material Scan Data Wolff-Alport Chemical Company Site Ridgewood, NY

		Pre-Sampling Total	Removable (Wipe Samples)
Sample ID	Comments/Location Description	Alpha (d	pm/100cm²)
CIND-01-LOT33	Cinder block from Lot 33	63	0
BRICK-02-LOT33	Brick from Lot 33	131	0
CONC-07-LOT42	In Primo Auto Body main shop (Lot 42)	575	2
CONC-08-LOT42	Concrete collected in Primo Auto main shop (Lot 42) Brick collected in Primo Auto main shop (Lot 42)	724	2
BRICK-09-LOT42	but underneath the overlying concrete	2,363	0
BRICK-06-LOT44	In Primo Auto Body auxillary shop (Lot 44). Brick from short brick wall in front of one of the arches	27,365	0
BRICK-03-LOT46	Brick In basement of deli (Lot 46)	10,376	0
WOOD-04-LOT46	Wood from basement of deli (Lot 46)	63	0
IBEAM-05-LOT46	Rusted steel from I-beam in basement of Jarabacoa Deli	59	0

Notes:

ID - identification



Appendix B

Appendix B

Revised Hazardous Building Materials Survey (provided on CD)





FINAL REPORT FOR HAZARDOUS MATERIALS SURVEY

PERFORMED AT:

WOLFF-ALPORT CHEMICAL COMPANY SITE

11-33 IRVING AVENUE - LOT 33

11-29 IRVING AVENUE - LOT 42

11-27 IRVING AVENUE - LOT 44

11-25 IRVING AVENUE - LOT 46

15-14 COOPER AVENUE - LOT 48

QUEENS, NY 11385

SERVICE ORDER NO.: 3323-054-004-CS

PERFORMED FOR:



CDM FEDERAL PROGRAMS CORPORATION 555 17TH STREET, SUITE 1100 DENVER, CO 80202

ATTN: MR. MUZAFFAR RAHMANI

PREPARED BY:

ATHENICA ENVIRONMENTAL SERVICES, INC. 45-09 GREENPOINT AVENUE, LONG ISLAND CITY, NY 11104 ATHENICA PROJECT # 15-111-0420

REVISED REPORT DATE:

FEBRUARY 20TH, 2018



TABLE OF CONTENTS

1.0	BACKGROUND1
2.0	SCOPE OF WORK5
3.1	SUMMARY OF ASBESTOS INSPECTION RESULTS
3.2	SUMMARY OF LEAD-BASED PAINT INSPECTION RESULTS
3.3	SUMMARY OF HAZARDOUS MATERIALS INSPECTION RESULTS
4.1	ASBESTOS INSPECTION RESULTS
4.2	LEAD-BASED PAINT INSPECTION RESULTS
4.3	HAZARDOUS MATERIALS INSPECTION RESULTS
5.0	CONCLUSSIONS & RECOMENDATIONS
6.0	AREAS NOT ACCESIBLE
7.0	REPORT CERTIFICATIONS
APF	PENDICES
8.0	APPENDIX A: Analytical Results, Chain-of-Custody Forms and Certificates of Laboratory Analysis
9.0	APPENDIX B: Personnel Certificates
10.0	APPENDIX C: Consulting Company License
11.0	APPENDIX D: Laboratory Accreditation
12.0	APPENDIX E: Project Documents

1.0 BACKGROUND

Athenica Environmental Services, Inc. was retained by CDM Smith to perform Site Survey for hazardous materials at the Wolff-Alport Chemical Company Site located at 15-14 Cooper Avenue, Queens NY 11385 (Lot 48), 11-25 Irving Avenue, Queens, NY 11385 (Lot 46), 11-27 Irving Avenue, Queens, NY 11385 (Lot 44), 11-29 Irving Avenue, Queens, NY 11385 (Lot 42) & 11-33 Irving Avenue, Queens, NY 11385 (Lot 33). The scope of the project was to perform hazardous materials surveys limited to asbestos containing materials (ACM), lead-based paint (LBP), polychlorinated biphenyls (PCBs), and various mercury, chlorofluorocarbon (CFC) or tritium containing materials as specified under specifications of service order 3323-054-004-CS.

Access to the site was provided by CDM Smith representatives and surveys were performed in all accessible areas. Areas which were not accessible were assumed to contain asbestos and lead-based paint containing materials, presence or absence of which cannot be confirmed without visual inspection.

Work Order: Service Order No.: 3323-054-004-CS

Site: Wolff-Alport Chemical Company Site

Address: 15-14 Cooper Avenue, Queens, NY 11385 – Lot 48

11-33 Irving Avenue, Queens, NY 11385 – Lot 33 11-29 Irving Avenue, Queens, NY 11385 – Lot 42 11-27 Irving Avenue, Queens, NY 11385 – Lot 44 11-25 Irving Avenue, Queens, NY 11385 – Lot 46

The Project Managers/ Inspectors/ Investigator/ Lead-risk Assessors/Hazardous Materials Evaluation responsible for this project were:

Asbestos Inspectors/ Investigator

Wojciech Sikorski NYC Investigator # 128636 Exp.: 02/24/2017

NYS Inspector: 08-08985 Exp.: 02/2016

Juraj Bardiovsky NYS Inspector: 08-04420 Exp.: 10/16

Nicholas Del Grosso NYS Inspector: 15-11534 Exp.: 07/16

Lead-based Paint Risk Assessor

Jeffrey Strykowski NYS/EPA Risk Assessor: NY-R-113399-2 Exp: 11/01/2017 Juraj Bardiovsky NYS/EPA Risk Assessor: NY-R-18077-2 Exp: 09/05/2018

Other Hazardous Materials Evaluation

William Silveri Certified Hazardous Materials Mgr. (CHMM) Exp: 03/30/2016

Site Visits: November 12th, 2015, November 13th, 2015 & December 4th, 2015

Report Date: January 5th, 2016 Revised Date: February 20th, 2018

2.0 BACKGROUND

Athenica Environmental Services, Inc. was retained by CDM Smith to perform surveys for hazardous materials at the Wolff-Alport Chemical Company Site located at 15-14 Cooper Avenue, Queens NY 11385 (Lot 48), 11-25 Irving Avenue, Queens, NY 11385 (Lot 46), 11-27 Irving Avenue, Queens, NY 11385 (Lot 44), 11-29 Irving Avenue, Queens, NY 11385 (Lot 42) & 11-33 Irving Avenue, Queens, NY 11385 (Lot 33). The scope of the project was to perform hazardous materials surveys limited to asbestos containing materials (ACM), lead-based paint (LBP), polychlorinated biphenyls (PCBs), and various mercury, chlorofluorocarbon (CFC) or tritium containing materials as specified under specifications of service order 3323-054-004-CS.

Access to the site was provided by CDM Smith representatives and surveys were performed in all accessible areas. Areas which were not accessible were assumed to contain asbestos and lead-based paint containing materials, presence or absence of which cannot be confirmed without visual inspection. The following filed procedures and analysis methods were employed for completion of hazardous materials surveys:

Asbestos Containing Materials Survey Field Procedures:

Guidelines used for the inspection were established by the Environmental Protection Agency (EPA) in the Guidance for Controlling Asbestos Containing Materials in Buildings, Office of Pesticides and Toxic Substances, DOC # 560/5-85-024, and 40 CFR Part 763, Asbestos Hazard Emergency Response Act (AHERA).

Field information was organized as per the AHERA concept of homogenous area (HA). That is, suspect ACM with similar age, appearance, and texture was grouped together, sampled and assessed for condition. The survey consisted of checking and inspecting the building for evidence of ACM. The survey has two components:

- Inspecting materials throughout all locations
- Sampling for laboratory confirmation that asbestos is present.

For the purpose of the inspection, suspect ACM materials have been grouped into three categories:

- Surfacing Materials, e.g.: wall plaster, ceiling plaster and other materials.
- Thermal System Insulation, e.g.: pipe insulation, boiler insulation, duct insulation and other materials
- Other Miscellaneous Materials, e.g.: floor and ceiling tiles, mastic/glue and other materials.

Asbestos Containing Materials Analysis Methodology:

Bulk samples were analyzed using Polarized Light Microscopy (PLM) and Non-Organically Bound Polarized Light Microscopy (PLM-NOB) and Transmission Electron Microscopy (TEM-NOB) by Laboratory Testing Services, Inc. Laboratory Testing Services, Inc. laboratory is accredited by the New York State Department of Health under their Environmental Laboratory Approval Program (ELAP ID # 10955) and by the National Institute of Standards and Technology (NIST) under their National Voluntary Laboratory Accreditation Program (NVLAP Laboratory ID 101958).

Lead-Based Paint Survey Field Procedures:

The lead-based paint survey was performed by NYS/EPA Risk Assessors certified to conduct lead-based paint activities pursuant to 40 CFR Part 745.226. An X-ray Fluorescence (XRF) device was utilized to determine the presence of lead-based paint in a surface-by-surface investigation, in accordance with the EPA/HUD, and following the Performance Characteristics Sheet (PCS) for the XRF device and the Manufactures Operating instructions. Lead-based paint was identified per the EPA/HUD of lead concentrations equal to or greater than 1.0 mg/cm², via XRF measurements.

The XRF instrument utilized, Niton XLp 302A is a complete lead paint analysis system that quickly, accurately and non-destructively measures the concentration of LBP on surfaces. The Niton XLp 302A relies on the measurement of the K-shell X-rays to determine the amount of lead present in the painted surface. K-shell X-rays can penetrate many layers of paint and allow a good measurement of the lead content of paint to be made without being significantly affected by the thickness or number of layers of paint on the surface of the sample.

The Niton XLp 302A has the ability to analyze and compute corrections for the differences in the energy spectrums relating to different substrates. This analysis of the energy spectrum means that the lead paint reading displayed on the instrument already accounts for any substrate effects and no correction is required by an operator. The Niton XLp 302A field of view is limited to a depth of 3/8", deep enough to handle virtually all painted surfaces, but not prone to detect lead objects located behind the surface.

Upon arrival at the job site and once every four hours or after the day's inspection work was completed, a "validation test" was performed to assure that the instrument was operating properly. A series of three test measurements (three readings each) were taken on a National Institute of Standards & Technology (NIST) Standard Reference Material (SRM) 2573 on a 1.0 mg/cm² calibration block provided by the manufacturer, as required by the instrument's PCS. The individual readings and an average of the three readings were recorded and compared to the standards. In all cases the instrument was functioning within the standard deviation as defined by the manufacturer and the PCS. All validation readings were recorded on Calibration Check Test Results Forms. If for any reason the XRF does not pass the quality control procedures, it is Niton's policy to replace that instrument with an XRF that passes the above criteria for calibration.

The parameters used to interpret XRF results are outlined in the PCS in Appendix. According to the PCS, each XRF result is classified as positive or negative as follows:

<u>Positive</u>: A positive classification indicates that LBP is present on the testing combination at or above the EPA/HUD standard of 1.0 mg/cm². A positive XRF result is any value greater than or equal to the threshold, as specified on the applicable XRF PCS.

<u>Negative:</u> A negative classification indicates that LBP is not present on the testing combination at or above the EPA/HUD standard. A negative XRF result is any value less than the threshold specified on the PCS.

The XRF inspection data specifies which surfaces were tested. Each side of a room is assigned a number for identification purposes. Wall 1 is designated as the side of the room of which the main entrance is situated. The remaining wall designations are assigned clockwise, in numerical order. Multiples of a component along a wall are also assigned clockwise in numerical order.

Lead-based Paint Analysis Methodology:

Paint chip samples shall be collected for inconclusive XRF testing combination and any surface which cannot be tested utilizing an XRF device (e.g., curved or rounded surfaces). Athenica does not anticipate collecting many such samples. Paint chip samples shall, whenever possible, be collected in inconspicuous areas. Paint samples shall be analyzed by Athenica's fully certified and accredited laboratory to perform the required analysis in accordance with New York State, HUD and EPA requirements.

Other Hazardous Building Materials Methodology:

Inspection for other hazardous building materials was conducted and entailed observing and inventorying potential PCB-containing, mercury-containing, tritium and chlorofluorocarbons (CFCs) containing items. Suspect PCB-containing, mercury-containing, tritium and chlorofluorocarbons (CFCs) containing items were closely inspected and inventoried. Findings of the survey can be found in Section 3.0.

3.1 SUMMARY OF ASBESTOS CONTAINING MATERIALS SURVEYS

The asbestos inspection involved a thorough visual examination of all areas affected by planned project and sampling of all suspect materials. The following is a summary of materials which were confirmed as ACM by laboratory analysis to contain asbestos and may be disturbed during this project:

LOCATION	MATERIAL	APPROX ACM QUANTITY						
11-33 IRVING AVENUE, QUEENS, NY – LOT 33								
INTERIOR	INTERIOR TAR ON CINDERBLOCK WALL							
INTERIOR	ABANDONED PANEL BOARD BACKING PAPER	12 SF						
EXTERIOR – FRONT FAÇADE BELOW ROOF EDGE	TAR ON FRONT EDGE TRIM BELOW ROOF	100 SF						
INTERIOR – LARGE	ASSUMED ACM ELECTRICAL PANELS	6 SF						
WAREHOUSE AREA	ASSUMED ACM ELECTRICAL WIRE INSULATION	1,200 LF						
INTERIOR – SMALL	ASSUMED ACM ELECTRICAL PANELS	20 SF						
ELECTRICAL ROOM	ASSUMED ACM ELECTRICAL WIRE INSULATION	300 LF						
	ROOF MEMBRANE/ FLASHING/ PITCH POCKET TAR/ DRAIN FLASHING	13,400 SF						
EXTERIOR – ROOF	FLASHING ON ROOF FANS/ GOOSENECK FLASHING	40 SF						
11-29 IRVING AVENUE, QUEENS, NY – LOT 42								
	ROOF MEMBRANE	7,800 SF						
EXTERIOR – ROOF	ROOF FLASHING/ PARAPET WALL TAR/ FLASHING	1,720 SF						
	COPING STONE TAR	150 SF						
	VENT STACK TAR/ FLASHING	40 SF						
11-27 I	RVING AVENUE, QUEENS, NY – LOT 44							
	ROOF MEMBRANE	2,500 SF						
EXTERIOR – ROOF	ROOF FLASHING/ PARAPET WALL TAR/ FLASHING	500 SF						
	VENT STACK TAR/ FLASHING	10 SF						
	TAR ON BEAMS	20 SF						
11-25 I	RVING AVENUE, QUEENS, NY – LOT 46							
EXTERIOR – FLAT FIX SHOP	TAR/ PAINT ON GATE	30 SF						
	ROOF MEMBRANE	1,000 SF						
BACK ROOF (1 ST FLOOR ROOF)	ROOF FLASHING PARAPET / WALL TAR/ FLASHING	520 SF						
	TAR ON BEAM	40 SF						
2 ND FLOOR ROOF	ASSUMED ASBESTOS CONTAINING ROOFING MATERIALS	1,500 SF						

11-25 I	RVING AVENUE, QUEENS, NY – LOT 46	
FACADES	ASSUMED ASBESTOS CONTAINING WINDOW CAULKING MATERIALS	12 LF
	ASSUMED ASBESTOS CONTAINING SURFACING MATERIALS THROUGHOUT INTERIOR	3,000 SF
PRIVATE APARTMENTS ON 1ST AND 2ND FLOORS	ASSUMED ASBESTOS CONTAINING THERMAL INSULATION MATERIALS THROUGHOUT INTERIOR	120 LF
	ASSUMED ASBESTOS CONTAINING MISCELLANEOUS MATERIALS THROUGHOUT INTERIOR	2,000 SF
15-14 C	OOPER AVENUE, QUEENS, NY – LOT 48	
CMALL CTED UD DOOF AT	ROOF MEMBRANE	90 SF
SMALL STEP-UP ROOF AT REAR OF BUILDING	ROOF FLASHING	40 SF
REAR OF BOILDING	TAR ON WALLS	10 SF
FACADES - AT FRONT OF AUTO REPAIR SHOP	TAR/ PURPLE PAINT ON WALL	320 SF
	ROOF MEMBRANE	1,000 SF
EXTERIOR - ROOF	PARAPET WALL TAR/ ROOF FLASHING	520 SF
EXTERIOR - ROOF	COPING STONE TAR	10 SF
	VENT STACK TAR/ FLASHING	10 SF

Materials which were tested positive must be abated prior to performing any work in the areas where they were found. In order to determine the exact quantities, a detailed scope of work should be determined. In the event that suspect ACM materials are encountered during the renovation project and are to be disturbed by the proposed construction work, all work must immediately stop. The suspect ACM materials should be tested and abated properly should they be found to contain asbestos.

3.2 SUMMARY OF LEAD-BASED PAINT SURVEYS

Paint film surfaces in all areas which are anticipated to be impacted by planned project and were screened for LBP. The following table lists the components which tested positive for LBP. A complete summary of XRF screening data is provided in Section 4.0.

LOCATION	COMPONENT	SUBSTRATE	COLOR	CONDITION					
11-29 IRVING AVENUE, QUEENS, NY – LOT 42									
TERRA NOVA	SHELF	METAL	PURPLE	FAIR					
TERRA NOVA	COLUMN	METAL	WHITE	INTACT					
	11-25 IRVING AVENU	E, QUEENS, NY -	LOT 46						
PRIMO FLAT FIX -	WALL	BRICK	GRAY	POOR					
TIRE STORAGE	COLUMN	CONCRETE	WHITE	INTACT					
DELI BASEMENT -	COLUMN	METAL	WHITE	INTACT					
DELI STORAGE RM.	COLUMN	METAL	ORANGE	POOR					
	COLUMN	METAL	ORANGE	POOR					
DELI BASEMENT -	COLUMN	METAL	ORANGE	POOR					
DELI UTILITY RM.	COLUMN	METAL	ORANGE	POOR					
	DOOR CASE	METAL	SILVER	FAIR					
PRIVATE APARTMENTS ON 1 ST AND 2 ND FLOORS	SUSPECT LBP COMPONENTS	N/A	N/A	ASSUMED TO CONTAIN LBP DUE TO NO ACCESS					
	15-14 COOPER AVEN	UE, QUEENS, NY -	- LOT 48						
	WALL	CINDERBLOCK	WHITE	POOR					
EXTERIOR	WALL	CINDERBLOCK	PURPLE	INTACT					
	WALL	CINDERBLOCK	PURPLE	INTACT					

3.3 SUMMARY OF HAZARDOUS MATERIALS SURVEYS

The other hazardous materials inspection involved a thorough visual examination of all equipment and items of concern. The following is a summary of the findings of this inspection. As indicated below, the items of environmental concern related to fluorescent light bulbs (mercury) and ballasts (PCBs) as well as potential mercury containing switches.

LOCATION	ITEM OF ENVIRONMENTAL CONCERN	SIZE	QUANTITY	COMMENT
	THROUGHOUT ALL B	UILDINGS		
THROUGHOUT INTERIOR	FLUORESCENT LIGHT FIXTURE BALLASTS	N/A	N/A	Non-PCB – Limited Visual inspection of light fixture ballasts revealed that light ballasts are labeled as non- PCB containing by manufacturer.
	11-33 IRVING AVENUE, QUEE	ENS, NY -	LOT 33	
THROUGHOUT INTERIOR	SUSPECT MERCURY CONTAINING FLOURESCENT LIGHT BULBS	4 FT.	68	See Note 2
INTERIOR	ELECTRIC WALL THERMOSTATS	6 IN.	4	See Note 2
	11-29 IRVING AVENUE, QUEE	ENS, NY -	LOT 42	
TERRANOVA - THROUGHOUT INTERIOR	SUSPECT MERCURY CONTAINING FLOURESCENT LIGHT BULBS	4 FT.	40	See Note 2
PRIMO AUTO BODY -	FLOURESCENT LIGHT BALLASTS	N/A	40	See Notes 1
THROUGHOUT INTERIOR	SUSPECT MERCURY CONTAINING FLOURESCENT LIGHT BULBS	4 FT.	40	See Note 2
	11-27 IRVING AVENUE, QUEE	NS, NY -	LOT 44	
THROUGHOUT	SUSPECT MERCURY CONTAINING FLOURESCENT	2 FT.	6	See Note 2
INTERIOR	LIGHT BULBS	4 FT.	10	See Note 2
	11-25 IRVING AVENUE, QUEE	NS, NY –	LOT 46	
THROUGHOUT -	SUSPECT MERCURY	2 FT.	6	See Note 2
PRIMO FLAT FIX	CONTAINING FLOURESCENT LIGHT BULBS	4 FT.	10	See Note 2
THROUGHOUT – DELI STORE		2 FT.	30	See Note 2
	15-14 COOPER AVENUE, QUE	ENS, NY	LOT 48	
THROUGHOUT INTERIOR	SUSPECT MERCURY CONTAINING FLOURESCENT LIGHT BULBS	4 FT.	24	See Note 2

Notes:

- Two (2) ballasts were presumed to be associated with each fluorescent light fixture.
 Each fluorescent light bulb and thermostat was presumed to contain mercury.

4.1 ASBESTOS INSPECTION RESULTS – 11-33 IRVING AVENUE, QUEENS, NY – LOT 33

HA No.	Sample Numbers	Location	Material	No. of Samples	Inspection Results	Notes/Comments
1.	1. 2. 3.		Brick Mortar	3	Non-ACM	Negative by PLM analysis.
2.	4. 5. 6.	Interior/ Exterior	Cinderblock Mortar	3	Non-ACM	Negative by PLM analysis.
3.	7. 8.		Gypsum Wall Board	2	Non-ACM	Negative by PLM analysis.
4.	9. 10.		Gypsum Ceiling Board	2	Non-ACM	Negative by PLM analysis.
5.	11. 12.		Black Paper on Sheetrock Ceiling	2	Non-ACM	Negative by PLM analysis.
6.	13. 14.		Interior Window Putty	2	Non-ACM	Negative by NOB-TEM analysis.
7.	15. 16.	Interior – Throughout	Tar on Cinderblock Wall	2	ACM	Positive by NOB-PLM analysis. Found in East Room on West Wall.
8.	17. 18.		White Paint on Cinderblock Walls	2	Non-ACM	Negative by NOB-TEM analysis.
9.	19.		Brown Paper Door Insulation	2	Non-ACM	Negative by PLM analysis.
10.	21. 22.		Abandoned Panel Board Backing Paper	2	ACM	Positive by NOB-PLM analysis. Abandoned panel box was found in on the floor of East Room.
11.	23. 24.		Abandoned Panel Black Components (Bakelite)	2	Non-ACM	Negative by NOB-TEM analysis.
12.	25. 26.		Stucco	2	Non-ACM	Negative by PLM analysis.
13.	27. 28.		Pink Paint on Stucco	2	Non-ACM	Negative by PLM analysis.
14.	29. 30.		Sidewalk Exp. Joint Caulking	2	Non-ACM	Negative by NOB-TEM analysis.
15.	31. 32.	Exterior	Asphalt At Exterior Base of Building	2	Non-ACM	Negative by NOB-TEM analysis.
16.	33. 34.		Textured Gray Paint on Metal Beams	2	Non-ACM	Negative by NOB-TEM analysis.
17.	35. 36.		Concrete Cement Board at Ceiling	2	Non-ACM	Negative by PLM analysis.
18.	37. 38.		Tar on Front Edge Trim below Roof	2	ACM	Positive by NOB-PLM analysis.

HA No.	Sample Numbers	Location	Material	No. of Samples	Inspection Results	Notes/Comments
19.	39. 40.		Roof Insulation	2	Non-ACM	Negative by NOB-TEM analysis.
20.	41. 42.		Roof Membrane	2	АСМ	Positive by NOB-TEM analysis.
21.	43. 44.		Roof Flashing	2	АСМ	Positive by NOB-TEM analysis.
22.	45. 46.	Exterior - Roof	Pitch Pocket Tar	2	АСМ	Positive by NOB-TEM analysis.
23.	47. 48.		Flashing on Roof Fans	2	АСМ	Positive by NOB-TEM analysis.
24.	49. 50.		Drain Flashing	2	АСМ	Positive by NOB-TEM analysis.
25.	51. 52.		Gooseneck Flashing	2	АСМ	Positive by NOB-TEM analysis.
N/A	N/A		Metal Floor	0	Non-Suspect	
N/A	N/A		Water Pump Pipe	0	Non-Suspect	Insulation was not observed
N/A	N/A		PVC Drain Pipe	0	Non-Suspect	Insulation was not observed
N/A	N/A		Metal Gate	0	Non-Suspect	
N/A	N/A	Interior	Assumed ACM Contaminated Debris in Water	0	Assumed ACM	Some debris was observed in large water puddle. Due to live electricity/ broken conduits in the area of the water puddle, samples from debris which may contain roofing materials were not collected. Debris should be sampled when the area is isolated form electric power.
N/A	N/A	Interior – Large Warehouse	Assumed ACM Panels	0	Assumed ACM	Live never muchibited never the e
N/A	N/A	Area	Assumed ACM Wire Insulation	0	Assumed ACM	Live power prohibited sampling. Materials must be assumed until
N/A	N/A	Interior – Small Electrical Room	Assumed ACM Panels	0	Assumed ACM	sampled.
N/A	N/A	intendi – Small Electrical Room	Assumed ACM Wire Insulation	0	Assumed ACM	Sampleu.
			Total for Building:	52	Affected ACM Quantity	

4.1 ASBESTOS INSPECTION RESULTS – 11-29 IRVING AVENUE, QUEENS, NY – LOT 42

	T		- , -, -, -	· · · · · · · · · · · · · · · · · · ·		
HA No.	Sample Numbers	Location	Material	No. of Samples	Inspection Results	Notes/Comments
1.	1. 2. 3.	Interior – Throughout	Brick Mortar	3	Non-ACM	Negative by PLM analysis.
2.	4. 5. 6.		Cinderblock Mortar	3	Non-ACM	Negative by PLM analysis.
3.	7. 8.		Ceiling Sheetrock	2	Non-ACM	Negative by PLM analysis.
4.	9. 10. 11. 12. 13.	Interior – West Half of Building	Wall Plaster (Scratch Coat Only)	5	Non-ACM	Negative by PLM analysis.
5.	14. 15.	Interior – East Wall	Interior Window Putty	2	Non-ACM	Negative by NOB-TEM analysis.
6.	16. 17.	Interior – West Half of Building (Upstairs Office)	12x12 Floor Tiles/ Glue	2	Non-ACM	Negative by NOB-TEM analysis.
7.	18. 19.	Interior – Throughout	Door Insulation (Front & Back Doors)	2	Non-ACM	Negative by PLM analysis.
8.	20. 21.	Interior – Throughout	Joint Caulking on Metal Floor Plate	2	Non-ACM	Negative by NOB-TEM analysis.
9.	22. 23.		Roof Membrane (Bottom Layer)	2	ACM	Positive by NOB-TEM analysis.
10.	24. 25.		Roof Membrane (Top Layer)	2	ACM	Positive by NOB-TEM analysis.
11.	26. 27.		Roof Flashing (Bottom Layer)	2	ACM	Positive by NOB-TEM analysis.
12.	28. 29.		Roof Flashing (Top Layer)	2	ACM	Positive by NOB-TEM analysis.
13.	30. 31.	Exterior - Roof	Coping Stone Tar	2	ACM	Positive by NOB-TEM analysis.
14.	32. 33.		Parapet Wall Tar/ Flashing	2	ACM	Positive by NOB-TEM analysis.
15.	34. 35.		Vent Stack Tar/ Flashing	2	ACM	Positive by NOB-TEM analysis.
16.	36. 37.		Loose Car Parts/ Body Lining	2	Non-ACM	Negative by NOB-TEM analysis.
N/A	N/A	1	Roof Wood Decking Below Roofing	0	Non-Suspect	
N/A	N/A		Metal Floor	0	Non-Suspect	
N/A	N/A		Exposed Pipes Throughout	0	Non-Suspect	All visible pipes were found to be non- insulated.
N/A	N/A	Interior - Throughout	Electrical Wiring	0	Non-Suspect	Non-suspect vinyl wiring was observed in panels and conduits.
N/A	N/A		Electrical Panels	0	Non-Suspect	Metal electrical panels were observed.

HA No.	Sample Numbers	Location	Material	No. of Samples	Inspection Results	Notes/Comments
			Total for Building:	37	Affected ACM Quantity	

4.1 ASBESTOS INSPECTION RESULTS – 11-27 IRVING AVENUE, QUEENS, NY – LOT 44

HA No.	Sample Numbers	Location	Material	No. of Samples	Inspection Results	Notes/Comments
	1.					
1.	2.		Brick Mortar	3	Non-ACM	Negative by PLM analysis.
	3.					
2.	4. 5.		Cinderblock Mortar	3	Non-ACM	Negative by PLM analysis.
۷.	6.		Ciliderblock Mortal	3	NOTI-ACIVI	Negative by FLIVI arialysis.
_	7.		W(1) B : (O)			N. C. I. NOD TEM
3.	8.	Interior - Throughout	White Paint on Cinderblocks	2	Non-ACM	Negative by NOB-TEM analysis.
4.	9.		Wall Sheetrock	2	Non-ACM	Negative by PLM analysis.
٠.	10.		Wall Chooliook		11011710111	riogative by i Livi analysis.
5.	11. 12.		Floor Debris	3	Non-ACM	Negative by DLM englysis
5.	13.		Floor Debits	3	NON-ACIVI	Negative by PLM analysis.
_	14.			_		
6.	15.		Joint Caulking on Metal Plate	2	Non-ACM	Negative by PLM analysis.
7.	16. 17.		Roof Membrane (Bottom Layer)	2	ACM	Positive by NOB-TEM analysis.
8.	18. 19.		Roof Membrane (Top Layer)	2	ACM Contaminated	Positive by NOB-TEM analysis.
9.	20.	Exterior - Roof	Parapet Wall Tar/ Flashing	2	ACM	Positive by NOB-TEM analysis.
9.	21.	Exterior - Rooi	Farapet Wall Tail Flashing		ACIVI	Positive by NOB-1EM analysis.
10.	22.		Tar on Beams	2	ACM	Negative by NOB-TEM analysis.
	23. 24.					,
11.	25.		Vent Stack Tar/ Flashing	2	ACM	Positive by NOB-TEM analysis.
N/A	N/A		Metal Floor	0	Non-Suspect	
N/A	N/A	Interior - Throughout	Electrical Wiring	0	Non-Suspect	Non-suspect vinyl wiring was observed in panels and conduits.
N/A	N/A		Electrical Panels	0	Non-Suspect	Metal electrical panels were observed.
			Total for Building:	25	Affected ACM Quantity	

4.1 ASBESTOS INSPECTION RESULTS – 11-25 IRVING AVENUE, QUEENS, NY – LOT 46

HA No.	Sample Numbers	Location	Material	No. of Samples	Inspection Results	Notes/Comments
1.	1. 2. 3.	Interior- Basement	Brick Mortar	3	Non-ACM	Negative by PLM analysis.
2.	4. 5.		White Coating on Bricks	2	Non-ACM	Negative by PLM analysis.
3.	6. 7.		Wall Sheetrock	2	Non-ACM	Negative by PLM analysis.
4.	8. 9.		Ceiling Sheetrock	2	Non-ACM	Negative by PLM analysis.
5.	10. 11. 12.		Beam Plaster/ Cement	3	Non-ACM	Negative by PLM analysis.
6.	13. 14.	Interior – Ground Floor Deli Store (Toilet)	Ceramic Floor Tile Grout	2	Non-ACM	Negative by PLM analysis.
7.	15. 16.		Ceramic Floor Tile Setting Cement	2	Non-ACM	Negative by PLM analysis.
8.	17. 18.		Ceramic Wall Tile Grout	2	Non-ACM	Negative by PLM analysis.
9.	19. 20.		Ceramic Wall Tile Setting Cement	2	Non-ACM	Negative by PLM analysis.
10.	21. 22.	Interior – Ground Floor Deli Store (Behind Counter)	Mastic Associated with 12x12 Floor Tiles	2	Non-ACM	Negative by NOB-TEM analysis.
11.	23. 24.		12x12 Floor Tiles (Black)	2	Non-ACM	Negative by NOB-TEM analysis.
12.	25. 26.		12x12 Floor Tiles (Grey)	2	Non-ACM	Negative by NOB-TEM analysis.
13.	27. 28.	Interior – Flat Fix Shop (Back Portion of Building)	Ceiling Sheetrock	2	Non-ACM	Negative by PLM analysis.
14.	29. 30.	Exterior – Flat Fix Shop	Grey Stucco on Building Façade	2	Non-ACM	Negative by PLM analysis.
15.	31. 32.		Caulking on Gate (Silver)	2	Non-ACM	Negative by NOB-TEM analysis.
16.	33. 34.		Caulking on Gate (Brown)	2	Non-ACM	Negative by NOB-TEM analysis.
17.	35. 36.		Tar/ Paint on Gate	2	ACM	Positive by NOB-PLM analysis.
18.	37. 38.		Coating on Bricks	2	Non-ACM	Negative by PLM analysis.

HA No.	Sample Numbers	Location	Material	No. of Samples	Inspection Results	Notes/Comments
19.	39. 40.	Back Roof (1 st Floor Roof)	Roof Membrane (Bottom Layer)	2	ACM	Positive by NOB-TEM analysis.
20.	41. 42.		Roof Membrane (Top Layer)	2	ACM Contaminated	Positive by NOB-TEM analysis.
21.	43. 44.		Parapet Wall Tar/ Flashing	2	ACM	Positive by NOB-TEM analysis.
22.	45. 46.		Tar on Beam	2	ACM	Positive by NOB-TEM analysis.
N/A	N/A	2 nd Floor Roof	Assumed Asbestos Containing Roofing Materials	0	Assumed ACM	Access to materials on 2 nd Floor Roof, areas belonging to the private apartments and Façade at 2 nd Floor were not accessible during the building surveys and must be assumed to contain asbestos materials.
N/A	N/A	Facades	Assumed Asbestos Containing Window Caulking Materials			
			Assumed Asbestos Containing Materials throughout Facades			
N/A	N/A	- Private Apartments on 1 st and 2 nd Floors	Assumed Asbestos Containing Surfacing Materials Throughout Interior	0	Assumed ACM	Wall and Ceiling Plaster may be present and must be assumed to exist until tested.
N/A	N/A		Assumed Asbestos Containing Thermal Insulation Materials Throughout Interior	0	Assumed ACM	Miscellaneous materials which may be present include pipe insulation must be assumed to exist until tested.
N/A	N/A		Assumed Asbestos Containing Miscellaneous Materials Throughout Interior	0	Assumed ACM	Miscellaneous materials which may be present include interior caulking, grouts/ mortars/ setting bed/ soft cement associated with Kitchen and Bathroom tiles, floor tiles/ mastics/ glues/ flooring, wall/ ceiling materials, sink under coatings must be assumed to exist until tested.
N/A	N/A	Interior - Throughout	Electrical Wiring	0	Non-Suspect	Non-suspect vinyl wiring was observed in panels and conduits.
N/A	N/A		Electrical Panels	0	Non-Suspect	Metal electrical panels were observed.
			Total for Building:	46	Affected ACM Quantity	

4.1 ASBESTOS INSPECTION RESULTS - 15-14 COOPER AVENUE, QUEENS, NY – LOT 48

HA No.	Sample Numbers	Location	Material	No. of Samples	Inspection Results	Notes/Comments
1.	1. 2.		Brick Mortar	3	Non-ACM	Negative by PLM analysis.
	3. 4.	Interior/ Exterior				
2.	5.		Cinderblock Mortar	3	Non-ACM	Negative by PLM analysis.
	6. 7.					
3.	8.		White Coating on Bricks	2	Non-ACM	Negative by NOB-TEM analysis.
4.	9. 10.	Interior	Wall Sheetrock	2	Non-ACM	Negative by PLM analysis.
5.	11. 12.		Ceiling Sheetrock	2	Non-ACM	Negative by PLM analysis.
6.	13. 14.		Roof Membrane	2	ACM	Positive by NOB-TEM analysis.
7.	15.	Small Step-up Roof at Rear of	Roof Flashing	2	ACM	Positive by NOB-PLM analysis.
	16. 17.	Building		_		
8.	18.		Tar on Walls	2	ACM	Positive by NOB-TEM analysis.
9.	19. 20.		Tar Above Store/ Garage Gate	2	Non-ACM	Negative by NOB-TEM analysis.
10.	21.	Facades	Tar/ Purple Paint on Wall	2	ACM	Positive by NOB-TEM analysis.
11.	23.		Door Mortar	2	Non-ACM	Negative by PLM analysis.
12.	25. 26.		Roof Membrane (Bottom Layer)	2	ACM	Positive by NOB-TEM analysis.
13.	27. 28.		Roof Membrane (Top Layer)	2	ACM Contaminated	Negative by NOB-TEM analysis.
14.	29.		Parapet Wall Tar/ Flashing	2	ACM	Positive by NOB-TEM analysis.
17.	30. 31.	Exterior - Roof				
15.	32.		Coping Stone Tar	2	ACM	Positive by NOB-TEM analysis.
16.	33. 34.		Vent Stack Tar/ Flashing	2	ACM	Positive by NOB-TEM analysis.
17.	35. 36.		Gooseneck Flashing	2	Non-ACM	Negative by NOB-TEM analysis.
N/A	N/A	Interior - Throughout	Electrical Wiring	0	Non-Suspect	Non-suspect vinyl wiring was observed in panels and conduits.
N/A	N/A	<u> </u>	Electrical Panels	0	Non-Suspect	Metal electrical panels were observed.
			Total for Building:	36	Affected ACM Quantity	

4.2 LEAD-BASED PAINT RESULTS – 11-33 IRVING AVENUE, QUEENS, NY – LOT 33

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
East Room	1		Column	Metal	Gray	Intact	0.3	Non-LBP
East Room	-	5	Beam	Metal	Gray	Intact	0.3	Non-LBP
East Room	-	3	Beam	Metal	Gray	Intact	0.2	Non-LBP
East Room	-		Ceiling	Sheetrock	Gray	Poor	0.0	Non-LBP
East Room	-		Ceiling	Sheetrock	Gray	Poor	0.0	Non-LBP
East Room	-		Ceiling	Sheetrock	Gray	Poor	0.0	Non-LBP
East Room	-	1	Beam	Metal	Gray	Fair	0.3	Non-LBP
East Room	1		Door Case	Metal	Gray	Poor	0.2	Non-LBP
East Room	2		Wall	Brick	White	Intact	0.0	Non-LBP
East Room	2		Wall	Cinderblock	White	Intact	0.0	Non-LBP
East Room	2	1	Molding	Wood	White	Intact	0.0	Non-LBP
East Room	2	2	Molding	Wood	White	Fair	0.0	Non-LBP
East Room	2	3	Molding	Wood	White	Fair	0.0	Non-LBP
East Room	2		Wall	Cinderblock	Black	Fair	0.0	Non-LBP
East Room	2		Column	Metal	Gray	Intact	0.4	Non-LBP
East Room	2		Pipe	Metal	Gray	Poor	0.3	Non-LBP
Middle Room	1	1	Column	Brick	White	Intact	0.0	Non-LBP
Middle Room	1	2	Column	Brick	White	Intact	0.0	Non-LBP
Middle Room	1	2	Column	Brick	Dark Brown	Intact	0.0	Non-LBP
Middle Room	1		Wall	Brick	Dark Brown	Intact	0.0	Non-LBP
Middle Room	1		Wall	Brick	White	Intact	0.0	Non-LBP
Middle Room	1		Window Sill	Metal	White	Poor	0.0	Non-LBP
Middle Room	1		Window Sash	Metal	White	Poor	0.0	Non-LBP
Middle Room	1		Window Header	Metal	White	Fair	0.0	Non-LBP
Middle Room	1	1	Door Case	Metal	Gray	Intact	0.2	Non-LBP
Middle Room	1	2	Door Case	Metal	Dark Brown	Fair	0.0	Non-LBP
Middle Room	1	2	Door	Metal	Dark Brown	Intact	0.0	Non-LBP
Middle Room	2		Wall	Sheetrock	Dark Brown	Poor	0.0	Non-LBP
Middle Room	2		Wall	Sheetrock	White	Poor	0.0	Non-LBP
Middle Room	2	1	Electric Conduit	Metal	Dark Brown	Intact	0.0	Non-LBP
Middle Room	2	1	Electric Conduit	Metal	White	Intact	0.0	Non-LBP
Middle Room	2	2	Electric Conduit	Metal	Dark Brown	Intact	0.0	Non-LBP
Middle Room	2	3	Electric Conduit	Metal	Dark Brown	Intact	0.0	Non-LBP
Middle Room	2	3	Electric Conduit	Metal	White	Intact	0.0	Non-LBP
Middle Room	2	4	Electric Conduit	Metal	Dark Brown	Intact	0.0	Non-LBP
Middle Room	2	4	Electric Conduit	Metal	White	Intact	0.0	Non-LBP
Middle Room	2	5	Electric Conduit	Metal	Dark Brown	Intact	0.2	Non-LBP
Middle Room	2	5	Electric Conduit	Metal	White	Intact	0.2	Non-LBP
Middle Room	2	1	Door Case	Wood	Dark Brown	Poor	0.0	Non-LBP
Middle Room	2	1	Door Jamb	Wood	Gray	Intact	0.0	Non-LBP
Middle Room	2	1	Door	Wood	White	Intact	0.0	Non-LBP
Middle Room	2	2	Door	Metal	Dark Brown	Intact	0.0	Non-LBP

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Middle Room	2	2	Door Case	Metal	Dark Brown	Intact	0.0	Non-LBP
Middle Room	2	2	Door Jamb	Metal	Dark Brown	Intact	0.0	Non-LBP
Middle Room	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Middle Room	2	1	Column	Wood	White	Intact	0.0	Non-LBP
Middle Room	2	3	Column	Wood	White	Intact	0.0	Non-LBP
Middle Room	3	1	Column	Cinderblock	White	Intact	0.0	Non-LBP
Middle Room	3	2	Column	Wood	White	Intact	0.0	Non-LBP
Middle Room	3	3	Column	Wood	White	Intact	0.0	Non-LBP
Middle Room	3	4	Column	Cinderblock	White	Intact	0.0	Non-LBP
Middle Room	3	5	Column	Wood	White	Intact	0.0	Non-LBP
Middle Room	3		Wall	Metal	White	Intact	0.0	Non-LBP
Middle Room	3		Wall	Metal	White	Intact	0.0	Non-LBP
Middle Room	4		Wall	Brick	White	Intact	0.0	Non-LBP
Middle Room	4		Wall	Cinderblock	White	Intact	0.0	Non-LBP
Middle Room	4		Wall	Cinderblock	White	Intact	0.0	Non-LBP
Middle Room	4	4	Column	Cinderblock	White	Intact	0.0	Non-LBP
Middle Room	4	5	Column	Cinderblock	White	Intact	0.0	Non-LBP
Middle Room	4	1	Column	Wood	White	Intact	0.0	Non-LBP
Middle Room	4	2	Column	Wood	White	Intact	0.0	Non-LBP
Middle Room	4	3	Column	Wood	White	Intact	0.0	Non-LBP
Middle Room	4	1	Window Sash	Metal	White	Poor	0.0	Non-LBP
Middle Room	4	2	Window Sash	Metal	White	Poor	0.2	Non-LBP
Middle Room	4	3	Window Sash	Metal	White	Poor	0.0	Non-LBP
Middle Room	-		Ceiling	Sheetrock	White	Poor	0.0	Non-LBP
Middle Room	-		Ceiling	Sheetrock	White	Poor	0.0	Non-LBP
Middle Room	-		Ceiling	Sheetrock	White	Poor	0.0	Non-LBP
Middle Room	-	1	Beam	Metal	Gray	Intact	0.2	Non-LBP
Middle Room	-	2	Beam	Metal	Gray	Intact	0.0	Non-LBP
Middle Room	-	3	Beam	Metal	Gray	Intact	0.0	Non-LBP
Middle Room	-	4	Beam	Metal	Gray	Intact	0.0	Non-LBP
Middle Room	-	5	Beam	Metal	Gray	Intact	0.0	Non-LBP
Middle Room	-	1	Vent Cover	Metal	White	Intact	0.0	Non-LBP
Middle Room	-	2	Vent Cover	Metal	White	Intact	0.0	Non-LBP
Middle Room	-	1	Pipe	Metal	Gray	Poor	0.0	Non-LBP
Middle Room	-	2	Pipe	Metal	Gray	Fair	0.0	Non-LBP
Middle Room	-		Floor	Concrete	Gray	Poor	0.0	Non-LBP
Electrical Panel Room	-		Floor	Concrete	Gray	Poor	0.0	Non-LBP
Electrical Panel Room	1		Door Case	Wood	White	Intact	0.0	Non-LBP
Electrical Panel Room	1		Door	Wood	White	Intact	0.0	Non-LBP
Electrical Panel Room	1		Door Jamb	Wood	Gray	Intact	0.0	Non-LBP
Electrical Panel Room	1		Wall	Sheetrock	White	Fair	0.0	Non-LBP
Electrical Panel Room	1		Wall	Sheetrock	White	Fair	0.0	Non-LBP
Electrical Panel Room	1		Column	Wood	White	Intact	0.0	Non-LBP
Electrical Panel Room	2		Wall	Cinderblock	White	Intact	0.0	Non-LBP
Electrical Panel Room	2		Wall	Cinderblock	White	Intact	0.0	Non-LBP

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Electrical Panel Room	2		Column	Cinderblock	White	Intact	0.0	Non-LBP
Electrical Panel Room	2	1	Electric Box	Metal	Gray	Fair	0.0	Non-LBP
Electrical Panel Room	2	2	Electric Box	Metal	Gray	Fair	0.1	Non-LBP
Electrical Panel Room	2	3	Electric Box	Metal	Gray	Fair	0.1	Non-LBP
Electrical Panel Room	2	4	Electric Box	Metal	Gray	Fair	0.0	Non-LBP
Electrical Panel Room	2	5	Electric Box	Metal	Gray	Poor	0.0	Non-LBP
Electrical Panel Room	2	6	Electric Box	Metal	Gray	Poor	0.1	Non-LBP
Electrical Panel Room	2		Divider	Wood	White	Intact	0.0	Non-LBP
Electrical Panel Room	2		Window Sill	Metal	White	Poor	0.1	Non-LBP
Electrical Panel Room	2		Window Sash	Metal	Gray	Poor	0.0	Non-LBP
Electrical Panel Room	2		Column	Metal	White	Intact	0.0	Non-LBP
Electrical Panel Room	2		Window Header	Metal	Gray	Poor	0.0	Non-LBP
Electrical Panel Room	-	2	Beam	Metal	Gray	Intact	0.0	Non-LBP
Electrical Panel Room	-	1	Beam	Metal	Gray	Intact	0.0	Non-LBP
Electrical Panel Room	-		Ceiling	Sheetrock	Gray	Fair	0.0	Non-LBP
Electrical Panel Room	-		Ceiling	Sheetrock	Gray	Fair	0.0	Non-LBP
Electrical Panel Room	-		Ceiling	Sheetrock	Gray	Fair	0.0	Non-LBP
Electrical Panel Room	3		Wall	Wood	White	Intact	0.0	Non-LBP
Electrical Panel Room	3		Wall	Wood	White	Intact	0.0	Non-LBP
Electrical Panel Room	3		Baseboard	Wood	White	Intact	0.0	Non-LBP
Electrical Panel Room	4		Baseboard	Wood	White	Intact	0.0	Non-LBP
Electrical Panel Room	4		Wall	Wood	White	Poor	0.0	Non-LBP
Electrical Panel Room	4		Wall	Wood	White	Poor	0.0	Non-LBP
Electrical Panel Room	2	1	Electric Conduit	Metal	White	Poor	0.1	Non-LBP
Electrical Panel Room	2	2	Electric Conduit	Metal	White	Poor	0.0	Non-LBP
Electrical Panel Room	2	3	Electric Conduit	Metal	White	Poor	0.0	Non-LBP
Electrical Panel Room	2		Pipe	Metal	White	Intact	0.0	Non-LBP
Large Warehouse Area	1		Wall	Cinderblock	White	Intact	0.0	Non-LBP
Large Warehouse Area	1		Wall	Brick	White	Intact	0.0	Non-LBP
Large Warehouse Area	1	2	Door Case	Metal	Dark Brown	Fair	0.1	Non-LBP
Large Warehouse Area	1		Column	Cinderblock	White	Intact	0.0	Non-LBP
Large Warehouse Area	1		Column	Metal	Gray	Intact	0.0	Non-LBP
Large Warehouse Area	1		Window Sill	Metal	Gray	Poor	0.0	Non-LBP
Large Warehouse Area	1		Window Sash	Metal	Gray	Poor	0.0	Non-LBP
Large Warehouse Area	1		Window Header	Metal	Gray	Fair	0.0	Non-LBP
Large Warehouse Area	1		Pipe	Metal	White	Intact	0.0	Non-LBP
Large Warehouse Area	1	1	Door Case	Metal	White	Fair	0.0	Non-LBP
Large Warehouse Area	1		Fence	Metal	Gray	Intact	0.0	Non-LBP
Large Warehouse Area	-	5	Beam	Metal	Gray	Intact	0.0	Non-LBP
Large Warehouse Area	-	1	Beam	Metal	Gray	Intact	0.0	Non-LBP
Large Warehouse Area	-	7	Beam	Metal	Gray	Intact	0.0	Non-LBP
Large Warehouse Area	-		Ceiling	Sheetrock	Gray	Intact	0.0	Non-LBP
Large Warehouse Area	-		Ceiling	Sheetrock	Gray	Intact	0.0	Non-LBP
Large Warehouse Area	-		Ceiling	Sheetrock	Gray	Intact	0.0	Non-LBP
Large Warehouse Area	3		Door	Wood	White	Fair	0.0	Non-LBP

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Large Warehouse Area	4		Door Case	Metal	Red	Fair	0.0	Non-LBP
Large Warehouse Area	-	1	Column	Metal	Gray	Fair	0.0	Non-LBP
Large Warehouse Area	-	2	Column	Metal	Gray	Fair	0.0	Non-LBP
Large Warehouse Area	-	3	Column	Metal	Gray	Fair	0.0	Non-LBP
Large Warehouse Area	-	4	Column	Metal	Gray	Fair	0.1	Non-LBP
Large Warehouse Area	-	5	Column	Metal	Gray	Fair	0.0	Non-LBP
Large Warehouse Area	2		Wall	Cement	Gray	Poor	0.0	Non-LBP
Large Warehouse Area	2		Wall	Cement	Gray	Poor	0.0	Non-LBP
Large Warehouse Area	2		Pipe	Metal	Gray	Poor	0.0	Non-LBP
Large Warehouse Area	-		Hatch Door	Metal	Gray	Poor	0.0	Non-LBP
Exterior	1	1	Door Case	Metal	Yellow	Intact	0.2	Non-LBP
Exterior	1	2	Door Case	Metal	Dark Brown	Fair	0.3	Non-LBP
Exterior	1	3	Door Case	Metal	Dark Brown	Intact	0.0	Non-LBP
Exterior	1	4	Door Case	Metal	Yellow	Fair	0.0	Non-LBP
Exterior	1	5	Door Case	Metal	Dark Brown	Fair	0.1	Non-LBP
Exterior	1		Wall	Cement	Pink	Poor	0.0	Non-LBP
Exterior	1		Panel	Metal	Red	Poor	0.0	Non-LBP

4.2 LEAD-BASED PAINT INSPECTION DATA – 11-29 IRVING AVENUE, QUEENS, NY – LOT 42

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Terra Nova - Exterior	1		Fence	Metal	Red	Intact	0.0	Non-LBP
Terra Nova - Exterior	1	2	Door Case	Metal	Dark Brown	Fair	0.0	Non-LBP
Terra Nova - Exterior	1		Wall	Brick	Gray	Intact	0.0	Non-LBP
Terra Nova - Exterior	1	1	Door Case	Metal	Gray	Intact	0.0	Non-LBP
Terra Nova-Bay	1		Wall	Brick	White	Intact	0.0	Non-LBP
Terra Nova-Bay	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova-Bay	2		Wall	Cinderblock	White	Intact	0.0	Non-LBP
Terra Nova-Bay	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova-Bay	2		Wall	Sheetrock	Gray	Intact	0.0	Non-LBP
Terra Nova-Bay	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova-Bay	2	1	Door	Wood	White	Intact	0.0	Non-LBP
Terra Nova-Bay	2	1	Door Case	Wood	White	Intact	0.0	Non-LBP
Terra Nova-Bay	2	4	Door Case	Wood	White	Intact	0.0	Non-LBP
Terra Nova-Bay	2	4	Door	Wood	White	Intact	0.0	Non-LBP
Terra Nova-Bay	2	1	Shelf	Wood	White	Intact	0.0	Non-LBP
Terra Nova-Bay	2	2	Shelf	Wood	Gray	Intact	0.0	Non-LBP
Terra Nova-Bay	2	3	Shelf	Wood	White	Intact	0.8	Non-LBP
Terra Nova-Bay	2	4	Shelf	Metal	White	Fair	0.0	Non-LBP
Terra Nova-Bay	2	5	Shelf	Metal	Purple	Fair	1.4	LBP
Terra Nova-Bay	2	6	Shelf	Wood	Gray	Intact	0.0	Non-LBP
Terra Nova-Bay	3		Door	Metal	White	Intact	0.0	Non-LBP
Terra Nova-Bay	3		Door Case	Metal	White	Intact	0.0	Non-LBP
Terra Nova-Bay	3		Wall	Cinderblock	White	Poor	0.0	Non-LBP
Terra Nova-Bay	3		Column	Brick	White	Poor	0.0	Non-LBP
Terra Nova-Bay	4		Wall	Cinderblock	White	Intact	0.1	Non-LBP
Terra Nova-Bay	4		Column	Brick	White	Intact	0.0	Non-LBP
Terra Nova-Bay	4		Wall	Cinderblock	White	Intact	0.0	Non-LBP
Terra Nova-Bay	4	2	Window Sash	Metal	White	Fair	0.1	Non-LBP
Terra Nova-Bay	4	3	Window Sash	Metal	White	Fair	0.1	Non-LBP
Terra Nova-Bay	2		Baseboard	Wood	Gray	Intact	0.0	Non-LBP
Terra Nova-Office	1		Door	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	1		Door Case	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	1		Baseboard	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	1		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova - Office	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova - Office	2		Baseboard	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	2		Door	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	2		Door Case	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	3		Baseboard	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	3		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova - Office	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova - Office	4		Wall	Sheetrock	White	Intact	0.0	Non-LBP

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Terra Nova - Office	4		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova - Office	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova - Office	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova - Office	4		Baseboard	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	4		Door	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	4		Door Case	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	4	1	Window Jamb	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Office	4	2	Window Jamb	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Closet 1	3		Peg Board	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Closet 1	3		Wall	Cinderblock	White	Intact	0.0	Non-LBP
Terra Nova - Closet 1	2		Peg Board	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Closet 2	3		Wall	Cinderblock	White	Intact	0.0	Non-LBP
Terra Nova Bathroom	1		Upper Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova	2		Upper Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova	3		Upper Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova	4		Upper Wall	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Terra Nova - Closet 3	-		Ceiling	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Closet 3	1		Wall	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Closet 3	3		Wall	Wood	White	Intact	0.0	Non-LBP
Terra Nova - Closet 3	2	2	Column	Metal	White	Intact	3.3	LBP
Primo Auto Body-Exterior	2		Wall	Brick	Gray	Intact	0.0	Non-LBP
Primo Auto Body-Exterior	2	1	Door Case	Metal	Gray	Fair	0.6	Non-LBP
Primo Auto Body-Exterior	2	2	Door Case	Metal	Gray	Poor	0.0	Non-LBP
Primo Auto Body-Exterior	2	2	Door	Metal	Gray	Fair	0.0	Non-LBP
Primo Auto Body-Bay 1	1		Wall	Brick	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	1		Beam	Metal	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	1		Column	Cement	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	1	2	Door Case	Wood	Gray	Poor	0.2	Non-LBP
Primo Auto Body-Bay 1	1	2	Door Case	Wood	White	Poor	0.3	Non-LBP
Primo Auto Body-Bay 1	2		Lower Wall	Cement	Gray	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2		Wall	Cement	White	Fair	0.0	Non-LBP
Primo Auto Body-Bay 1	2		Electric Box	Metal	Gray	Fair	0.0	Non-LBP
Primo Auto Body-Bay 1	2	1	Panel	Sheetrock	Gray	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	1	Panel	Sheetrock	White	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	1	Column	Brick	Gray	Fair	0.0	Non-LBP
Primo Auto Body-Bay 1	2	1	Column	Metal	Gray	Fair	0.0	Non-LBP
Primo Auto Body-Bay 1	2	1	Column	Metal	White	Fair	0.1	Non-LBP
Primo Auto Body-Bay 1	2	2	Panel	Sheetrock	White	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	2	Panel	Sheetrock	Gray	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	3	Panel	Sheetrock	Grav	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	3	Panel	Sheetrock	White	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	4	Panel	Sheetrock	White	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	4	Panel	Sheetrock	Grav	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	5	Panel	Sheetrock	Gray	Poor	0.0	Non-LBP

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Primo Auto Body-Bay 1	2	5	Panel	Sheetrock	White	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	6	Panel	Sheetrock	White	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	2	Column	Brick	Gray	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	2	2	Column	Metal	Gray	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	2	Column	Metal	White	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	3	Column	Metal	Gray	Poor	0.1	Non-LBP
Primo Auto Body-Bay 1	2	3	Column	Brick	Gray	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	2	4	Column	Metal	Gray	Fair	0.1	Non-LBP
Primo Auto Body-Bay 1	2	4	Column	Metal	White	Fair	0.0	Non-LBP
Primo Auto Body-Bay 1	2	5	Column	Cement	Gray	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	2	5	Column	Cement	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	2		Upper Wall	Cement	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	3		Beam	Metal	White	Fair	0.0	Non-LBP
Primo Auto Body-Bay 1	3		Wall	Cinderblock	White	Fair	0.0	Non-LBP
Primo Auto Body-Bay 1	4		Wall	Cinderblock	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	4		Wall	Cinderblock	Gray	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	4		Panel	Wood	Gray	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	4		Door Case	Metal	Gray	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	4		Lower Wall	Sheetrock	Gray	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	4		Upper Wall	Sheetrock	White	Poor	0.0	Non-LBP
Primo Auto Body-Bay 1	4		Upper Wall	Sheetrock	Green	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	4		Molding	Wood	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	-		Column	Metal	Blue	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	2		Pipe	Metal	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	2		Beam	Metal	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 2	1	1	Door	Wood	Light Green	Fair	0.0	Non-LBP
Primo Auto Body-Bay 2	1	1	Door Case	Wood	Light Green	Intact	0.0	Non-LBP
Primo Auto Body-Bay 2	1		Wall	Sheetrock	White	Fair	0.0	Non-LBP
Primo Auto Body-Bay 2	1	2	Door Case	Metal	Gray	Intact	0.0	Non-LBP
Primo Auto Body-Bay 2	1		Pipe	Metal	Black	Intact	0.0	Non-LBP
Primo Auto Body-Bay 2	2		Wall	Cinderblock	Gray	Intact	0.0	Non-LBP
Primo Auto Body-Bay 2	2		Wall	Cinderblock	White	Fair	0.0	Non-LBP
Primo Auto Body-Bay 2	2	1	Column	Cinderblock	White	Fair	0.0	Non-LBP
Primo Auto Body-Bay 2	2	2	Column	Cinderblock	White	Fair	0.0	Non-LBP
Primo Auto Body-Bay 2	3		Door Case	Metal	Gray	Intact	0.0	Non-LBP
Primo Auto Body-Bay 2	4		Wall	Plaster	White	Fair	0.0	Non-LBP
Primo Auto Body-Bay 2	4		Wall	Plaster	White	Fair	0.0	Non-LBP
Primo Auto Body-Bay 2	4		Cabinet	Metal	White	Fair	0.0	Non-LBP
Primo Auto Body-Bathroom	1		Upper Wall	Sheetrock	Green	Fair	0.0	Non-LBP
Primo Auto Body-Bathroom	2		Upper Wall	Sheetrock	Green	Fair	0.0	Non-LBP
Primo Auto Body-Bathroom	3		Upper Wall	Sheetrock	Green	Fair	0.0	Non-LBP
Primo Auto Body-Bathroom	4		Upper Wall	Sheetrock	Green	Fair	0.0	Non-LBP
Primo Auto Body-Bathroom	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Primo Auto Body-Bathroom	1		Door	Wood	Light Green	Fair	0.0	Non-LBP
Primo Auto Body-Bathroom	1		Door Jamb	Wood	Light Green	Intact	0.0	Non-LBP
Primo Auto Body- Storage Space	1		Wall	Sheetrock	Peach	Fair	0.0	Non-LBP
Primo Auto Body- Storage Space	2		Wall	Sheetrock	Peach	Fair	0.0	Non-LBP
Primo Auto Body- Storage Space	3		Wall	Sheetrock	Peach	Fair	0.0	Non-LBP
Primo Auto Body- Storage Space	4		Wall	Sheetrock	Peach	Fair	0.0	Non-LBP
Primo Auto Body- Storage Space	3		Shelf	Wood	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	4		Door	Wood	White	Intact	0.0	Non-LBP
Primo Auto Body-Bay 1	4		Door Case	Wood	White	Intact	0.0	Non-LBP
Primo Auto Body-Office	1		Door Case	Wood	White	Intact	0.0	Non-LBP
Primo Auto Body-Office	1		Door	Wood	White	Intact	0.0	Non-LBP
Primo Auto Body-Office	1		Wall	Sheetrock	Green	Intact	0.0	Non-LBP
Primo Auto Body-Office	1		Wall	Sheetrock	Peach	Poor	0.0	Non-LBP
Primo Auto Body-Office	2		Wall	Sheetrock	Peach	Intact	0.0	Non-LBP
Primo Auto Body-Office	3		Wall	Sheetrock	Green	Intact	0.0	Non-LBP
Primo Auto Body-Office	4		Wall	Sheetrock	Peach	Intact	0.0	Non-LBP
Primo Auto Body-Office	3		Shelf	Sheetrock	Peach	Poor	0.0	Non-LBP
Primo Auto Body-Office	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Primo Auto Body-Office	1		Window Case	Wood	White	Intact	0.0	Non-LBP
Primo Auto Body-Office	2		Window Case	Wood	White	Intact	0.0	Non-LBP
Primo Auto Body-Office	-		Pipe	Metal	White	Intact	0.0	Non-LBP

4.2 LEAD-BASED PAINT INSPECTION DATA – 11-27 IRVING AVENUE, QUEENS, NY – LOT 44

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Exterior	1		Panel	Metal	Gray	Poor	0.0	Non-LBP
Exterior	1	1	Door	Metal	Gray	Fair	0.0	Non-LBP
Exterior	1	1	Door Case	Metal	Gray	Fair	0.0	Non-LBP
Exterior	1	2	Door Case	Metal	Blue	Fair	0.0	Non-LBP
Exterior	1	2	Door Case	Metal	Yellow	Fair	0.0	Non-LBP
Exterior	1		Wall	Cement	Gray	Poor	0.0	Non-LBP
Exterior	1		Upper Wall	Brick	Gray	Intact	0.0	Non-LBP
Exterior	1	1	Fence	Metal	Blue	Poor	0.0	Non-LBP
Exterior	1	2	Fence	Metal	Blue	Poor	0.0	Non-LBP
Bay	1	2	Door	Metal	Blue	Intact	0.0	Non-LBP
Bay	2		Pipe	Metal	Black	Intact	0.0	Non-LBP
Bay	2		Shelf	Metal	Yellow	Poor	0.0	Non-LBP
Bay	3		Wall	Cinderblock	Gray	Intact	0.0	Non-LBP
Bay	=		Column	Metal	Blue	Intact	0.0	Non-LBP
Bay	-		Floor	Metal	Gray	Poor	0.0	Non-LBP
Hallway	1		Door	Metal	Gray	Intact	0.0	Non-LBP
Hallway	1		Door Case	Metal	Gray	Intact	0.0	Non-LBP
Hallway	4		Wall	Cinderblock	Black	Intact	0.0	Non-LBP

4.2 LEAD-BASED PAINT INSPECTION DATA – 11-25 IRVING AVENUE, QUEENS, NY – LOT 46

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Exterior	2		Wall	Brick	Purple	Poor	0.1	Non-LBP
Exterior	-		Lightpost	Metal	Purple	Poor	0.6	Non-LBP
Exterior	1		Fence	Metal	Black	Intact	0.0	Non-LBP
Exterior	1		Fence	Metal	Peach	Intact	0.0	Non-LBP
Exterior	1		Wall	Brick	Peach	Intact	0.1	Non-LBP
Exterior	1	1	Door Case	Metal	Peach	Intact	0.0	Non-LBP
Exterior	1	1	Door	Metal	Gray	Fair	0.0	Non-LBP
Exterior	1	2	Door	Wood	White	Intact	0.0	Non-LBP
Exterior	1	2	Door Case	Wood	White	Intact	0.0	Non-LBP
Exterior	1		Window Sash	Wood	White	Intact	0.0	Non-LBP
Exterior	1		Window Case	Metal	Black	Fair	0.0	Non-LBP
Office	1		Window Sash	Wood	White	Intact	0.0	Non-LBP
Office	1		Door	Wood	White	Intact	0.0	Non-LBP
Office	1		Door Case	Wood	White	Intact	0.0	Non-LBP
Office	1		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Office	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Office	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Office	4		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Office	3		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Office	3		Door	Wood	White	Intact	0.0	Non-LBP
Office	3		Door Case	Wood	White	Intact	0.0	Non-LBP
Office	3		Baseboard	Wood	White	Intact	0.0	Non-LBP
Office	2		Baseboard	Wood	White	Intact	0.0	Non-LBP
Office	4		Baseboard	Wood	White	Intact	0.0	Non-LBP
Exterior	1	2	Door	Metal	Silver	Intact	0.0	Non-LBP
Exterior	1	3	Door	Metal	Silver	Intact	0.0	Non-LBP
Exterior	1	3	Door Case	Metal	Black	Poor	0.0	Non-LBP
Exterior	1	4	Door Case	Metal	Black	Poor	0.0	Non-LBP
Exterior	1		Wall	Brick	Gray	Intact	0.0	Non-LBP
Tire Storage	1	1	Door	Metal	Silver	Intact	0.0	Non-LBP
Tire Storage	1	2	Door	Metal	Silver	Intact	0.0	Non-LBP
Tire Storage	1		Beam	Metal	Gray	Intact	0.0	Non-LBP
Tire Storage	1		Upper Wall	Brick	Gray	Poor	0.0	Non-LBP
Tire Storage	3		Wall	Brick	White	Poor	0.4	Non-LBP
Tire Storage	3		Wall	Brick	Gray	Poor	2.8	Positive
Tire Storage	2		Door	Wood	White	Intact	0.0	Non-LBP
Bathroom	1		Door	Wood	White	Intact	0.0	Non-LBP
Bathroom	2		Door	Wood	White	Intact	0.0	Non-LBP
Bathroom	2		Door Case	Wood	White	Intact	0.0	Non-LBP
Bathroom	1		Door Jamb	Wood	White	Intact	0.0	Non-LBP
Bathroom	1		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Bathroom	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Bathroom	-		Ceiling	Sheetrock	White	Poor	0.0	Non-LBP
Bathroom	3		Wall	Brick	White	Fair	0.0	Non-LBP
Bathroom	4		Wall	Brick	White	Intact	0.0	Non-LBP
Tire Storage	1	1	Pipe	Metal	Black	Poor	0.0	Non-LBP
Tire Storage	1	2	Pipe	Metal	White	Poor	0.1	Non-LBP
Tire Storage	1		Panel	Metal	Silver	Intact	0.0	Non-LBP
Deli	1		Wall	Metal	Gray	Intact	0.0	Non-LBP
Deli	1		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Deli	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Deli	3		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Deli	3		Wall	Sheetrock	Blue	Intact	0.0	Non-LBP
Deli	4		Wall	Sheetrock	Blue	Intact	0.0	Non-LBP
Deli	-	1	Column	Sheetrock	Blue	Intact	0.0	Non-LBP
Deli	-	2	Column	Sheetrock	Blue	Intact	0.0	Non-LBP
Deli	3		Door	Wood	White	Intact	0.0	Non-LBP
Deli	3		Door Case	Wood	White	Intact	0.0	Non-LBP
Deli	4		Door Case	Wood	White	Intact	0.0	Non-LBP
Deli	4		Door	Wood	White	Intact	0.0	Non-LBP
Deli	4		Column	Wood	White	Intact	0.0	Non-LBP
Deli	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Deli	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Storage Space	1		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Storage Space	1		Divider	Sheetrock	White	Intact	0.0	Non-LBP
Storage Space	2		Wall	Wood	White	Intact	0.0	Non-LBP
Storage Space	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Storage Space	3		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Storage Space	4		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Storage Space	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Storage Space	1	1	Door Case	Wood	White	Intact	0.0	Non-LBP
Storage Space	1	2	Door Case	Wood	White	Intact	0.0	Non-LBP
Storage Space	1	2	Door	Wood	White	Intact	0.0	Non-LBP
Storage Space	2	1	Pipe	Metal	White	Fair	0.0	Non-LBP
Storage Space	2	2	Pipe	Metal	Black	Intact	0.0	Non-LBP
Storage Space	-	1	Beam	Wood	White	Intact	0.0	Non-LBP
Storage Space	-	2	Beam	Wood	White	Intact	0.0	Non-LBP
Storage Space	-	3	Beam	Wood	White	Intact	0.0	Non-LBP
Storage Space	-	4	Beam	Metal	White	Intact	0.1	Non-LBP
Storage Space	-	1	Column	Metal	White	Intact	0.0	Non-LBP
Storage Space	-	2	Column	Metal	White	Intact	0.0	Non-LBP
Storage Space	-	3	Column	Metal	White	Intact	0.0	Non-LBP
Storage Space	-	4	Column	Metal	White	Intact	0.0	Non-LBP
Storage Space	<u> </u>	5	Column	Concrete	White	Intact	4.4	LBP
Storage Space	-	6	Column	Metal	White	Intact	0.0	Non-LBP
Storage Space	-	7	Column	Metal	White	Intact	3.9	LBP
Storage Space	2	'	Hatch Door	Wood	White	Intact	0.0	Non-LBP

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Utility Room	2		Wall	Brick	White	Fair	0.0	Non-LBP
Utility Room	2		Wall	Brick	Black	Fair	0.0	Non-LBP
Utility Room	4		Wall	Brick	Silver	Intact	0.0	Non-LBP
Utility Room	4	1	Electric Box	Metal	Black	Fair	0.0	Non-LBP
Utility Room	4	2	Electric Box	Metal	Black	Fair	0.0	Non-LBP
Utility Room	4	3	Electric Box	Metal	Gray	Intact	0.0	Non-LBP
Utility Room	4	4	Electric Box	Metal	Gray	Intact	0.0	Non-LBP
Utility Room	4	5	Electric Box	Metal	Gray	Intact	0.0	Non-LBP
Utility Room	4	6	Electric Box	Metal	Gray	Intact	0.0	Non-LBP
Utility Room	4	2	Pipe	Metal	Black	Intact	0.0	Non-LBP
Utility Room	4	3	Pipe	Metal	Gray	Fair	0.0	Non-LBP
Utility Room	-	1	Column	Metal	Black	Poor	0.0	Non-LBP
Utility Room	-	2	Column	Metal	Black	Poor	0.0	Non-LBP
Utility Room	_	3	Column	Metal	Red	Poor	0.1	Non-LBP
Utility Room	_	4	Column	Metal	Orange	Poor	2.2	LBP
Utility Room	_	5	Column	Metal	Black	Poor	0.0	Non-LBP
Utility Room	_	6	Column	Concrete	Black	Fair	0.0	Non-LBP
Utility Room	_	7	Column	Metal	Black	Poor	0.0	Non-LBP
Utility Room	_	8	Column	Metal	Black	Intact	0.0	Non-LBP
Utility Room	_	9	Column	Metal	Orange	Poor	4.5	LBP
Utility Room	_	10	Column	Metal	Black	Poor	0.0	Non-LBP
Utility Room	_	11	Column	Metal	Black	Poor	0.0	Non-LBP
Utility Room	_	12	Column	Metal	Black	Poor	0.0	Non-LBP
Utility Room	_	13	Column	Metal	Black	Poor	0.0	Non-LBP
Utility Room	_	14	Column	Metal	Orange	Poor	1.7	LBP
Utility Room	-	15	Column	Metal	Black	Poor	0.0	Non-LBP
Utility Room	_	16	Column	Metal	Orange	Poor	2.2	LBP
Utility Room	-	17	Column	Metal	Black	Poor	0.0	Non-LBP
Utility Room	4	1	Pipe	Metal	Gray	Poor	0.0	Non-LBP
Utility Room	3		Column	Metal	Black	Intact	0.0	Non-LBP
Utility Room	4		Door Case	Metal	Silver	Fair	3.0	LBP
Utility Room	4		handrail	Metal	Silver	Fair	0.1	Non-LBP
Utility Room	4		Door Jamb	Wood	Green	Poor	0.5	Non-LBP
Utility Room	4		Hatch Door	Metal	Silver	Intact	0.0	Non-LBP
Bathroom	1		Door	Wood	White	Intact	0.0	Non-LBP
Bathroom	1		Door Case	Wood	White	Intact	0.0	Non-LBP
Bathroom	1		Upper Wall	Sheetrock	White	Intact	0.0	Non-LBP
Bathroom	2		Upper Wall	Sheetrock	White	Intact	0.0	Non-LBP
Bathroom	3		Upper Wall	Sheetrock	White	Intact	0.0	Non-LBP
Bathroom	4		Upper Wall	Sheetrock	White	Intact	0.0	Non-LBP
Bathroom	 		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Exterior	1		Lower Wall	Cement	Beige	Intact	0.0	Non-LBP
Exterior	1		Door Case	Metal	Silver	Intact	0.0	Non-LBP
Exterior	1		handrail	Metal	Silver	Intact	0.0	Non-LBP
Exterior	2		Wall	Plaster	Gray	Fair	0.0	Non-LBP

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Exterior	2		Hatch Door	Metal	Silver	Intact	0.0	Non-LBP
Exterior	2		Wall	Ceramic	Beige	unpainted	0.0	Non-LBP
Exterior	2		Pipe	Metal	Light Green	Poor	0.6	Non-LBP

In addition to the above testing via XRF analyzer, paint chip samples were collected from metal components which tested psoitvie for lead-based paint and analyzed for confirmation of lead-based paint content. The results of the components identified to contain lead-based paint via XRF analyzer are listed below with the paint chip results listed next to the XRF result:

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	XRF Reading	Paint Chip Result	Classification
Terra Nova - Closet 3	2	2	Column	Metal	White	Intact	3.3	0.992 % by Weight	LBP
Terra Nova-Bay	2	5	Shelf	Metal	Purple	Fair	1.4	1.198 % by Weight	LBP

4.2 LEAD-BASED PAINT INSPECTION DATA - 15-14 COOPER AVENUE, QUEENS, NY - LOT 48

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Office	1		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Office	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Office	3		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Office	4		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Office	4		Door	Wood	White	Intact	0.0	Non-LBP
Office	4		Door Case	Wood	White	Intact	0.0	Non-LBP
Office	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Office	3		Door Case	Wood	White	Intact	0.0	Non-LBP
Office	3		Door	Wood	White	Intact	0.0	Non-LBP
Bathroom	1		Door	Wood	White	Intact	0.0	Non-LBP
Bathroom	1		Door Case	Wood	White	Intact	0.0	Non-LBP
Bathroom	1		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Bathroom	2		Wall	Ceramic	White	Intact	0.0	Non-LBP
Bathroom	3		Wall	Ceramic	White	Intact	0.0	Non-LBP
Bathroom	4		Wall	Ceramic	White	Intact	0.0	Non-LBP
Bathroom	-		Floor	Ceramic	White	Intact	0.1	Non-LBP
Bathroom	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Bathroom	3		Window Case	Metal	White	Fair	0.0	Non-LBP
Storage Space	1		Wall	Cinderblock	White	Intact	0.1	Non-LBP
Storage Space	2		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Storage Space	3		Wall	Cinderblock	White	Intact	0.2	Non-LBP
Storage Space	4		Wall	Cinderblock	White	Intact	0.1	Non-LBP
Storage Space	4		Door Case	Metal	White	Intact	0.2	Non-LBP
Storage Space	1		Door Case	Wood	White	Intact	0.0	Non-LBP
Storage Space	1		Door	Wood	White	Intact	0.0	Non-LBP
Storage Space	2		Door	Wood	White	Intact	0.0	Non-LBP
Storage Space	2		Door Case	Wood	White	Intact	0.0	Non-LBP
Storage Space	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Storage Space	-		Electric Conduit	Metal	White	Intact	0.0	Non-LBP
Storage Space	3		Panel	Wood	White	Intact	0.0	Non-LBP
Bathroom	1		Wall	Sheetrock	White	Intact	0.0	Non-LBP
Bathroom	2		Wall	Cinderblock	White	Poor	0.0	Non-LBP
Bathroom	3		Wall	Cinderblock	White	Poor	0.0	Non-LBP
Bathroom	4		Wall	Cinderblock	White	Poor	0.1	Non-LBP
Bathroom	-		Ceiling	Sheetrock	White	Intact	0.0	Non-LBP
Bathroom	1		Door	Wood	White	Intact	0.0	Non-LBP
Bathroom	1		Door Case	Wood	White	Intact	0.0	Non-LBP
Bathroom	2		Shelf Support	Metal	White	Intact	0.0	Non-LBP
Bathroom	2		Shelf	Wood	White	Intact	0.0	Non-LBP
Bathroom	2		Electric Conduit	Wood	White	Intact	0.0	Non-LBP
Bathroom	4		Electric Conduit	Wood	White	Fair	0.0	Non-LBP
Bay	1		Wall	Brick	White	Intact	0.0	Non-LBP

Room/ Location	Wall	Unit	Component	Substrate	Color	Condition	Reading	Classification
Bay	1	51.II.	Wall	Brick	White	Intact	0.0	Non-LBP
Bay	2		Wall	Cinderblock	White	Intact	0.1	Non-LBP
Bav	2		Wall	Cinderblock	White	Intact	0.7	Non-LBP
Bay	3		Wall	Cinderblock	White	Poor	0.2	Non-LBP
Bav	3		Wall	Cinderblock	White	Poor	0.1	Non-LBP
Bay	4		Wall	Cinderblock	White	Intact	0.1	Non-LBP
Bay	4		Wall	Cinderblock	White	Intact	0.0	Non-LBP
Bay	2		Vent Cover	Metal	White	Fair	0.0	Non-LBP
Bay	2	1	Door Case	Metal	Red	Fair	0.0	Non-LBP
Bay	2		Window Case	Metal	Red	Intact	0.0	Non-LBP
Bay	2	1	Pipe	Metal	White	Intact	0.0	Non-LBP
Bay	2	2	Pipe	Metal	White	Intact	0.0	Non-LBP
Bay	2	3	Pipe	Metal	White	Intact	0.0	Non-LBP
Bay	2	4	Pipe	Metal	White	Intact	0.0	Non-LBP
Bay	2	5	Pipe	Metal	White	Intact	0.1	Non-LBP
Bay	2	6	Pipe	Metal	White	Intact	0.1	Non-LBP
Bay	3		Column	Brick	White	Intact	0.1	Non-LBP
Bay	2		Baseboard	Concrete	Gray	Fair	0.3	Non-LBP
Bay	-		Floor	Concrete	Red	Poor	0.0	Non-LBP
Bay	-		Floor	Concrete	Red	Poor	0.0	Non-LBP
Bay	-		Ceiling	Sheetrock	White	Fair	0.0	Non-LBP
Bay	-		Ceiling	Sheetrock	White	Fair	0.0	Non-LBP
Bay	-		Beam	Metal	White	Fair	0.0	Non-LBP
Bay	1		Beam	Metal	White	Poor	0.0	Non-LBP
Bay	1		Beam	Wood	White	Poor	0.0	Non-LBP
Bay	4		Pipe	Metal	White	Fair	0.0	Non-LBP
Exterior	2		Wall	Cinderblock	White	Poor	6.2	LBP
Exterior			Wall	Cinderblock	Purple	Intact	5.8	LBP
Exterior	1		Wall	Cinderblock	Purple	Intact	3.5	LBP
Exterior	1		Wall	Brick	Purple	Intact	0.0	Non-LBP
Exterior	1	1	Window Apron	Cement	Purple	Poor	0.5	Non-LBP
Exterior	1	2	Window Apron	Cement	Purple	Poor	0.2	Non-LBP
Exterior	1	1	Window Case	Metal	Brown	Intact	0.0	Non-LBP
Exterior	1	2	Window Case	Metal	Red	Intact	0.0	Non-LBP
Exterior	1	1	Door Case	Metal	Red	Poor	0.0	Non-LBP
Exterior	1	1	Door Case	Metal	Gray	Poor	0.0	Non-LBP
Exterior	1	2	Door Case	Metal	Gray	Fair	0.0	Non-LBP
Exterior	1	2	Door Case	Metal	Red	Fair	0.1	Non-LBP
Exterior	1	2	Door Case	Metal	Purple	Intact	0.0	Non-LBP
Exterior	1	3	Door Case	Metal	Yellow	Poor	0.0	Non-LBP
Exterior	1	4	Door Case	Metal	Yellow	Poor	0.0	Non-LBP
Exterior	1	3	Door Case	Metal	Gray	Fair	0.0	Non-LBP
Exterior	1	4	Door Case	Metal	Gray	Fair	0.0	Non-LBP
Exterior	1	4	Door	Metal	Gray	Fair	0.0	Non-LBP

4.3 HAZARDOUS MATERIALS SURVEY DATA – ALL BUILDINGS

LOCATION	ITEM OF ENVIRONMENTAL CONCERN	SIZE	QUANTITY	COMMENT
	THROUGHOUT	ALL BUIL	DINGS	
THROUGHOUT INTERIOR	FLUORESCENT LIGHT FIXTURE BALLASTS	N/A	N/A	Non-PCB – Limited Visual inspection of light fixture ballasts revealed that light ballasts are labeled as non-PCB containing by manufacturer.
	11-33 IRVING AVENUE,	QUEENS	, NY – LOT 3	3
THROUGHOUT	SUSPECT MERCURY CONTAINING FLOURESCENT LIGHT BULBS	4 FT.	68	See Note 2
INTERIOR	ELECTRIC WALL THERMOSTATS	6 IN.	4	See Note 2
	11-29 IRVING AVENUE,	QUEENS	, NY – LOT 42	2
TERRANOVA - THROUGHOUT INTERIOR	SUSPECT MERCURY CONTAINING FLOURESCENT LIGHT BULBS	4 FT.	40	See Note 2
PRIMO AUTO BODY -	FLOURESCENT LIGHT BALLASTS	N/A	40	See Notes 1
THROUGHOUT INTERIOR	SUSPECT MERCURY CONTAINING FLOURESCENT LIGHT BULBS	4 FT.	40	See Note 2
	11-27 IRVING AVENUE,	QUEENS	, NY – LOT 44	4
THROUGHOUT	SUSPECT MERCURY CONTAINING	2 FT.	6	See Note 2
INTERIOR	FLOURESCENT LIGHT BULBS	4 FT.	10	See Note 2
	11-25 IRVING AVENUE,	QUEENS	, NY – LOT 40	3
THROUGHOUT -		2 FT.	6	See Note 2
PRIMO FLAT FIX	SUSPECT MERCURY CONTAINING FLOURESCENT LIGHT BULBS	4 FT.	10	See Note 2
THROUGHOUT – DELI STORE		2 FT.	30	See Note 2
	15-14 COOPER AVENUE	, QUEEN	S, NY – LOT 4	18
THROUGHOUT INTERIOR	SUSPECT MERCURY CONTAINING FLOURESCENT LIGHT BULBS	4 FT.	24	See Note 2

Notes:

- 1. Two (2) capacitors were presumed to be associated with each fluorescent light fixture.
- 2. Each fluorescent light bulb and thermostat was presumed to contain mercury.

5.0 CONCLUSIONS AND RECOMMENDATIONS

Asbestos containing materials and Assumed-asbestos-containing materials, lead-based paint and assumed lead-based paint components and suspect hazardous materials have been identified during this survey.

In the event that any concealed ACM, LBP or other hazardous materials are identified and to be disturbed by the proposed renovation work, proper procedures shall be implemented prior to the commencement of such work. All asbestos and lead abatement work shall be performed in accordance with all applicable Federal, State and Local rules and regulations. The abatement project shall be filed with all agencies having jurisdiction over this project, such as USEPA, NYSDOL, and NYCDEP. All waste generated by the abatement of asbestos containing materials, lead-based paint containing materials and hazardous materials shall be disposed of in accordance with current applicable Federal, State and Local rules and regulations.

6.0 AREAS NOT ACCESSIBLE

Athenica Environmental Services, Inc. inspected and sampled materials, which were observable and accessible to the survey team. It is possible, however, that additional suspect ACM, LBP or hazardous materials may exist inside concealed spaces, which were not accessible without using destructive means.

Athenica Environmental Services, Inc. certifies that the information contained herein is based on the physical and visual inspections conducted by Athenica Environmental Services, Inc. and data collected during the inspection survey.

During our site visits, access to the 2nd floor areas including 2nd floor roof of 11-25 Irving Avenue, Queens, NY was not granted, therefore It was assumed that suspect asbestos containing materials and lead-based paint are present.

7.0 REPORT CERTIFICATIONS

Athenica Environmental Services, Inc. certifies that the information contained herein is based on the physical and visual inspections conducted by Athenica and data collected during the inspection survey.

NYSCOASSISTERIOS Inspector/

NYC DEP Asbestos Investigator

Juraj Bardiovsky

Project Manager/ NYS DOL Asbestos

Inspector/ Project Designer

APPENDIX A

8.0 Analytical Results, Chain-of-Custody Forms and Certificates of Laboratory Analysis



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104 Ph.: (718) 389 3470, Fax: (718) 389 3471

BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

|--|

ANALYTICAL RESULTS

				2		
CLIENT ID# LABORATORY ID#	STEREO MICROSCOP' RESULTS	OPPY	SAMPLE DESCRIPTION	FIBROUS	NON FIBROUS MATERIAL	% ASBESTOS AND
						TYPE
01	COLOR	Brown	Brick Mortar, Interior - Basement	%0	100%	NAD
15-12-029-01	# LAYERS	-				
	SCAN					
02	COLOR	Brown	Brick Mortar, Interior - Basement	%0	100%	NAD
15-12-029-02	# LAYERS	1				
	SCAN					
03	COLOR	Brown	Brick Mortar, Interior - Basement	%0	100%	NAD
15-12-029-03	# LAYERS	1		h		
	SCAN					
04	COLOR	White	White Coating on Bricks, Interior –	%0	100%	NAD
15-12-029-04	# LAYERS	1	Basement			
	SCAN					
05	COLOR	White	White Coating on Bricks, Interior -	%0	100%	NAD
15-12-029-05	# LAYERS	-	Basement			
	SCAN					
90	COLOR	White/Brown	Wall Sheetrock, Interior - Basement	3%CELL	%16	NAD
15-12-029-06	#LAYERS	2				
	SCAN					



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104
Ph.: (718) 389 3470, Fax: (718) 389 3471

BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 11104 PROJECT: 11-25 Irving Ave	PROJECT: 11-25 Irving Ave
DATE OF ANALYSIS: 12/04/15	DATE OF REPORT: 12/08/15

ANALYTICAL RESULTS

CLIENT ID#	STEREO		SAMPLE DESCRIPTION	FIBROUS	NON	%
LABORATORY ID#	MICROSCOPY RESULTS	OPY		MATERIAL	FIBROUS	ASBESTOS AND TYPE
07	COLOR	White/Brown	Wall Sheetrock, Interior – 1st Floor	30%CELL	%02	NAD
15-12-029-07	# LAYERS	2				
	SCAN					
80	COLOR	White/Brown	Ceiling Sheetrock, Interior – 1 st	10%CETL	%06	NAD
15-12-029-08	# LAYERS	2	Floor			
	SCAN					
60	COLOR	White/Brown	Ceiling Sheetrock, Interior –	15%CELL	85%	NAD
15-12-029-09	# LAYERS	2	Basement			
	SCAN					
10	COLOR	Brown	Beam Plaster/Cement, Interior –	%0	100%	NAD
15-12-029-10	# LAYERS	1	Basement			
	SCAN					
11	COLOR	Gray	Beam Plaster/Cement, Interior –	%0	100%	NAD
15-12-029-11	# LAYERS	1	Basement			
	SCAN					
12	COLOR	Gray	Beam Plaster/Cement, Interior -	%0	100%	NAD
15-12-029-12	# LAYERS	- 1	Basement			
	SCAN					



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104
Ph.: (718) 389 3470, Fax: (718) 389 3471

BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

ROJECT: 11-25 Irving Ave	DATE OF REPORT: 12/08/15
CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 11104 PRO.	DATE OF ANALYSIS: 12/04/15

ANALVTICAL RESILTS

2000 日曜人

CLIENT ID# LABORATORY ID#	STEREO MICROSCOPY RESULTS	OPY	SAMPLE DESCRIPTION	FIBROUS	NON FIBROUS MATERIAL	% ASBESTOS AND TVDE
13	COLOR	Light Brown	Ceramic Floor Tile Grout, Interior –	%0	100%	CAN
15-12-029-13	# LAYERS	I	Ground Floor Front Deli			TON TON
	SCAN					
14	COLOR	Light Brown	Ceramic Floor Tile Grout, Interior –	%0	100%	NAD
15-12-029-14	# LAYERS	1	Ground Floor Front Deli			
	SCAN					
15	COLOR	Gray	Ceramic Floor Tile Setting Cement,	%0	100%	NAN
15-12-029-15	# LAYERS	1	Interior - Ground Floor Front Deli			
	SCAN					
16	COLOR	Gray	Ceramic Floor Tile Setting Cement,	%0	100%	NAD
15-12-029-16	# LAYERS	1	Interior - Ground Floor Front Deli			
	SCAN					
17	COLOR	Brown	Ceramic Wall Tile Grout, Interior -	%0	100%	NAN
15-12-029-17	# LAYERS	1	Ground Floor Front Deli, Toilet	9		
	SCAN					
81	COLOR	Brown	Ceramic Wall Tile Grout, Interior –	%0	100%	NAD
15-12-029-18	# LAYERS	1	Ground Floor Front Deli, Toilet			
	SCAN					



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104 Ph.: (718) 389 3470, Fax. (718) 389 3471

BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

PROJECT: 11-25 Irving Ave	The state of the s	DATE OF DEPODT. 12/00/15	LATE OF INT. 12/00/13
CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 11104 PROJECT: 11-25 Irving Ave	DAMP OF ATTACACH	DATE OF ANALYSIS: 12/04/15	

ANALYTICAL RESULTS

14 Aug. 1

CLIENT ID# LABORATORY	STEREO MICROSCOPY	OPY	SAMPLE DESCRIPTION	FIBROUS	NON	% SOTSTOR
D#	RESULTS				MATERIAL	AND TYPE
19	COLOR	Brown/White	Ceramic Wall Tile Setting Cement,	%0	100%	NAN
15-12-029-19	# LAYERS	2	Interior - Ground Floor Front Deli,			
	SCAN		Toilet			
20	COLOR	Brown/White	Ceramic Wall Tile Setting Cement,	%0	100%	NAD
15-12-029-20	# LAYERS	2	Interior - Ground Floor Front Deli,			
	SCAN		Toilet			
27	COLOR	White	Ceiling Sheetrock, Interior Flat Fix	2%CELL	%86	NAN
15-12-029-27	# LAYERS	I	Shop			
	SCAN					
28	COLOR	White	Ceiling Sheetrock, Interior Flat Fix	5%CELL	95%	CAN
15-12-029-28	# LAYERS	1	Shop			av.
	SCAN					
29	COLOR	Gray/White	Grey Stucco, Exterior	20%FBGL	%08	NAD
15-12-029-29	#LAYERS	2				
	SCAN					
30	COLOR	Gray/White	Grey Stucco, Exterior	5%FBGL	95%	NAD
15-12-029-30	# LAYERS	2				
	SCAN					



LABORATORY TESTING SERVICES INC. LIC, NY 11104 Ph.: (718) 389 3470, Fax: (718) 389 3471 45-09 GREENPOINT AVE.

BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

7. 11.25 Iming Asia	. II-ZJ IIVIIIS AVE	DATE OF DEDODE. 12/09/12	
PROJECT. 1	TOOTE	DATEOR	うとうなら
C: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave. LIC NY 11104	THE COLUMN CANAL	JE ANALY SIS: 12/04/15	
CLIENT	DATE O	DAIL	

In Breitako

C. Gooding

Analyst:

on Bive trahas Laboratory Director:

E. Dimitrakas

- NAD: No Asbestos Detected, CELL: Cellulose, FBGL: Fiberglass, H: Hair, SY: Synthetics, CH: Chrysotile, AMOS: Amosite, TRE: Tremolite, ANTH: Anthophyllite, ACT: Actinolite, CRO: Crocidolite, VERM:
 - Analytical Methodologies: EPA 600/M4-82-020 (Point Count only) and ELAP Method 198.1.
- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

 The liability of Laboratory Testing Services Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104 Ph.: (718) 389 3470, Fax: (718) 389 3471

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

I AROBATOBV DESITTE

	Negat.	Negat.	Negat.	Negat.	Negat.	Negat.
TYPE OF	NA NA	NA	NA	NA	NA	NA
TEM	NAD	NAD	NAD	NAD	NAD	NAD
TYPE OF ASBEST	NA	NA	NA	NA	NA	NA
PLM RESULTS	NAD	NAD	NAD	NAD	NAD	NAD
%AII	27.12	23.68	3.87	5.86	8.22	8.54
%ASI	15.25	21.05	80.65	78.40	74.79	72.76 8.54
%ORG	57.63	55.26	15.48	15.74	17.00	18.70
LOCATION	Mastic Associated w/12x12 Floor Tiles, Behind Counter	Mastic Associated w/12x12 Floor Tiles, Behind Counter	12x12 Floor Tiles (Black), Behind Counter	12x12 Floor Tiles (Black), Behind Counter	12x12 Floor Tiles (Gray), Interior – Ground Floor Front Deli, Behind Counter	12x12 Floor Tiles (Gray), Interior – Ground Floor Front Deli, Behind Counter
LAB. ID #	15-12- 029-21	15-12- 029-22	15-12- 029-23	15-12- 029-24	15-12- 029-25	15-12- 029-26
CLIENT #	21	22	23	24	25	26

LABORATORY DIRECTOR E. Dimitrakas

ANALYST

E. Loukianova

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

NAD: No Asbestos Detected

The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104 Ph.: (718) 389 3470, Fax: (718) 389 3471

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

11.25 f A	11-23 If vilig Ave.	LABORATORY ID #: 15_12_020	170-17-17-17-17	DATE OF REPORT: 12/04/15
CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue 11C NV 11104 PROTECT: 11 25 Leading A.	secondaria de la comercia del la comercia de la comercia de la comercia del la comercia de la comercia del la comercia de la comercia del la comercia de la comercia de la comercia del la comerci	ETHODOLOGIES: ELAP 198.6, ELAP 198.4	DATES OF ANALYSIS: 12/02/15	1313: 12/03/13

-	7
4	
5	Z C E
14	-
TO	
A	LABOR
Ħ	-

POSIT. /	Negat.	Negat.	Negat.	Negat.	Posit.	
TYPE OF	NA	NA	NA	NA	NA	YZED
TEM	NAD	NAD	NAD	NAD	NA	SAMPLE NOT ANALYZED
TYPE OF	NA	NA	NA	NA	Chrys.	SAMPLE
PLM RESULTS	NAD	NAD	NAD	NAD	2.85	
%AII	9.25	5.79	33.46	32.51	28.45	28.17
%ASI	28.77	28.93	25.74	23.22	6.11	4.37
%ORG	61.99	65.29	40.81	44.26	62.60	67.46
LOCATION	Caulking on Gate Silver, Exterior – Flat Fix Shop	Caulking on Gate Silver, Exterior – Flat Fix Shop	Caulking on Gate (Brown), Exterior – Flat Fix Shop	Caulking on Gate (Brown), Exterior – Flat Fix Shop	Tar/Paint on Gate, Exterior – Flat Fix Shop	Tar/Paint on Gate, Exterior – Flat Fix Shop
LAB. ID #	15-12- 029-31	15-12- 029-32	15-12- 029-33	15-12- 029-34	15-12- 029-35	15-12- 029-36
CLIENT #	31	32	33	34	35	36

LABORATORY DIRECTOR E. Dimitrakas

ANALYST

E. Loukianova

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

NAD: No Asbestos Detected

The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice,



LABORATORY TESTING SERVICES INC. LIC, NY 11104 Ph.: (718) 389 3470, Fax: (718) 389 3471 45-09 GREENPOINT AVE.

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

PROJECT: 11-25 Irving Ave.	LABORATORY ID #: 15-12-029	DATE OF REPORT: 12/04/15
CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY 11104 PROJECT: 11-25 Irving	ANALYT. METHODOLOGIES: ELAP 198.6, ELAP 198,4	DATES OF ANALYSIS: 12/03/15

I AROBATORV BESIII TS

121 171	4. 4.						-			
EN!	LAB. ID #	LOCATION	%ORG	%ASI	%AII	PLM RESILITS	TYPE OF	TEM TYPE OF	TYPE OF	POSIT. /
2	15-12- 029-37	Coating on Brick (Gray), Exterior – Flat 17.10 Fix Shop	17.10	64.25	18.65	64.25 18.65 NAD	NA	NAD	NA NA	Negat.
∞	15-12- 029-38	Coating on Brick (Gray), Exterior – Flat Fix Shop	18.08 63.46 18.46	63.46	18.46	NAD	NA	NAD	NA	Negat.

ANALYST

E. Loukianova

LABORATORY DIRECTOR E. Dimitrakas

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.

	MATERIAL STATES	A SERVICES INC. ENVIRONMENTAL TRA	ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 11-25 IRVING AVE., QUEENS NY - LOT 46	<u>DATE</u> 10/24/2015	
INSPECTOR J. BARDIOV	I <u>NSPECTOR</u> J. BARDIOVSKY/ W. SIKORSKI	KORSKI	CDM SMITH	PROJECT # IFB-3323-054-004-CS	# OF SAMPLES
COMMENTS		STOP AT FIRST POSITIVE		PLM NOB-PLM NOB-TEM NOB-TEM 12 HRS 24 HRS	NOB-TEM
HOM. AREA	SAMLPLE #		SAMPLE	FIELD LABORATORY FORMMENTS PI M PI M-NOR	LABORATORY RESULTS
		BRICK MURTHER	ANTERIUR - BASEMBUT	-	-
	200			INAD	
2	2	WHITE CONTINGON		**	
2	S	CAR (CLC)		J. NAYD	
v	D (1	WAIL SHIPTIRECK	7		
^ -3	-00	R. B. A. IN ST CHERDON	10007 151 - 10017 NI	OWN X	
5	0		INTERIOR BASEMENT		
S	3:	Bram putstadioment			
ur	12	•		NAN	
TRANSMITTAL C []STANDARD []TELEPHONE []FAX RESUL	TRANSMITTAL OF RESULTS: []STANDARD []TELEPHONE RESULTS TO I 1FAX RESULTS TO	TS: STO	TELEPHONE #:	BATCH#: 15 -	12+028
			CHAIN OF CUSTODY RECORD		
RECEIVED BY:	KELINQUISHED BY : SEIVED BY :	: JURAJ BARDIOVSKY	Continue DATE: 12, 2	/ 2015 TIME: /7:3>	
LABORATORY A	ပ္မ	REDITATION: /		, /	

A SENTES INC.	WOLFF-ALPORT CHEMICAL CO SITE, 11-25 IRVING AVE OLIFENS NY - 1 OT 46	10/24/2015	
<u>INSPECTOR</u> J. BARDIOVSKY/ W. SIKORSKI	CLIENT CDM SMITH	PROJECT # IFB-3323-054-004-CS	# OF SAMPLES
COMMENTS STOP AT FIRST POSITIVE	IVE	BPLM NOB-PLM 6 HRS	MOB-TEM
HOM. SAMLPLE SAMPLE AREA # DESCRIPTION	SAMPLE LOCATION	FIELD LA	LABORATORY RESULTS
6 13 CERPINIC FLOOR	INTERIOR.		A CA
7 () CERPMIC FLOOR	2 FRONT VELI	1	CAN
TILESETIME	EMENT		
S 17 COUNTIL WALL	T.	TOLLET (-)	MATO
CISOMMIC INSH	THE THE	*	4
10	2		NATO A
MASTIC ASSCRIPTED	WITH	PSCHIND COURTE P	11-18-11
2 12x12 FU	<i>y</i> 1	1	To the state of th
(1 24 (BURCE)		B	N-3000(-)
TRANSMITTAL OF RESULTS: []STANDARD []TELEPHONE RESULTS TO	TELEPHONE #:	BATCH#: 15	: 15 - 12-028
	CHAIN OF CUSTODY RECORD		
RECEIVED BY: JURAJ BARDIOVSKY RECEIVED BY:		/ 2015 TIME: / 7.3	
LABORATORY ACCREDITATION:			

SAMPLE PROJECTOR			ATHENICA ENVIRONMENTAL. TAL. SERVICE, INC. ENVIRONMENTAL GAR	ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 11-25 IRVING AVE., QUEENS NY - LOT 46	<u>DATE</u> 10/24/2015	
ST POSITIVE SAMPLE SAM	J. BARDIC	OR NVSKY/ W. SIKC	JRSKI	CDM SMITH	PROJECT # IFB-3323-054-004-CS	# OF SAMPI
SAMPLE SSAMPLE	COMMEN.		AT FIRST POSITIVE		s	≥ □
FLUVE TILES INTRELOR-GROWNO FLOOR—BEHIND COLNER (-) MAYO STUCCO FREELOR (-) NTERIOR STUCCO FREELOR INDENDICATE EXTRELOR STUCCO FREELOR INDENDICATE EXTRELOR STUCCO FREELOR INDENDICATE EXTRELOR SHOO INDENDICATE EXTRELOR SHOO STUCCO FREELOR INDENDICATE EXTRELOR SHOO SHOO STUCCO FREELOR SHOO	HOM. AREA	SAMLPLE #	SAMPLE DESCRIPTION	SAMPLE LOCATION	FIELD	ABORATORY RE
STUCCO EXTERIOR PROPERTY STUCK STUCCO EXTERIOR PLATFIX STUCK STUCCO EXTERIOR PLATFIX STUCK INCONCATE EXTERIOR PLATFIX SULCO STUCCO EXTERIOR PLATFIX SULCO SULCO STUCCO EXTERIOR PLATFIX SULCO STUCCO EXTERIOR PLATFIX SULCO STUCCO EXTERIOR PLATFIX SULCO SULCO STUCCO EXTERIOR PLATFIX SULCO SULCO SULCO SULCO SULCO PLATFIX SULCO SULCO SULCO SULCO SULCO SULCO SULCO PLATFIX SULCO S	12	X	12 FWUR	INTERIOR-GROWNO FLOOR	BEHIND COUNTER	(-) MA
STUCCO EXTERIOR INCOMENTE EXTERIOR SHOC	in	35		FLOOR! DEL	~9	0
STUCO ST	2	28		1x SHOP		2
INSCNORTE KYTORIOR - PLAT FIX C- MAD MAD C-	6)	20		EXTERIOR		1
TELEPHONE #: BARDIOVSKY TELEPHONE #: EAX#; DATE: Z Z Z Z Z Z Z Z Z	(5)	31	KING	EXTERIOR - FLAT FIX		71100
### (=) A & & & (=) A & (=)	2	200	SILVER	SHOD		W To Caller To
TELEPHONE #: FAX#:	9)	30	ROBULL ON			N(-) ONN(-)
TELEPHONE #: EAX#: CHAIN OF CUSTODY RECORD J. P. CI 1 2015 TIME: 77 470	E	35	0/PAINT			1 00 0 C/T/
TELEPHONE #: BATCH #: 15 - 12	4	2	CATE	0		10.80/14
J. BARDIOVSKY CHAIN OF CUSTODY RECORD J. G. L.	TRANSMITT []STAND, []TELEPF []FAX RE:	AL OF RESULTS ARD HONE RESULTS SULTS TO	01	TELEPHONE #:	m m	71-
JAYINGARA GONTE: 1212 12015 TIME: 1				CHAIN OF CUSTODY RECORD		
DAIE: 1212 12015 TIME: 1	RECEIVED	QUISHED BY:	JURAJ BARDIOVSKY	DATE: 121 C		1.35
	LABORAT(ORY ACCREDI	2	10AIE: 1/2/2		2 40

	# OF SAMPLES	NOB-TEM 24 HRS	LABORATORY RESULTS	(-) NAD					15 -12-029			
<u>DATE</u> 10/24/2015	PROJECT # IFB-3323-054-004-CS	PLM NOB-PLM TALARS	FIELD LA						BATCH#:		(2015 TIME : (7 - 5)	(2015 TIME: 1740
<u>ADDRESS</u> WOLFF-ALPORT CHEMICAL CO SITE, 11-25 IRVING AVE., QUEENS NY - LOT 46	CLIENT CDM SMITH		SAMPLE LOCATION	EXTERIOR- FLAT FIX SHIP	D. D.				TELEPHONE #:	CHAIN OF CUSTODY RECORD	1212	1 cf for CH DATE: 121 2 1
A THENICA ENVIRONMENTAL. TAL. SENICISE INC. ENVIRONMENTAL TAL.		STOP AT FIRST POSITIVE	SAMPLE DESCRIPTION	COATING ON BRICK	(2027)			· · ·	170		JURAJ BARDIC	TATION . J. P. J. KNR.A.
	INSPECTOR J. BARDIOVSKY/ W. SIKORSKI	COMMENTS STOP	νς Σ. ξ.		20			TRANSMITTAL OF RESULTS:	[]STANDARD []TELEPHONE RESULTS TO []FAX RESULTS TO		RELINQUISHED BY:	RECEIVED BY:



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104 Ph.: (718) 389 3470, Fax: (718) 389 3471

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

nica Env	nica Environmental / 45-09 Greenpoint Avenue, LIC, NY 11104 PROJECT: 11-25 Irving Ave	ALYT. METHODOLOGIES: ELAP 198.6, ELAP 198.4	MAVIE
----------	-----------------------------------------------------------------------------------------	---------------------------------------------	-------

LABORATORY RESULTS

TYPE OF	NA Posit.	VALYZED	NA Posit.	VALYZED	NA Posit.	VALYZED
OF TEM		SAMPLE NOT ANALYZED	ys. NA	SAMPLE NOT ANALYZED	/S. NA	SAMPLE NOT ANALYZED
PLM TYPE OF		SAM	2.77 Chrys.	SAM	7.31 Chrys.	SAM
%AII	24.39	32.66	39.79	31.16	16.43	20.65
%ASI	3.29	24.42	16.14	24.64	6.29	2.17
%ORG	70.52	42.92	41.30	44.21	96.69	77.17
LOCATION	Roof Membrane (Bottom Layer), Roof	Roof Membrane (Bottom Layer), Roof	Roof Membrane (Top Layer), Roof	Roof Membrane (Top Layer), Roof	Parapet Wall Tar/Flashing, Roof	Parapet Wall Tar/Flashing, Roof
LAB. ID #	15-12- 090-01	15-12- 090-02	15-12- 090-03	15-12- 090-04	15-12- 090-05	15-12-
##	39	40	41	42	43	44

In Breitaker

LABORATORY DIRECTOR

E. Dimitrakas

ANALYST A. Johnson

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

NAD: No Asbestos Detected

The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104 Ph.: (718) 389 3470, Fax: (718) 389 3471

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

ve.	12-090	12/08/15
104 PROJECT: 11-25 Irving Ave	LABORATORY ID #: 15-1	DATE OF REPORT: 12/08
45-09 Greenpoint Avenue, LIC, NY 11	ANALY I. METHODOLOGIES: ELAP 198.6, ELAP 198.4	DATES OF ANALYSIS: 12/04/15

LARORATORV DESITTE

TAD IN									
LAB. ID	LOCATION	%ORG	%ASI	%AII	PLM RESULTE	TYPE OF	TEM TYPE OF POSIT./	TYPE OF	POSIT. /
15 10	e e				CITOCON	ASDEST.	KESULIS	ASBES1.	NEGAI.
70-060	1 ar on beam, Koot	53.07	11.07	53.07 11.07 32.88	2.98	Chrys.	NA	NA	Posit.
15 10	- C								
80-060	I ar on beam, Koot	53.67	5.42	40.91		SAMPLE	SAMPLE NOT ANALYZED	LYZED	

In Birei krahan

LABORATORY DIRECTOR E. Dimitrakas

ANALYST

A. Johnson

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.

			AMTZE B, TEMONLY		180.	5	000	F	260		Co									
	# OF SAMPLES	2		ESULTS TEM NOB	(/ / / / / / / / / / / / / / / / / / /	1000	になった	101/2) (RE)+	144/	+12.98/	" hat "				040				
,	0#		NOB-TEM	LABORATORY RESULTS	1											15.				
			NOB-PLM	A a										-		BATCH#: 15		TIME: 12.50		
<u>DATE</u> 12/4/2015	PROJECT # IFB-3323-054-004-CS		PLM 6 HRS	FIELD															2015 IIIv	
46	· ·															i -	OV DECODO		てレ	
ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 11-25 IRVING AVE., QUEENS NY - LOT 46	CLIENT CDM SMITH			SAMPLE	OOF							R				TELEPHONE #: FAX #:	CHAIN OF CLISTORY BECORD	DATE	Link I	
ADD WOL	CLIENT CDM SN		E I		LE R	(7)	3		417		+						- A		3/	
ATHENICA ENVIRONMENTAL TOL.	RSKI		STOP AT FIRST POSITIVE	SAMPLE DESCRIPTION	ROOF MEMBRANE	(BOTTOM LITTER	2004 MEMPRENC	(TOP CAMED)	THAT SALL	TUNE AND	THIS ON GERMY.	9)				.: 0		JURAJ BARDIOVSKY	ATION:	ELAP# 10955
	INSPECTOR J. BARDIOVSKY/ W. SIKORSKI	0 I 0		SAMLPLE #	39	040	dí	.25	43	5 3	53	25	73	65	30	TRANSMITTAL OF RESULTS: []STANDARD []TELEPHONE RESULTS TO		RELINQUISHED BY:	00	
¥	INSPECTOR J. BARDIOV		COMMENTS	HOM. AREA	6)	5	20	3	12	77	77	11				TRANSMITTAL OF RES []STANDARD []TELEPHONE RESI []TAX RESULTS TO		RECEIVED BY:	LABORATORY A	NVLAF# 101

R



Services and LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104 BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

NY 11104 PROJECT: 11-27 Irving Ave., C DATE OF REPORT: 12/17/15	
/45-09 Greenpoint Ave., LIC, NY 11104	
LIENT: Athenica Environmental Services Inc. ATE OF ANALYSIS: 12/03/15	

CLIENT ID# LABORATORY ID#	STEREO MICROSCOPY RESULTS	ρΥ	SAMPLE DESCRIPTION	FIBROUS	NON FIBROUS MATERIAL	% ASBESTOS AND TVPF
01	COLOR	Gray	Brick Mortar, Interior	%0	1000%	
15-12-028-01	# LAYERS	-				TAN T
	SCAN					
02	COLOR	Gray	Brick Mortar, Interior	%0	100%	NAN
15-12-028-02	# LAYERS	-				OWN.
	SCAN					
03	COLOR	Gray	Brick Mortar, Interior	%0	100%	CAN
15-12-028-03	# LAYERS	-				TENT
	SCAN					
04	COLOR	Gray	Cinderblock Mortar, Interior	%0	100%	CAN
15-12-028-04	# LAYERS	1			0/001	INAD
	SCAN					
05	COLOR	Brown	Cinderblock Mortar, Interior	%0	100%	CAN
15-12-028-05	# LAYERS	1		n Y		GEN
	SCAN					
90	COLOR	Gray	Cinderblock Mortar, Interior	%0	100%	NAN
13-12-028-06	# LAYERS	-				TANK!
	SCAN					



Sacrices BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

.ve LIC. NY 11104 PROJECT: 11-27 Irving Ave Onesing	The state of the s	DATE OF REPORT: 12/17/15
CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 1110.	DATE OF ANALYSIS, 12/02/15	DAIL OF AIMEL SIS: 12/03/13

ANALYTICAL BESTILTS

CLIENT ID# LABORATORY ID#	STEREO MICROSCOPY RESULTS	OPY	SAMPLE DESCRIPTION	FIBROUS MATERIAL	NON FIBROUS MATERIAL	% ASBESTOS AND TVDE
60	COLOR	Gray	Wall Sheetrock, Interior	2%FBGI	%80	NAN
15-12-028-09	# LAYERS				0/0/	INAD
	SCAN					
10	COLOR	Gray/Brown	Wall Sheetrock, Interior	10%CELL	%68	NAN.
15-12-028-10	# LAYERS	2		1%FBGL		av.
	SCAN					
11	COLOR	Brown	Floor Debris, Interior	2%CELL	%80	242
15-12-028-11	# LAYERS	1				NAD
	SCAN					
12	COLOR	Gray/Brown	Floor Debris, Interior	20%CELL	80%	C & Z
15-12-028-12	# LAYERS	2				TV
	SCAN					
13	COLOR	Gray	Floor Debris, Interior	5%CELL	92%	CAN
15-12-028-13	# LAYERS	1				TVI
	SCAN					



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104

BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 11104 | PROJECT: 11-27 Irving Ave., Queens DATE OF REPORT: 12/17/15 DATE OF ANALYSIS: 12/03/15

nalyst:

K. Esnard

Laboratory Director:

E. Dimitrakas

NAD: No Asbestos Detected, CELL: Cellulose, FBGL: Fiberglass, H. Hair, SY: Synthetics, CH: Chrysotile, AMOS: Amosite, TRE: Tremolite, ANTH: Anthophyllite, ACT: Actinolite, CRO: Crocidolite, VERM:

Analytical Methodologies: EPA 600/M4-82-020 (Point Count only) and ELAP Method 198.1.

Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

The liability of Laboratory Testing Services Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

6, ELAP 198.4 LAC, NY 11104 PROJECT: 11-27 Irving Ave. Project #: IFB-3323-054-004-CS LAP 198.4 LABORATORY ID #: 15-12-028	198.4 LABORATORY ID #: 15-12-028
23-054-004-CS	ve. rroject #: 1FB-55 -12-028

LABORATORY RESULTS

	TYPE OF	RESOLIS ASBEST. RESOLIS ASBEST. NEGAT.	12.71 60.81 26.48 NAD NA NAD NA Negat.		27.11 NAD NA NAD NA Negat.		4.29 NAD NA NAD NA Negat.		3.62 NAD NA NAD NA Negat.
CIPACITY TARACTE	%ASI		60.81		59.71 2		50.29 45.43 4.29		50.13 46.25 3.62
	%ORG		12.71		13.19 59.71		50.29	0.01	50.13
	LOCATION	White Dain on Challet 1	winte rain on Cinderblocks, Interior	W.T. t. D.	while rain on Cinderblocks, Interior	Toint Coulting and Marie 1871	Joint Caulking on Metal Plate, Interior	Toint Caulling on Metal Die r	John Caulking on Metal Plate, Interior
TAN TA	# ##	15.12	028-07	15 13	028-08	15 10	028-14	15.12	-21-01
TINII IC	##	0.7		80	00	1.1		15	2

LABORATORY DIRECTOR E. Dimitrakas

ANALYST

E. Loukianova

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.
- Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.

STOP AT FIRST POSITIVE SAMLPLE SAMPLE SAMPLE BESCRIPTION LINDIR BLOOK MURTHL SAMPLE BESCRIPTION LINDIR BLOOK WALL SHEFFLOCK BESCRIPTION CINDER BLOOK WALL SHEFFLOCK BESCRIPTION CINDER BLOOK CINDER BLOOK CINDER BLOOK CINDER BLOOK CONDER B	※		ILE INVINCE AVE., GOEENS INT - LOI 44		
STOP AT FIRST POSITIVE SAMPLE	COMMENTS STOP AT F		CLIENT CDM SMITH	PROJECT #	# OF SAMPLES
SAMIPLE SAMPLE SAMPLE SAMPLE FIELD LABORATORY RE 1 CANDRELOS LABORATORY 1 CANDRELOS LABORATORY 2 CANDRELOS LABORATORY 3 CANDRELOS LABORATORY 4 CANDRELOS LABORATORY 5 CANDRELOS LABORATORY 6 CANDRELOS LABORATORY 6 CANDRELOS LABORATORY 7 CANDRELOS LABORATORY 8 CANDRELOS LABORATORY 9 CANDRELOS LABORATORY 10 CANDRELOS LABORATORY 11 CANDRELOS LABORATORY 12 CANDRELOS LABORATORY 13 CANDRELOS LABORATORY 14 CANDRELOS LABORATORY 15 CANDRELOS LABORATORY 16 CANDRELOS LABORATORY 17 CANDRELOS LABORATORY 18 CANDRELOS LABORATORY 19 CANDRELOS LABORATORY 10 CANDRELOS LABORATORY 10 CANDRELOS LABORATORY 10 CANDRELOS LABORATORY 11 CANDRELOS LABORATORY 11 CANDRELOS LABORATORY 12 CANDRELOS LABORATORY 13 CANDRELOS LABORATORY 14 CANDRELOS LABORATORY 15 CANDRELOS LABORATORY 16 CANDRELOS LABORATORY 17 CANDRELOS LABORATORY 18 CANDRELOS LABORATORY 19 CANDRELOS LABORATORY 10 CANDRELOS LABORATORY 10 CANDRELOS LABORATORY 10 CANDRELOS LABORATORY 10 CANDRELOS LABORATORY 11 CANDRELOS LABORATORY 11 CANDRELOS LABORATORY 11 CANDRELOS LABORATORY 11 CANDRELOS LABORATORY 12 CANDRELOS LABORATORY 13 CANDRELOS LABORATORY 14 CANDRELOS LABORATORY 15 CANDRELOS LABORATORY 16 CANDRELOS LABORATORY 17 CANDRELOS LABORATORY 17 CANDRELOS LABORATORY 18 CANDRELOS LABORATORY 18 CANDRELOS LABORATORY 18 CANDRELOS LABORATORY 18 CANDRELOS LABORATORY 19 CANDRELOS LABORATORY 19 CANDRELOS LABORATORY 19 CANDRELOS LABORATORY 10 CAND		IRST POSITIVE		NOB-PLM 12 HRS	
1 CALLE MURTHER LOPE 1 S b 1 LINDIX CLOSE LEGISLE 2 S CLINER BULKS 3 S CLINER BULKS 4 WALL SHEETERCH 10 IN FLOOR OF BRITE 11 FLOOR OF BRITE 11 FLOOR OF BRITE 12 S CLINER BULKS 13 S CLINER BULKS 14 WALL SHEETERCH 15 S S CLINER BULKS 16 S S S S S S S S S S S S S S S S S S S		SAMPLE DESCRIPTION	SAMPLE LOCATION	٦	DRATORY RESULTS
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	I BRI	1)	-	/	+
1 S b b CINDRECEDER MATTER PRINTON 2 A WALL SHEETEDCK 1 IN FLOOR OFBRIS 1 IN FLOOR OFB	1		-		
1 CINDER CLOCK FLOCK FLOCK FLOCK PAGENT (-)NATO S	1 3	9			
S S WHITE PAINT ON S S S S S S S S S S S S S S S S S S	2 4 UR	DERBOCKMOTHE			
4 WHITE PAINT ON S & CLINDRABUCKS G WALL SHEETCOCK IN FLOOR OFBRIS 1. FLOOR OFBRIS 1. Thoras of the second of	5 7				
3 7 WHITE PAINTON S CINDERBUCKS G WALL SHEFTEDCK 10 J.		9			
S & CINVARABOLUS 1 G WALL SHERTEDOCK 10 LOOR OFBRIS 11 FLOOR OFBRIS 12 LOOR OFBRIS 13 LOOR OFBRIS 14 LOOR OFBRIS 15 LOOR OFBRIS 16 LOOR OFBRIS 17 LOOR OFBRIS 17 LOOR OFBRIS 18 LOOR OFBRIS 18 LOOR OFBRIS 19 LOOR OFBRIS 10 LOOR OFBRIS 10 LOOR OFBRIS 11 LOO	d			>	124011
10 MAL SHEFTEDOCK (-)NAT	2	NVOGR BLOCKS			W - 1 / W - 1 / W
FUDOR ORBRIS	6	1			*
FUDOR ORBRIS 6	01 h				
		or otheris			
	5 2	_ (8		
			FAX#:	BAICH#: I	
FAX#: FAX#:			CHAIN OF GUSTODY RECORD		
BATCH#: 15		JRAJ BARDIOVSKY	717	TIME:	
HED BY: JURAJ BARDIOVSKY CHAIN OF CUSTODY RECORD TIME: 15	LABORATORY ACCREDITATION	IN:	JONE 121 2	/ 2015 TIME: / 700	

SAMPLE LOCATION INTERLOCATION INTE	ADDRESS WOLFF-ALPORT CHEMICAL T-27 IRVING AVE., QUEEN CLIENT CDM SMITH CDM SMITH CDM SMITH LOCATION SAMPLE AREA # DESCRIPTION COMMENTS SAMPLE AREA # DESCRIPTION COMMENTS COMMENTS WOLFF-ALPORT CHEMICAL WOLFF-ALPORT CHEMICAL CLIENT CDM SMITH LOCATION LOCATION COMMENTS SAMPLE LOCATION COMMENTS COMENTS COMMENTS COMMENT		# OF SAMPLES IFB-3323-054-004-CS	PLM MOB-PLM MOB-TEM 12 HRS	IABOR P	
	RST POSITIVE SAMPLE DESCRIPTION OR ORGANIS TORNILMS IN TORNILMS IN TORNILMS IN	ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 11-27 IRVING AVE., QUEENS NY - LOT 44	JIENT DM SMITH		SAMPLE LOCATION	



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. Ph.: (718) 389 3470, Fax: (718) 389 3471 LIC, NY 11104

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

	DKESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY PROJECT: 11-27 Irving Ave.	Project #: IFB-3323-054-004-CS	ALTI: METHODOLOGIES: ELAP 198.6, ELAP 198.4 LABORATORY ID #: 15-12-123	09/15
Souther / Thaile	11104	ANAIVE METERICA COLOR	BATTE OF THE HODOLOGIE	DALES OF ANALYSIS: 12/09

I ARODATOBY DEST

LOCATION %ORG %ASI %ASI PLM TYPE OF ASBEST. TYPE OF ASBEST. TYPE OF ASBEST. Roof Membrane (Bottom Layer), Roof 85.66 0.98 13.35 3.12 Chrys. NA NA NA Roof Membrane (Bottom Layer), Roof 64.53 8.92 26.55 NAD NA NA NA Roof Membrane (Top Layer), Roof 52.43 14.39 33.18 NAD NA NA Parapet Wall Flashing/Tar, Roof 79.68 2.54 15.04 2.74 Chrys. NA NA Parapet Wall Flashing/Tar, Roof 79.47 5.75 14.78 SAMPLE NOT ANALYZED		NEGAT.	I OSIL.		Negat.	Negat.		Posit.	
n Layer), Roof 57.29 6.02 33.57 3.12 n Layer), Roof 85.66 0.98 13.35 Layer), Roof 64.53 8.92 26.55 NAD Layer), Roof 52.43 14.39 33.18 NAD s/Tar, Roof 79.68 2.54 15.04 2.74	TYPE OF	ASBEST.	1317	YZED	NA	NA		A	YZED
n Layer), Roof 57.29 6.02 33.57 3.12 n Layer), Roof 85.66 0.98 13.35 Layer), Roof 64.53 8.92 26.55 NAD Layer), Roof 52.43 14.39 33.18 NAD s/Tar, Roof 79.68 2.54 15.04 2.74	TEM	RESULTS	****	NOT ANAL	NAD	NAD		NA	NOT ANAL
n Layer), Roof 57.29 6.02 33.57 n Layer), Roof 85.66 0.98 13.35 Layer), Roof 64.53 8.92 26.55 Layer), Roof 52.43 14.39 33.18 s/Tar, Roof 79.68 2.54 15.04	TYPE OF	Chrvs.		SAMPLE	NA	NA	5	CIII'ys.	SAMPLE
n Layer), Roof 67.29 6.02 n Layer), Roof 85.66 0.98 Layer), Roof 64.53 8.92 Layer), Roof 52.43 14.39 s/Tar, Roof 79.68 2.54	PLM PEGIII TG	3.12			NAD	NAD	27.6	*	
n Layer), Roof 9,0RG 9,0ASI n Layer), Roof 85.66 0.98 Layer), Roof 64.53 8.92 Layer), Roof 52.43 14.39 s/Tar, Roof 79.68 2.54	%AII	33.57		13.35	26.55	33.18	15.04	10:01	14.78
n Layer), Roof n Layer), Roof Layer), Roof Layer), Roof s/Tar, Roof	%ASI	6.02		86'0	8.92		2 54	i	
Roof Membrane (Bottom Layer), Roof Roof Membrane (Bottom Layer), Roof Roof Membrane (Top Layer), Roof Roof Membrane (Top Layer), Roof Parapet Wall Flashing/Tar, Roof Parapet Wall Flashing/Tar, Roof	%ORG	57.29		85.66	64.53	52.43	89.62		79.47
	LOCATION	Roof Membrane (Bottom Layer), Roof		Koot Membrane (Bottom Layer), Roof	Roof Membrane (Top Layer), Roof	Roof Membrane (Top Layer), Roof	Parapet Wall Flashing/Tar, Roof		Parapet Wall Flashing/Tar, Roof
	##	17	10	0	19	20	21	S	77

LABORATORY DIRECTOR E. Dimitrakas

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

A. Korionova ANALYST

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

PROJECT: 11-27 Irving Ave.	1101ct #. IFB-3323-034-004-CS	LABORATORV ID #: 15.12.12.	C71-71-01 ID II. 17-17-173	DATE OF REPORT: 12/10/15
CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY PROJECT: 11-27 Irving Ave.		CARLO I I METHODOGIES: ELAP 198.6, ELAP 198.4	DATES OF ANALYSIS. 12/00/15	MLI 313: 12/09/13

LABORATORY RESULTS

LOCATION	%OBG	13V/0	-	DITLE	IL	11		
	DNOW	ICHO/	%AII	RESILTS	TYPE OF ASBEST		TEM TYPE OF POSIT./	POSIT. /
Tar on Metal Beams, Roof	99.86	0.50	98.66 0.50 0.84	1		1	NA NA	Negat.
December 19.16	100							
i al Oli Metal Deallis, Kool	68.76	1.32	0.79	NAD	NA	NAD	NA	Negat.
Manhan D. C.								
vent stack Lat/Flashing, K001	82.16	2.97	82.16 2.97 12.39	2.48	Chrys.	NA	NA Posit.	Posit.
Vent Stack Tar/Flashing, Roof	77.30	77.30 2.14 20.55	20.55		SAMPLE	SAMPLE NOT ANALYZED	LYZED	

LABORATORY DIRECTOR E. Dimitrakas

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

A. Korionova ANALYST

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.

	# OF SAMPLES		NOB-TEM ANNUZE BY	RESUL	TEINING IEMINOB	MAN	CAND	*	(7) 2. 74/04	1	(1) (A)	(4) 2 48/C4	1	-12-123			
<u>DATE</u> 12/4/2015	PROJECT # IFB-3323-054-004-CS	-3-	PLM NOB-PLM K	FIELD LABOR.										BATCH#: 15		2015 INME:	1 12-773
ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 11-27 IRVING AVE., QUEENS NY - LOT 44	CLIENT CDM SMITH	2		SAMPLE	Roof								9	TELEPHONE #:	CHAIN OF CUSTODY RECORD	12/8/12/	The state of the s
A STRENGS INC. TRI. INDICATION OF THE RESIDENCE TRI.	V. SIKORSKI		STOP AT FIRST POSITIVE	PLE SAMPLE DESCRIPTION	T ROOF MEMBRANE	CBUTT	KOUP MEMBRANE	DOOD OF LANEK)	C ASK IN C LAD	NO O	4 BEAMS	S VENT STACK TARY	FLASHING	SULTS:	BY: JURAJ BARDIOVSKY	REDITATION: Own office of	
	<u>INSPECTOR</u> J. BARDIOVSKY/ W. SIKORSKI		COMMENTS ST	HOM. SAMLPLE AREA #	ti it	27 1 12	83 6	200	2000	2 600	108 20	11 9 25	7 00 11	TRANSMITTAL OF RESULTS: []STANDARD []TELEPHONE RESULTS TO	RELINQUISHED BY:	LABORATORY ACCREDITATION : NVLAP# 101958	



BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

Irving Ave	II VIII & LIVE	T. 12/00/15	
14 Ave., LIC, NY 11104 PROJECT: 11-29		DATE OF DEDOCT. 12/09/15	
vironmental Services Inc. / 45-09 Greenpoir	71/00/01	12: 12/03/13	
LIENT: Athenica Env	NATE OF ANATARVET	ALE OF AIMLISE	

CLIENT ID#	STEREO		SAMPLE DESCRIPTION	FIBROUS	NON	%
LABORATORY ID#	MICROSCOPY RESULTS	PY		MATERIAL	FIBROUS	ASBESTOS AND TYPE
01	COLOR	Grey	Brick Mortar, Interior	%0	100%	NAN
15-12-030-01	# LAYERS	1				TWI
	SCAN					
02	COLOR	Brown	Brick Mortar, Interior	%0	100%	Z A N
15-12-030-02	# LAYERS	1)		IVAD
	SCAN					
03	COLOR	Brown	Brick Mortar, Interior	%0	100%	2
15-12-030-03	# LAYERS	1			2001	NAD.
	SCAN					
04	COLOR	Brown	Cinderblock Mortar, Interior	%0	100%	447
15-12-030-04	# LAYERS	1)		INAD
	SCAN					
05	COLOR	Brown	Cinderblock Mortar, Interior	%0	100%	CAN
15-12-030-05	# LAYERS	1				ANI T
	SCAN					
90	COLOR	Brown	Cinderblock Mortar, Interior	%0	100%	CAN
15-12-030-06	# LAYERS			9		TO L
	SCAN					



BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

PROJECT: 11-29 Irvino Ave	DATE OF REPORT: 12/08/15
CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 11104 PROJECT: 11-29 Irvi	DATE OF ANALYSIS: 12/03/15

CLIENT ID#	STEREO		SAMPLE DESCRIPTION	FIRDAIR	NON	/0
LABORATORY ID#	MICROSCOPY RESULTS	OPY		MATERIAL	FIBROUS MATERIAL	ASBESTOS AND TYPE
07	COLOR	Cream/Brown	Ceiling Sheetrock, Interior	5%CELL	94%	NAD
15-12-030-07	# LAYERS	2		1%FBGL		
	SCAN					
80	COLOR	Cream/Brown	Ceiling Sheetrock, Interior	2%CELL	%86	NAD
15-12-030-08	# LAYERS	2				
	SCAN					
60	COLOR	Light Brown	Wall Plaster (Scratch Coat), Interior	%0	100%	NAD
15-12-030-09	# LAYERS	I				
	SCAN					
10	COLOR	Light Brown	Wall Plaster (Scratch Coat), Interior	%0	100%	NAD
15-12-030-10	# LAYERS					
	SCAN					
11	COLOR	Light Brown	Wall Plaster (Scratch Coat), Interior	%0	100%	NAD
15-12-030-11	# LAYERS	-				
	SCAN					
12	COLOR	Light Brown	Wall Plaster (Scratch Coat), Interior	%0	100%	NAD
15-12-030-12	# LAYERS	I				
	SCAN					



BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

NY 11104 PROJECT: 11 20 Ferring A.:.	TANGET TI-27 IIVIII AVE	DATE OF REPORT: 12/08/15
IENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 1110	TE OF ANALYSIS. 12/03/15	0.100/10

CLIENT ID# LABORATORY ID#	STEREO MICROSCOPY RESULTS	OPY	SAMPLE DESCRIPTION	FIBROUS NON MATERIAL FIBROUS MATERIA	NON FIBROUS MATERIAL	% ASBESTOS. AND
13	COLOR	Light Brown	Wall Plaster (Scratch Coat). Interior	%00	1000	IIIE
15-12-030-13	# LAYERS	1			100%	NAD
	SCAN					
18	COLOR	Dark Brown	Door Insulation, Interior, Front	90%CELT	100	4
15-12-030-18	# LAYERS	I	Door		10%	NAD
	SCAN					
19	COLOR	Brown	Door Insulation, Interior. Back Door	95%CELT	/05	20.00
15-12-030-19	# LAYERS	1			970	NAD
	SCAN					

K. Gibson Analyst:

Laboratory Director:

E. Dimitrakas

- NAD: No Asbestos Detected, CELL: Cellulose, FBGL: Fiberglass, H: Hair, SY: Synthetics, CH: Chrysotile, AMOS: Amosite, TRE: Tremolite, ANTH: Anthophyllite, ACT: Actinolite, CRO: Crocidolite, VERM:
 - Analytical Methodologies: EPA 600/M4-82-020 (Point Count only) and ELAP Method 198.1.
- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

 The liability of Laboratory Testing Services Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. Ph.: (718) 389 3470, Fax: (718) 389 3471 LIC, NY 11104

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

PROJECT: 11-29 Irving Ave.	LABORATORY ID #: 15-12-030	DATE OF REPORT: 12/04/15
1 Environment		DATES OF ANALYSIS: 12/03/15

LABORATORY RESILLTS

POSIT./	Negat.	Negat.	Negat.	Negat.	Negat.	Negat.
-	ASBEST. NA	NA	NA	NA	NA	NA
	NAD	NAD	NAD	NAD	NAD	NAD
TYPE OF	NA	NA	NA	NA	NA	NA
PLM RESILLTS	NAD	NAD	NAD	NAD	NAD	NAD
%AII	8.71	20.21	15.77	11.51	3.67	3.77
%ASI	84.52	72.84	60.69	73.48	36.19	35.68
%ORG	6.77	6.95	15.14	15.01	60.15	60.55
LOCATION	Window Putty Interior, Interior	Window Putty Interior, Interior	12x12 Floor Tiles/Glue, Interior	12x12 Floor Tiles/Glue, Interior	Joint Caulking on Floor Plate, Interior	Joint Caulking on Floor Plate, Interior
LAB. IID #	15-12- 030-14	15-12- 030-15	15-12- 030-16	15-12- 030-17	15-12- 030-20	15-12- 030-21
# #	14	15	16	17	20	21

ANALYST

E. Loukianova

LABORATORY DIRECTOR E. Dimitrakas

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



SAMPLE DESCRIPTION LLL MORTHE BESCRIPTION JOHN SHEET/LOGL LAND SHEET/L	<u>INSPECTOR</u> J. BARDIOVSKY/ W. SIKORSKI	EXHIBITION ENGLISHED INC.	WOLFF-ALPORT CHEMICAL CO SITE, 11-29 IRVING AVE., QUEENS NY - LOT 42	CAL CO SITE, ENS NY - LOT 42	10/24/2015		
SAMPLE SAMPLE SECRETION C.E. POSTTAGE C.E.			CDM SMITH		PROJECT # IFB-3323-054-004-CS	#	OF SAMPLES
SAMPLE SAMPLE SAMPLE COMMENTS FILE LABORATORY RE LOCATION CL PLOCATION	COMMENTS STOP AT FIRST	T POSITIVE				IX L	W
CL MORTAR INTERIOR GEOLOGIC MOCTAR BATCHETICOGIC AMBARDIOVSKY TELEPHONE #: TOTAL OF 12 2 2 2015 TIME: 17 2 4 2015 TIME: 17 2 4 2015	SAMLPLE #	SAMPLE	SAMPLE	X			RESULTS
SEBLUCK MOGTAR BERLINGLY JOS SHEETILGLY JOS SHEETILGLY JOS SHEETILGLY LELEPHONE #: TELEPHONE #: TOTAL PARCE PARCE TIME: PARCE TOTAL PARCE PARCE TOTAL PARCE TIME:	1 I BRICK	MURTHR	STERIOR			Σ .	-
SCHEFTLE CH. STATE OF THE PROPERTY CONT. ALBARDIOVSKY A		-				, de	
WIRL GORTCH CONT. ALBARDIOVSKY ALBARDIOVSK	- n	J					
AN BARDIOVSKY AL BAR	5 (SLUCK MUZTAR				(1)	
ADE SHEETROGG AND BARDIOVSKY A BARDIOVSKY CHAIN OF CUSTODY RECORD A DATE: 12 2 / 2015 TIME: 6 9 9 The standard of						1090	
AJ BARDIOVSKY AJ BAR	NEILAN				4	->	
TELEPHONE #: TELEPHONE #: FAX #: TELEPHONE #: TELEPHONE #: FAX #: DATE: 12/2/12/15 TIME: 17-2/0							
TELEPHONE #: FAX #: CHAIN OF CUSTODY RECORD A BARDIOVSKY A DARBIOVSKY DATE: 12 7 2 12015 TIME: 17 2 4 0	IMACL	ALGORATCH (DIAY)					
TELEPHONE #: FAX #: CHAIN OF CUSTODY RECORD A BARDIOVSKY CHAIN OF CUSTODY RECORD A DATE: 12 2 2015 TIME: 13 21						ĵ-	
TELEPHONE #: FAX #: CHAIN OF CUSTODY RECORD AJ BARDIOVSKY AJ BARDIOVSKY DATE: 121 2 1 2015 TIME: 14240	, <u>,</u>					Color	
TELEPHONE #: FAX #: CHAIN OF CUSTODY RECORD A BARDIOVSKY A DATE: 12 2 2015 TIME: 640 DATE: 12 2 2015 TIME: 7440		9	c		4	7 7 7	
AJ BARDIOVSKY AJ BARDIOVSKY AL CHAIN OF CUSTODY RECORD DATE: 121 2 1 2015 TIME: 17240	RANSMITTAL OF RESULTS: STANDARD TELEPHONE RESULTS TO FAX RESULTS TO		TELEPHON FAX#:	 		1	020
AJ BARDIOVSKY AL BARDIOVSKY AL DATE: 12 2 2015 TIME: 17 DATE: 12 2 2015 TIME: 17		(CHAIN OF C	dagged vaggrain			
STATISTICATE TO THE TOTAL TIME: 1		BARDIOVSKY	The same of the sa	DATE : 12 . 2		Mint.	
	ECEIVED BY:	AGIIKARAL	ATT	DATE: 12/2/		10 10 10 10 10 10 10 10 10 10 10 10 10 1	
	ABORATORY ACCREDITATION:		1			266	

INSPECTOR COMMENTS CLIENT PROJECT FIRE 3223-054-004-CS FIRE 324-MPS FIRE 3223-054-004-CS FIRE 324-MPS FIRE 324-MPS FIRE 324-MPS FIRE 3223-054-004-CS FIRE 324-MPS FIRE 3223-054-004-CS FIRE 324-MPS FIRE 3223-054-004-CS FIRE 324-MPS F		WINE SERVICE S	ATHENICA ENVIRONMENTAL. TAL. SERVICES, INC. ENVIRONMENTAL TAL.	ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 11-29 IRVING AVE QUEENS NY - 1 OT 47	DATE 10/24/2015	
ST POSITIVE SAMPLE SAMPLE SAMPLE SAMPLE SAMPLE SAMPLE SOMMENTS DATE: PLAN SAMPLE S	J. BARDIOV	SKY/W.SIF	KORSKI	CLIENT CDM SMITH	PROJECT # IFB-3323-054-004-CS	# OF SAMPLES
SAMPLE SAMPLE SAMPLE ESCRIPTION ESCRIPTION REST BLALL REST BLALL COMMENTS PLANDS PLANDS (-) NAPO (COMMENTS		AT FIRST POSITIVE		s	Σ.
TREEPHONE #: FRONT OLOG PUNTE PUNTE DESTRICT FRONT OLOG FRONT OLOG FRONT FRONT OLOG FRONT	HOM. AREA	SAMLPLE #		SAMPLE LOCATION	FIELD	BORATORY RES
RIUM WORTLES WANTEL PUNTE DUNTE JAMPE	31	23	0	INTERIOR		2
WALKING ON FRONT OSGE (-) PUNTE DATE: 19 12 1 2015 THEEPHONE #: FAX #: TELEPHONE #: FAX #: DATE: 19 12 1 2015 TIME: 17 12 12	עי	5 1	WINDOW PUTTY.		1	(-)NAD(-INA
MELLANDON PUNTE PUNTE	2	و (9)
PLUTEING ON PUTE	9	1)				2 (-) CON(-)
AULLINIS ON PUNTE PUNTE PUNTE TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: DATE: 19 12 1 2015 TIME: 17 140		69	INSA			7
TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: DATE: 12 1 2015 TIME: 17 12 1 2015 TIME: 17 12 1 2015	40	5	7			0 200
TELEPHONE #: FAX #: CHAIN OF CUSTODY RECORD J BARDIOVSKY CHAIN OF CUSTODY RECORD J ACTIMATANA DATE: 19 11 1 2015 TIME: FAY #:	×c	3,	CHULKING		1 1	(-) (14)
TELEPHONE #: FAX #: CHAIN OF CUSTODY RECORD J BARDIOVSKY CHAIN OF CUSTODY RECORD DATE: 12 1 2015 Time: 17 + 40	0	7	1	->-		
TELEPHONE #: FAX #: CHAIN OF CUSTODY RECORD J BARDIOVSKY DATE: 10 12 12015 TIME: 17 440						
TELEPHONE #: FAX #: GHAIN OF CUSTODY RECORD J BARDIOVSKY DATE: 19 12 1 2015 TIME: 19 14 10						
J BARDIOVSKY J ACTINATES 19 12 1 2015 TIME: 17 12 1 2015	TRANSMITTAI []STANDAR []TELEPHOI []FAX RESU	L OF RESUL RD NE RESULTS JLTS TO	.rs: sto	TELEPHONE #:	8	15
JACINAMAN DATE: 12 1 2015 TIME: 17			1 [CHAIN OF CUSTODY RECORD		
	RELINGL RECEIVED B	JISHED BY	JURAJ BARDIOVSKY	DATE: 121 Z		(6.4)
	-ABORATOR IVLAP# 1019	RY ACCRED				



BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

PROJECT: 11-29 Irving Ave., Queens	LABORATORY ID #: 15-12-124	DATE OF REPORT: 12/10/15
CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY 11104	ANALY I. METHODOLOGIES: ELAP 198.6, ELAP 198.4	DATES OF ANALYSIS: 12/09/15

I AROBATODV DECINT

POSIT./	Posit.		Posit.	LYZED	Posit.	
TYPE OF	ASBEST. NA	YZED	Chrys.	NOT ANA	NA	YZED
	NA	SAMPLE NOT ANALYZED	3.25	SAMPLE NOT ANALYZED	NA	SAMPLE NOT ANALYZED
TYPE OF	Chrys.	SAMPLE	NA	NA	Chrys.	SAMPLE
PLM PESTILTS	3.86		NAD	NAD	3.19	
%AII	22.23	40.84	29.25	33,46	17.50	21.83
%ASI	6.45	3.61	12.52	1.91	00.6	6.34
%ORG	67.45	55.55	54.98	64.63	70.31	71.83
LOCATION	Roof Membrane (Bottom Layer), Roof	Roof Membrane (Bottom Layer), Roof	Roof Membrane (Top Layer), Roof	Roof Membrane (Top Layer), Roof	Roof Flashing (Bottom Layer), Roof	Roof Flashing (Bottom Layer), Roof
LAB. ID #	15-12- 124-01	15-12- 124-02	15-12- 124-03	15-12- 124-04	15-12- 124-05	15-12- 124-06
CLIENT #	22	23	24	25	26	27

LABORATORY DIRECTOR E. Dimitrakas

ANALYST

E. Loukianova

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

NY 11104 PROJECT: 11-29 Irving Ave., Queens	LABORATORY ID #: 15-12-124	DATE OF REPORT: 12/10/15
Greenpoint Avenue, LIC	PATES OF ANALYSIS 1900.	DATES OF ANALYSIS: 12/09/15

POSIT. /	NEGAT.	*	Posit.		Posit.	
TYPE OF	ASBEST. NA	YZED	NA	YZED	NA	YZED
TEM	RESULTS NA	SAMPLE NOT ANALYZED	NA	NOT ANAL	NA	NOT ANAL
TYPE OF	Chrys.	SAMPLE	Chrys.	SAMPLE NOT ANALYZED	Chrys.	SAMPLE NOT ANALYZED
PLM	4.27		3.08		4.37	
%AII	28.85	47.64	19.23	25.44	20.72	46.56
%ASI	4.71	1.32	2.15	0.95	1.13	6.29
%ORG	62.18	51.04	75.54	73.61	73.78	47.16
LOCATION	Roof Flashing (Top Layer), Roof	Roof Flashing (Top Layer), Roof	Coping Stone Tar, Roof	Coping Stone Tar, Roof	Parapet Wall Tar/Flashing, Roof	Parapet Wall Tar/Flashing, Roof
LAB. ID #	15-12- 124-07	15-12- 124-08	15-12- 124-09	15-12- 124-10	15-12- 124-11	15-12-
##	28	29	30	31	32	33

LABORATORY DIRECTOR

E. Dimitrakas

ANALYST

E. Loukianova

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

NAD: No Asbestos Detected

The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

PROJECT: 11-29 Irving Ave., Oueens	LABORATORY ID #: 15-12-124	DATE OF REPORT: 12/10/15
numen	GIES: ELAP	DATES OF ANALYSIS: 12/09/15

1	-
Ì	1
1	1
ì	_
É	7
	>
5	2
-	
A .	1
Ç	Y
(3
-	ABLICA

TANT									
LAB. ID	D LOCATION	%ORG	%ORG %ASI	{	%AII PLM TYPE OF	TYPE OF	TEM TYPE OF POSIT. /	TYPE OF	POSIT. /
15.10					KESULIS	ASBEST.	RESULTS	ASBEST	NFGAT
124-13	Vent Stack Flashing, Root	79.05	0.81	79.05 0.81 16.92	3.22	Chrys.	NA	NA	Posit.
15.12									
124-14	Vent Stack Flashing, Koot	80.87	80.87 1.78 17.35	17.35		SAMPLE	SAMPLE NOT ANALYZED	YZED	h
15.10	-								
124-15	Cal Faits/Car Body Lining, Roof	37.03	29.71	33.26	37.03 29.71 33.26 NAD		NA Trace Chrys. Negat.	Chrys.	Negat.
15 10	-								
124-16	Car Parts/Car Body Lining, Roof	21.53	4.12	74.34	21.53 4.12 74.34 NAD	NA	NAD	NAD NA Negat.	Negat.

LABORATORY DIRECTOR E. Dimitrakas

ANALYST

E. Loukianova

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.

IFB-3323-054-004-CS PROJECT# 12/4/2015 DATE WOLFF-ALPORT CHEMICAL CO SITE, 11-29 IRVING AVE., QUEENS NY - LOT 42 **CDM SMITH** ADDRESS CLIENT STE ATHENICA ENVIRONMENTAL TAL.
SERVICES INC.
ENVIRONMENTALIENTE ETC. J. BARDIOVSKY/ W. SIKORSKI

OF SAMPLES

TEN 10/01 7308/CE +)402/CH TEM-NOB LABORATORY RESULTS 7 NOB-TEM PLM-NOB 24 HRS PLM NOB-PLM T12 HRS FIELD 6 HRS PLM SAMPLE 1200F STOP AT FIRST POSITIVE SAMPLE DESCRIPTION SAMLPLE # COMMENTS HOM. 5 17

RANSMITTAL OF RESULTS:

STANDARD TELEPHONE RESULTS TO FAX RESULTS TO

TELEPHONE #: FAX #:

BATCH #: 15

00 13330 TIME: TIME: K 1 2015 8 / 2015 CHAIN OF CUSTODY RECORD 121 DATE: DATE: JURAJ BARDIOVSKY LABORATORY ACCREDITATION: ELAP# 10955 RELINQUISHED BY: NVLAP# 101958 RECEIVED BY:

COMMENTS COMENTS COMMENTS	45	A MTHENICA ENVIRONMENTAL. TAL. SERVICES INC. HAMMACHTHIKGHTHITHE BLD	ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 11-29 IRVING AVE., QUEENS NY - LOT 42	<u>DATE</u> 12/4/2015	
STOP AT FIRST POSITIVE SAMPLE COMMENTS TELEPHONE #: 1000-1000 TELEPHONE #: TEL	INSPECTOR J. BARDIOVSKY	7 W. SIKORSKI	<u>OLIENT</u> CDM SMITH	PROJECT # IFB-3323-054-004-CS	# OF SAMPLES
STOP AT FIRST POSITIVE SAMPLE SAMPLE SAMPLE SAMPLE COMMENTS PLM PLM-NOB		30	X		
SAMPLE SAMPLE FIELD COMMENTS PLM PLM-NOB PLM PLM-NOB PLM PLM-NOB PLM PLM-NOB P		STOP AT FIRST POSITIVE		NOB-PLM [NOB-TEM 24 HRS
### TELEPHONE#: #### TELEPHONE#: FALL FLOW	× -		SAMPLE		ORATORY RESULTS PLM-NOB TEM-NOB
MMS MMS MMS MMS MMS MARCORD MARADIOVSKY MARCORD M	5)	VENT	roof		
MUS MINE MINE TELEPHONE #: FAX #: FAX #: FAX #: DATE: 21 21 2015 TIME: 12 3 3 TIME: 12 3 3 TIME: 12 3 3 3 TIME: 12 3 3 TIME: 12 3 3 3 TIME: 12 3 TIME: 13 3 TIME: 14 3 TIME: 14 3 TIME: 14 3 TIME: 14 3 TIME	()				M
TELEPHONE #: TELEPHONE #: TELEPHONE #: FAX #: ALBARDIOVSKY MAN WE DATE: 21 g 1 2015 TIME: 25 3 0 TIME: 12 3 3 0		CITY PARTS/CAR			1 24(-)
TELEPHONE #: FAX #: FAX #: AJ BARDIOVSKY MAIN OF CUSTODY RECORD AD BARDIOVSKY DATE: 21	9))			TWV T
TELEPHONE #: FAX #: AJ BARDIOVSK AJ BARDIOVSK AL BARDIOVSK AL BARDIOVSK AD BARDIOVSK AD BARDIOVSK AD BARDIOVSK AD BARDIOVSK AD BARDIOVSK BATCH #: BATCH #: BATCH #: BATCH #: 15 330					
TELEPHONE #: FAX #: FAX #: AJ BARDIOVSK AL BARDIOVSK AL BARDIOVSK DATE: 21 2 12 13 3 3 DATE: 12 5 2015 1 ME: 13 3 TIME: 13 3 3 DATE: 12 5 2015 1 ME: 13 3 TIME: 13 3 3 THE PHONE #: BATCH #: BATCH #: BATCH #: BATCH #: TIME: 13 3 3 TIME: 13 3 3 THE PHONE #: THE PHONE #: THE PHONE #: BATCH #: BATCH #: THE PHONE #: THE PHONE #: BATCH #: BATCH #: BATCH #: BATCH #: BATCH #: BATCH #: THE PHONE #: BATCH #: BATC					
TELEPHONE #: FAX #: GHAIN OF CUSTODY RECORD AJ BARDIOVSKY M DATE: /2					
AJ BARDIOVSKÝ JULÍ CHAIN OF. CUSTODY RECORD AJ BARDIOVSKÝ JULÍ DATE: 121 8 1 2015 TIME: 13 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	IRANSMITTAL O [] STANDARD [] TELEPHONE [] FAX RESULT	F RESULTS: RESULTS TO S TO	TELEPHONE #:	BATCH#:	
4J BARDIOVSKÝ (UM) DATE: 12 9 / 2015 TIME: 18 / 3 / 4 / 6 / 5 / 5 / 5 / 5 / 5 / 5 / 5 / 5 / 5			CHAIN OF CHISTODY RECORD		
Just Le Time: DATE: 121 8 1 2015 TIME: 13:	RELINQUIS	T	MUST DATE: 121 G	/ 2015	0
	RECEIVED BY:	Thelp for	121	/ 2015 TIME: /3:	2
	LABORATORY	ACCREDITATION:			



BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

PROJECT: 11-33 Indian Ave	TIPS II SO II NII BUYO	DATE OF REPORT: 12/08/15
CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 11104 PI	DAME OF ANY PROPERTY ACCOUNT	DATE OF AINALYSIS: 12/03/15

A CLEVE IN A	CHURL					
LABORATORY D#	MICROSCOPY RESULTS	УРУ	SAMPLE DESCRIPTION	FIBROUS	NON FIBROUS MATERIAL	% ASBESTOS AND
01	COLOR	Gray	Brick Mortar, Interior/Exterior	%0	100%	LYPE
15-12-025-01	# LAYERS	ı			8/001	(AAD)
	SCAN					
02	COLOR	Gray/Red	Brick Mortar, Interior/Exterior	%0	100%	CAN
15-12-025-02	# LAYERS	2				Text.
	SCAN					
03	COLOR	Gray	Brick Mortar, Interior/Exterior	%0	100%	NAD
15-12-025-03	# LAYERS	1				Text.
	SCAN					
04	COLOR	Gray	CMU Mortar, Interior	%0	100%	NAN
15-12-025-04	# LAYERS	1				O. C.
	SCAN					
05	COLOR	Gray	CMU Mortar, Interior	%0	100%	NAN
15-12-025-05	# LAYERS	1				-
	SCAN					
90	COLOR	Gray	CMU Mortar, Interior	%0	100%	NAD
15-12-025-06	# LAYERS	-				
	SCAN					



BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

. LIC. NY 11104 PROJECT: 11.33 Invina Ava	DATE OF REPORT: 12/08/15
CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 11104	DATE OF ANALYSIS: 12/03/15

A CI LATIO	CHEDEO					
LABORATORY ID#	MICROSCOPY RESULTS	OPY	SAMPLE DESCRIPTION	FIBROUS	NON FIBROUS MATERIAL	% ASBESTOS AND
07	COLOR	Brown/Brown	Gypsum Wall Board. Interior	5%CF1 I	7050	MAR
15-12-025-07	# LAYERS	2			0/66	NAD
	SCAN					
80	COLOR	Brown/Brown	Gypsum Wall Board, Interior	5%CFLI.	%50	247
15-12-025-08	# LAYERS	2			0/6/	NAN.
	SCAN					
60	COLOR	Brown/Gray	Gypsum Ceiling Board, Interior	3%CELL	%20	CAN
15-12-025-09	# LAYERS	2				OF I
	SCAN					
10	COLOR	Brown/Gray	Gypsum Ceiling Board, Interior	10%CELT.	%06	447
15-12-025-10	# LAYERS	2				NAD
	SCAN					
19	COLOR	Tan	Brown Paper Door Insulation,	100%CELL	%0	NAN
15-12-025-19	# LAYERS	1	Interior			TWI
	SCAN					
20	COLOR	Tan	Brown Paper Door Insulation,	100%CELL	%0	
15-12-025-20	# LAYERS	1	Interior			av.
	SCAN					



BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

PROJECT: 11-33 Irving Ave	DATE OF REPORT: 12/08/15
CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 1110	DATE OF ANALYSIS: 12/03/15

CLIENT ID# LABORATORY ID#	STEREO MICROSCOPY RESULTS)PY	SAMPLE DESCRIPTION	FIBROUS	NON FIBROUS MATERIAL	% ASBESTOS AND TYPE
21	COLOR	Beige	Panel Board Backing Paper,	70%CELL	14%	6%CH
15-12-025-21	# LAYERS	1	Interior, Abandoned Panel	10%SY		
		POINT				
22	COLOR		Panel Board Backing Paper,			AN AN
15-12-025-22	# LAYERS		Interior, Abandoned Panel			****
25	COLOR	Gray	Stucco, Exterior	%0	100%	NAD
15-12-025-25	# LAYERS	I				
	SCAN					
26	COLOR	Gray	Stucco, Exterior	%0	100%	NAD
15-12-025-26	# LAYERS	1				
	SCAN					
35	COLOR	Gray/White	Concrete/Cement Board at Ceiling,	%0	100%	NAD
15-12-025-35	# LAYERS	2	Interior			
	SCAN					
36	COLOR	Gray/White	Concrete/Cement Board at Ceiling,	%0	100%	NAD
15-12-025-36	# LAYERS	2	Interior			
	SCAN					



BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

ECT: 11-33 Irving Ave	DATE OF REPORT: 12/08/15
tal Services Inc. / 45-09 Greenpoint Ave., LIC, NY 11104 PROJECT	3/15 DATE
CLIENT: Athenica Environment	DATE OF ANALYSIS: 12/03

ANALYTICAL RESILL TS

CLIENT ID#	STEREO		SAMPLE DESCRIPTION F	FIRROIIS NON	NON	/0
LABORATORY ID#	MICROSCOPY RESULTS	¥.			FIBROUS ASBE MATERIAL AND	ASBESTOS AND TVPE
39	COLOR	Gray	Roof Insulation, Roof	3%CELT.	%20	CAN.
15-12-025-39	# LAYERS	-				O V
	SCAN					
40	COLOR	Gray	Roof Insulation, Roof	3%CFL1.	%20	447
15-12-025-40	# LAYERS	1				INAD
	SCAN					

Analyst:

Laboratory Director:

E. Dimitrakas

NAD: No Asbestos Detected, CELL: Cellulose, FBGL: Fiberglass, H: Hair, SY: Synthetics, CH: Chrysotile, AMOS: Amosite, TRE: Tremolite, ANTH: Anthophyllite, ACT: Actinolite, CRO: Crocidolite, VERM:

Analytical Methodologies: EPA 600/M4-82-020 (Point Count only) and ELAP Method 198.1.

Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

The liability of Laboratory Testing Services Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY 11104 PROJECT: 11-33 Irving Ave.	PROJECT: 11-33 Irving Ave.
ANALYT. METHODOLOGIES: ELAP 198.6, ELAP 198.4	LABORATORY ID #: 15-12-025
DATES OF ANALYSIS: 12/03/15	DATE OF REPORT: 12/04/15

TABOUT AGOTA OF THE

POSIT. /	Negat.	Negat.	Negat.	Negat.	Posit.	
TYPE OF ASBEST	NA	NA	NA	NA	NA	YZED
TEM		NAD	NAD	NAD	NA	SAMPLE NOT ANALYZED
TYPE OF ASBEST.	NA	NA	NA	NA	Chrys.	SAMPLE
PLM RESULTS	NAD	NAD	NAD	NAD	2.85	
%AII	52.45	55.99	15.91	13.25	20.72	25.93
%ASI	8.33	6.59	75.97	79.30	20.53	21.81
%ORG	39.22	37.43	8.12	7.45	55.89	52.26
LOCATION	Black Paper on Sheetrock Ceiling, Interior	Black Paper on Sheetrock Ceiling, Interior	Internal Window Putty, Interior	Internal Window Putty, Interior	Tar on Cinderblock Wall, Interior	Tar on Cinderblock Wall, Interior
LAB. ID #	15-12- 025-11	15-12- 025-12	15-12- 025-13	15-12- 025-14	15-12- 025-15	15-12- 025-16
CLIENT LAB. ID # #	11	12	13	14	15	16

ANALYST

E. Loukianova

LABORATORY DIRECTOR

E. Dimitrakas

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

PROJECT: 11-33 Irving Ave.	LABORATORY ID #: 15-12-025	DATE OF REPORT: 12/04/15
CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY 11104 PROJECT: 11-33 Irving Av	ANALY I. METHODOLOGIES: ELAP 198.6, ELAP 198.4	DATES OF ANALYSIS: 12/03/15

LABORATORY RESILTS

CLIENT	LAB. ID	LOCATION	000/0	O/ A CIT	27.4.70	2 5 5 5 5				
		NOTION	70UKU	%ASI	%AII	PLM RESILTE	TYPEOF	TEM	TYPE OF	
	15-12- 025-17	White Paint on Cinderblock Walls, Interior	37.50	30.47	32.03	NAD	NA	Trace	Chrys.	Negat.
	15-12- 025-18	White Paint on Cinderblock Walls, Interior	47.06	22.35	30.59	NAD	NA	Trace	Chrys.	Negat.
	15-12- 025-23	Black Panel Components (Bakelite), Interior	70.98	6.64	22.38	NAD	NA	NAD	NA	Negat.
	15-12- 025-24	Black Panel Components (Bakelite), Interior	71.18	7.29	21.53	NAD	NA	NAD	NA	Negat.
	15-12- 025-27	Pink Paint on Stucco, Exterior	50.00	11.43	38.57	NAD	NA	NAD	NA	Negat.
	15-12- 025-28	Pink Paint on Stucco, Exterior	49.14	1.72	49.14	NAD	NA	NAD	NA	Negat.

LABORATORY DIRECTOR E. Dimitrakas

ANALYST

E. Loukianova

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

NAD: No Asbestos Detected

The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. Ph.: (718) 389 3470, Fax: (718) 389 3471 LIC, NY 11104

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

The state of the s	
CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY 11104	oint Avenue, LIC, NY 11104 PROJECT: 11-33 Irvino Ave
	and an area of the second and area of the second ar
ANALY I. METHODOLOGIES: ELAP 198.6. ELAP 198.4	LABORATODY ID #. 15 12 025
	EABONALON ID #: 13-12-023
DATES OF ANALYSIS: 12/03/15	DATE OF PEDODT. 12/04/15
	DATE OF INET ONI: 12/04/13

POSIT. /	Negat.	Negat.	Negat.	Negat.	Negat.	Negat.
TYPE OF ASBEST	NA	NA	Chrys.	Chrys.	NA	NA
TEM	NAD	NAD	Trace	Trace	NAD	NAD
TYPE OF ASBEST	NA	NA	NA	NA	NA	NA
PLM	NAD	NAD	NAD	NAD	NAD	NAD
.%AII	4.17	3.94	80.81	80.25	59.23	54.00
%ASI	27.08	26.65	10.51	13.86	6.44	5.00
%ORG	68.75	69.41	69.8	5.89	34.33	41.00
LOCATION	Exp. Joint Sidewalk Caulking, Exterior	Exp. Joint Sidewalk Caulking, Exterior	Asphalt at Exterior Base of Building, Exterior	Asphalt at Exterior Base of Building, Exterior	Textured Gray Paint on Metal Beams, Interior	Textured Gray Paint on Metal Beams, Interior
CLIENT LAB. ID # #	15-12- 025-29	15-12- 025-30	15-12- 025-31	15-12- 025-32	15-12- 025-33	15-12- 025-34
CELENI #	29	30	31	32	33	34

LABORATORY DIRECTOR

E. Dimitrakas

E. Loukianova ANALYST

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

NAD: No Asbestos Detected

The liability of LTS Inc., witl. sspect to the services charged, shall in no event exceed the amount of the invoice.



BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY

AND TRANSMISSION ELECTRON MICROSCOPY

PROJECT: 11-33 Irving Ave.	I ARODATODVID #. 15 10 005	C70-71-C1 :# (1 I NO I WING TO-17-07)	DATE OF REPORT. 12/04/15
CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY 11104 PROJECT: 11-33 Irving	ANALYT. METHODOLOGIES: ELAP 198.6, ELAP 198.4	DATES OF ANALYSIS. 12/02/15	DATES OF AIMLESIS: 12/03/13

LOCATION %ORG %ASI PASIL TYPE OF TEM TYPE OF TEM TYPE OF TYPE OF TYPE OF TYPE OF ASBEST. TYPE OF		NEGAT.	Posit	Posit.		LYZED	Posit.
ION %ORG %ASI PLM TYPE OF ASBEST rim, Roof 73.85 19.27 6.19 0.69 Chrys. rim, Roof 70.13 15.91 12.37 1.59 Chrys. ane, Roof 64.92 6.30 21.20 7.58 Chrys. ane, Roof 61.64 5.64 32.73 SAMPLE N lg, Roof 53.61 10.54 35.12 0.72 Chrys. lg, Roof 51.71 7.52 38.57 2.20 Chrys.	TYPE OF	NOT ANA	NA	NA	YZED	NOT ANA	NA
ION %ORG %ASI %AII PLM Prim, Roof 73.85 19.27 6.19 0.69 Prim, Roof 70.13 15.91 12.37 1.59 ane, Roof 64.92 6.30 21.20 7.58 ane, Roof 61.64 5.64 32.73 1.58 Ig, Roof 53.61 10.54 35.12 0.72 Ig, Roof 51.71 7.52 38.57 2.20	TEM	SAMPLE	NA	NA	NOT ANAI	SAMPLE	NA
Trim, Roof %ASI %AII Trim, Roof 73.85 19.27 6.19 Trim, Roof 70.13 15.91 12.37 ane, Roof 64.92 6.30 21.20 ane, Roof 61.64 5.64 32.73 ag, Roof 53.61 10.54 35.12 ag, Roof 51.71 7.52 38.57	TYPE OF	Chrys.	Chrys.	Chrys.	SAMPLE	Chrys.	Chrys.
Trim, Roof %ASI Trim, Roof 73.85 19.27 Trim, Roof 70.13 15.91 ane, Roof 64.92 6.30 ane, Roof 61.64 5.64 lg, Roof 53.61 10.54 lg, Roof 51.71 7.52	PLM	0.69	1.59	7.58		0.72	2.20
Trim, Roof 73.85 Trim, Roof 70.13 ane, Roof 64.92 ane, Roof 61.64 lg, Roof 53.61	%AII	61.9	12.37	21.20	32.73	35.12	38.57
rim, Roof rim, Roof ane, Roof ane, Roof ag, Roof	%ASI	19.27	15.91	6.30	5.64	-	-
LOCATION Tar on Edge Trim, Roof Roof Membrane, Roof Roof Flashing, Roof Roof Flashing, Roof	%ORG	73.85	70.13	64.92	61.64	53.61	51.71
	LOCATION	Tar on Edge Trim, Roof	Tar on Edge Trim, Roof	Roof Membrane, Roof	Roof Membrane, Roof	Roof Flashing, Roof	Roof Flashing, Roof
### 15-12- 025-37 15-12- 025-38 15-12- 025-41 15-12- 025-42 15-12- 025-42 15-12- 025-42 15-12- 025-43 15-12- 025-44	CLIENI #	37	38	41	42	43	44

LABORATORY DIRECTOR E. Dimitrakas

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

ANALYST A. Aquino

Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE, Ph.: (718) 389 3470, Fax: (718) 389 3471 LIC, NY 11104

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

nue, LIC, NY 11104 PROJECT: 11-33 Irving Ave.	LABORATORY ID #: 15 12 025	10-12-023	DATE OF REPORT: 12/04/15
CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY 11104	ANALYT. METHODOLOGIES: ELAP 198.6, ELAP 198.4	DATES OF ANALYSIS. 10/00/12	DATES OF ANALISIS: 12/03/13

-	Posit.		Posit		Posit.	
TYPE OF	NA	YZED	NA	YZED	NA	YZED
TEM RESULTS	NA	SAMPLE NOT ANALYZED	NA	SAMPLE NOT ANALYZED	NA	SAMPLE NOT ANALYZED
TYPE OF ASREST	Chrys.	SAMPLE	Chrys.	SAMPLE	Chrys.	SAMPLE
PLM	2.25		10.90		2.62	
%AII	12.97	10.65	21.84	13.23	19.60	16.39
%ASI	15.75	18.48	5.31	1.45	64.10 13.68	1.00
%ORG	69.03	70.87	61.95	85.32	64.10	82.61
LOCATION	Pitch Pocket Tar, Roof	Pitch Pocket Tar, Roof	Flashing on Roof Fans, Roof	Flashing on Roof Fans, Roof	Drain Flashing, Roof	Drain Flashing, Roof
CLIENT LAB. ID # #	15-12- 025-45	15-12- 025-46	15-12- 025-47	15-12- 025-48	15-12- 025-49	15-12-
# EN	45	46	47	48	49	50

LABORATORY DIRECTOR

E. Dimitrakas

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

ANALYST A. Aquino

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability CLTS Inc., with respect to the services charged, shall in no event exceed the amou. Cof the invoice.



LABORATORY TESTING SERVICES INC. LIC, NY 11104 Ph.: (718) 389 3470, Fax: (718) 389 3471 45-09 GREENPOINT AVE.

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

ig Ave.	15-12-025	12/04/15
ental / 45-09 Greenpoint Avenue, LIC, NY 11104 PROJECT: 11-33 Irving Av	LABORATORY ID #: 15-12-025	DATE OF REPORT: 12/04/15
目	ELAP 198.6, ELAP 198.4	
CLIENT / ADDRESS: Athenica Env	ANALY I. METHODOLOGIES: EL.	DATES OF ANALYSIS: 12/03/15

LABORATORY RESILTS

ENT LAD						The second second second			
# # #	LOCATION	%ORG	%ORG %ASI	%AII	PLM PECIITE	TYPE OF	TEM TYPE OF POSIT. /	TYPE OF	POSIT. /
15-13	Concessor Placking D.	4. 60			NESOLIS	ASBEST.	KESULIS	ASBEST.	NEGAT.
025-5	Oboseneck Flashing, Kool	82.13	82.13 2.13 9.44	9.44	6.29	Chrys.	NA	NA	Posit.
01 31	i								
025-5	Cooseneck Flashing, Roof	81.17	81.17 0.62 18.21	18.21		SAMPLE	SAMPLE NOT ANALYZED	LYZED	

ANALYST A. Aquino

LABORATORY DIRECTOR E. Dimitrakas

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

 - NAD: No Asbestos Detected
 The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.

SAMPLE SAMPLE DESCRIPTION MORTH A. BANDOVSKY	STOP AT FIRST POSITIVE SAMPLE SAM		ATHEN SERVICE BEATER	A STRANCY ENVIRONMENTAL TAPOSE ENVIRONMENTAL TAPOSE INC. ENVIRONMENTAL TAPOSE ENVIRONMENTAL T	ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 11-33 IRVING AVE QUEENS NY - LOT 33	<u>DATE</u> 10/20/2015	
SAMPLE SA	SAMPLE SAMPLE SAMPLE SAMPLE SAMPLE SAMPLE SECRIPTION TO WARL FAVE TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: THE SAMPLE THE SAMPL	INSPECTO J. BARDIO	VSKY/ W. SIK	ORSKI	CDM SMITH	PROJECT #	# OF SAMPL
SAMPLE SAMPLE SAMPLE DESCRIPTION LOCATION INTERIOR INT	SAMPLE SAMPLE SAMPLE DESCRIPTION LOCATION DESCRIPTION MUCHAL	COMMENT	11125	AT FIRST POSITIVE		s	
MORTH A- INTERIOR PATERIOR MORTH A- INTERIOR MORTH A- INTERIOR WIN CELLING BARCH PARIS BARCH PARIS RACK CELLING RACK CELL	MORTH C. INTERIOR PATERIOR MORTH C. INTERIOR MORT	HOM. AREA	SAMLPLE #	SAMPLE DESCRIPTION	SAMPLE	FIELD	BORATORY RE
MORTH RANGE (1) TEREBOOK (1) AND (1) A	MORTARA INTERECTOR INT	-		BRICK MURTHR	ERIOR 1		3
MORTA C. MORTA C. MAN WALL BOATS UM CELLING BLACE MAD RACE R	MORTH A. INTERIOR UM WALL BAND UM CELLING BARCH CHILM A.BARDIOVSKY MACCHILM A.BARDIOVSKY MACCHILM A.BARDIOVSKY MACCHILM A.BARDIOVSKY MACCHILM A.BARDIOVSKY MACCHILM DATE: 1/21 2 / 2015 TIME: 16:30 TIME: 16:30	-	7				
WIN CELL NIGHTER LOR RARED WIN CELL NIGHT RARED	MORTH ILL INTERIOR UM WALL BAND BLACK OFILING AJBARDIOVSKY AJBARDIOVSKY ALAND AJBARDIOVSKY ALAND AJBARDIOVSKY ALAND AJBARDIOVSKY ALAND AJBARDIOVSKY ALAND AJBARDIOVSKY AJ	-	vi :		9		
AD BARDIOVSKY ALBARDIOVSKY A	UM WALL BANDS BLOCK OFILING RACE OF THE FACTOR TO THE FAX #: FAX #: CHANO	"	50		INTERIOR		011/-1
UM WALL BOARD LUM CELLING BUKL PROBL C-1 LA C-1 LA	WALL BUREL OF THE PHONE #: PLACE OF THE PHONE #: FAX#: TELEPHONE #: FAX#: A BARDIOVSKY CHARD (-) LAC (-	2	2	6			
BURL PROED PLACE ORUMN TELEPHONE #: FAX #: TELEPHONE #: TELEPHONE #: FAX #: DATE: 1/2/2 / 2015 TIME: 1/6/30	BURL PROBLEMAN OF CUSTODY RECORD A. BARDIOVSKY A. INME: 15.30 A. BATCH#: 15.30 A. BARDIOVSKY A. BARDIOVSKY A. INME: 16.30	3	1				0000
BURL PROEL PROEL PROEL PROEL PROCESSAL CHILD CHAIN OF CUSTODY RECORD AJ BARDIOVSKY AJ BARDIOVSKY AL BARDIOVS	BURCL PROBLE RUCL PROBLE RUCL PROBLE THEEPHONE #: FAX #: AJ BARDIOVSKY AJ BARDIOVSKY AJ BARDIOVSKY AN ECORD AD BARDIOVSKY AN ECORD AN ECORD AN ECORD AD BARDIOVSKY AN ECORD	3	.00	1			Craw -
BURL PROED PLAKE PROED TELEPHONE #: FAX #: AJ BARDIOVSKY THAT DATE: 12/2 2 / 2015 TIME: 16/30	BURLL PROBLE BURLL PROBLE TELEPHONE #: FAX #: AJ BARDIOVSKY AJ BARDIOVSKY AL	'n	6	GAPSUM CEIUNG			SALL
TRUCK CRUIN TELEPHONE #: FAX #: AJ BARDIOVSKY TIME:	THE CHUIN TELEPHONE #: FAX #: AJ BARDIOVSKY AJ B	7	. 9	CLAR. A.			7, 42, 7
TROCK CELLIN STATE	THE CALLINAL TELEPHONE #: FAX #: AJ BARDIOVSKY AJ BARDIOVSKY AL MAIN OF CUSTODY RECORD A. BARDIOVSKY A. B	S		BURCE			1110011-1
TELEPHONE #: FAX #: AJ BARDIOVSKY AJ BARDIOVSKY AL MAIN OF CUSTODY RECORD A BARDIOVSKY A LIKARA A LIKARA A LIME: 12.2 2 12015 TIME: 16.30	AJ BARDIOVSKY A. BARDIOVSKY A. BARDIOVSKY A. BATCH#: 15 - BATCH#: 15	8	17	TROCK	->-		
4J BARDIOVSKY A	AJ BARDIOVSKY (AAIN OF CUSTODY RECORD (A. 91) KPARA (A. 92) (A. 93)	TRANSMITT,	AL OF RESULTAND) -
AJ BARDIOVSKY TIME: CHÁIN OF CUSTODY RECORD AJ BARDIOVSKY A SIKARA DATE: 121 2 1 2015 TIME: 16	AJ BARDIOVSKY CHÁIN OF CUSTODY RECORD 1. А J I K P & I C. 1 2 1 2015 TIME: 6. 1. А J I K P & I C. 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1 2 1	I JELEPH I JEAX RES	SULTS TO	010	TELEPHONE #: FAX #:	ВАТ	1.
AJ BARDIOVSKY (TIME: 16. 12.12.12.15 TIME: 16. 16. 12.12.12.12.15 TIME: 16. 16. 16. 16. 16. 16. 16. 16. 16. 16.	LA 41KARA TIME: 121 2 1 2015 TIME: 16.				CHAIN OF CUSTODY RECORD		
1. A YIKARA TIME: 121 2 1 2015 TIME: 16:	1. A 41 KARA (46.1) DATE: 121 2 1 2015 TIME: 16:	RELINC	SUISHED BY:	JURAJ BA	MM DATE: 12,2		5.30
	NVLAP# 101958 ELAP# 10955	RECEIVED LABORATO	BY:	4	121		6:30

SAMPLES PROJECTIFE PROJEC		ATHER SERVICE STATES	SERVICES INC. BENEFICIAL BALL BENEFICES INC.	ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 11-33 IRVING AVE., QUEENS NY - LOT 33	<u>DATE</u> 10/20/2015	
SAMPLE SAMPLE SAMPLE DESCRIPTION TO THE LOCATION THE NUMBER OF THE LOCATION	INSPECTC J. BARDIO	<u>NVSKY/ W. SIK</u>	ORSKI	CDM SMITH	PROJECT # IFB-3323-054-004-CS	# OF SAMPL
SAMPLE SAMPLE SAMPLE FIELD LABORATORY REDESCRIPTION LABORATORY RECORD LABORATORY R	COMMENT		AT FIRST POSITIVE		8	
NAL WINDOWS IN TERING. 1	HOM. AREA	SAMLPLE #	SAMPLE DESCRIPTION	SAMPLE LOCATION		BORATORY RE
PANT CONTRACT FAUL COMPANY SECURE ALBARDIOVSKY ALBARDIOVSKY CLAMBER C	9	13	INTERNAL WINDOW	NTERI		(-)
PANT ON PAIR RELATION BARCE CODE APTION BARCE CODE APTION BARCE CODE ABARDIOVSKY ALBARDIOVSKY A	94	14	0			1
PANDLE COMPAGNE ALBARDIOVSKY	++	10	NA			2
ABARDIOVSKY AL HARDEN BONE AL BARDIOVSKY AL BARD	00	4	H			11/00/11
PAREL COMPUTANTS TELEPHONE #: FAX#: TELEPHONE #: FAX#: A 4 IKARA A BARDIOVSKY A 4 IKARA A BARDIOVSKY TOTAL AND A BARDIOVSKY A 4 IKARA A BARDIOVSKY TOTAL AND A BARDIO	00	9	CINDERPROPERTY INMINS			
PANEL EUMPARIN ABRADOVED PANEL 116.0 YCM 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0 15.0	0	10	BYCOMIN PAPER DODE)	100
PERCENTION OF CUSTODY RECORD A 4 IKARA A TARA A TA	-	2,	SUPTU		J->	
TELEPHONE #: FAX #: TELEPHONE #: FAX #: AJ BARDIOVSKY AJ BARD	or	17	BURGO) PAREL (-16.0 /CU
TELEPHONE #: BATCH #: LA 4 KARCA CHAIN OF CUSTODY RECORD TIME:	3:	22	MER		7	/ / W
TELEPHONE #: FAX #: CHAIN OF CUSTODY RECORD AJ BARDIOVSKY AJ BARDIOVSKY DATE: 12/2 / 2015 TIME: 16/30 TIME: 16/30	==	52	A PART			(-) 0 = N -)
AJ BARDIOVSKÝ AJ BARDIOVSKÝ AJ BARDIOVSKÝ AJ BARDIOVSKÝ A J IKARA A DATE: 121 2 1 2015 TIME: 16 30 TIME: 16 30	RANSMITT	FAL OF RESUL	4	A	9	1
AJ BARDIOVSKY AL HARDA AJ BARDIOVSKY AJ BARDIOVS	TELEPH TFAX RE	HONE RESULT: SULTS TO	вто	TELEPHONE #: FAX #:	BATCI	71-
AJ BARDIOVSKY AJ BARDIOVSKY AJ SARDIOVSKY AJ SARDIOVSKY AJ SARDIOVSKY SALDIOVSKY ADATE: 121 2, 1 2015 TIME: 16 3				CHAIN OF CUSTODY RECORD	4	
	RELING	QUISHED BY BY:	AJ BAI	121	TIME: //	
	ABORATO	ORY ACCREE				

INSPECTOR I BAPDIOVS	Libert	TAMEDIATING OF CHAIR COLOR	WOLFF-ALPORT CHEMICAL CO SITE, 11-33 IRVING AVE., QUEENS NY - LOT 33	10/20/2015	
	<u>INSPECTOR</u> J. BARDIOVSKY/ W. SIKORSKI		CLIENT CDM SMITH	PROJECT # IFB-3323-054-004-CS	# OF SAMPLES
COMMENTS	STOP	STOP AT FIRST POSITIVE		PLM NOB-PL	NOB-PLM NOB-TEM
HOM.	SAMLPLE #	SAMPLE DESCRIPTION	SAMPLE LOCATION	FIELD	LABORATORY RESULTS PLM PLM-NOB TEM-NOB
1.2	25	STUCCO	EXTERIOR		5
15	26	9			
(3	27	PINC PAINTON			8717 CENT
(3	28	STUCLO			
2	8	EXP. JOINT SIDEMAIK			TIMES () AND
5	20	CAULCING			
(5	35	ASPHALT AT EXTERIOR			0x (-) 00 / (-)
0	32	CHASE OF BLOG.			
9	33	TEXTURED EARLY DAINT	INTERIOR		81777
9)	34	ON METAL BEAMS			
2+	35	CONCACTE / LEMENT			C 44 D
4	36	RUMIND AT CENTING			
IRANSMITTAL OF RESULTS: STANDARD TELEPHONE RESULTS TO 1FAX RESULTS TO	OF RESULT	'S: 5.T0	TELEPHONE #: FAX #:		ВАТСН#: 15 -/\.
			CHAIN OF CUSTODY RECORD		
RELINQUI	RELINQUISHED BY:	JURAJ BAR	10066 , DATE: 1/21	2 / 2015 TIME: /	6:30
RECEIVED BY		J.A.YIXART	14(4/4) DATE: 121	2 / 2015 TIME:	16.30
LABORATORY ACCREDITATION: NVI AP# 101958 FI AP# 10955	T ACCREL	KEDITATION:	1		

COM SMITH COMMENTS SAMPLE LOCATION COMMENTS FIELD COMMENTS FIELD COMMENTS FIELD FIELD FIELD COMMENTS FIELD FIELD FIELD COMMENTS FIELD FIELD COMMENTS FIELD FIELD FIELD COMMENTS FIELD FIELD FIELD FIELD COMMENTS FIELD FI		ATHEM SERVICE	A THENICA ENVIRONMENTAL. TAL. FEMOGRAPHICOTOHICAL ALL FEMOGRAPHICOTOHICAL ALL	ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 11-33 IRVING AVE., QUEENS NY - LOT 33	<u>DATE</u> 10/20/2015	
SAMPLE DESCRIPTION ALL ON BETRUM BETR	J. BARDION	R/SKY/W. SIK	DRSKI	CDM SMITH	PROJECT #	# OF SAMPLES
SAMPLE DESCRIPTION LOCATION ROOF INSULATION OOF MEMPARAME CONTRACT ASHING ASHING ASHING ASHING ASHING ASHING CHAINOF CUSTODY RECORD IIIPAI BARDINASIA CHAINOF CUSTODY RECORD	COMMENT		AT FIRST POSITIVE			-PLM NOB-TEM RS 24 HRS
DOF INSULATION BOOK MEMBRANE CHAINS ON ROOF FAX#: FAX#: CHAINOF CUSTODY RECORD	HOM. AREA	SAMLPLE #	SAMPLE DESCRIPTION	SAMPLE LOCATION	FIELD	LABORATORY RESULTS PI M PI M-NOR TEM-NOR
DOF INSULATION BOOF MEMBRAINS ITCH PAIRET TARE ASHING SIN ROOF FAX#: FAX#: CHAINOF CUSTODY RECORD	200		N	ROOF,		(-)0.697
ASHING ON ROOF FAX#: FAX#: TELEPHONE#: FAX#: TELEPHONE#: FAX#: TELEPHONE#: FAX#: TELEPHONE#: FAX#:	00	87	d ACA			(+)1.59/CM
DOF MEMBRANE LOUF ALASHING ASHING ON ROOF PITCH POLICE TARR ASHING ON ROOF FAX#: FAX#: TELEPHONE #: FAX#: TELEPHONE #: FAX#:	5)	29	1000			-1800
ASHING ON ROOF FAX: FAX: TELEPHONE #: FAX: CHAIN OF CUSTODY RECORD	20	14	ROOF MEMBRAILE			MU/89 E(+)
ANHING ON ROOF FALLS TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: TELEPHONE #: FAX #: TELEPHONE #: TELEPHONE #: FAX #: FAX #: TELEPHONE #: FAX #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: FAX #: TELEPHONE #: FAX #:	2	25	g			NA NA
ASHING ON ROOF PHUS TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: TELEPHONE #: FAX #: FAX #: TELEPHONE #: FAX FAX #: FAX #: FAX F	2	43				かんした。ロノーノ
ASHING ON ROOF FAXE: FAXE: FAXE: CHAIN OF CUSTODY RECORD	26	UN CIN	9			(+)2.2/en
ASHING- ON ROOF WINDS TELEPHONE #: FAX #: CHAIN OF CUSTODY RECORD	36	53	は一年			(+12.28)CM
TELEPHONE #: FAX #: FAX #: CHAIN OF CUSTODY RECORD	32	47	5			14
FAX#: FAX#: CHAIN OF CUSTODY RECORD	23	817	FILS			1/0/1/2M
BY: I BA I BABDIOVSKY	TRANSMITT	AL OF RESULT: RD ONE RESULTS		TELEPHONE # :	- Ved	
INIBA I BABDIOVSKY						77
DAIE: 2015	RELING	UISHED BY:	JURAJ BARDIOVSKY	CHAIN OF CUSTODY RECORD DATE: 21 2	J 2015 TIME:	8:3
RECEIVED BY:	RECEIVED ABORATO	BY: RY ACCREDI	7.4	121		530

J. BARDIOVSKY/ W. SIKORSKI COMMENTS STOP AT FIRST POSITIVE HOM. SAMIPLE BESCRIPTION 24 49 DRAIN FLASK(NG-ROOF) CLIENT CDM SMITH CDM S	PROJECT# IFB-3323-054-004-CS PROJECT#	NOB-PLM NOB	# OF SAMPLES
STOP AT FIRST POSITIVE SAMLPLE BESCRIPTION UP DESCRIPTION DESCRIPTION			
SAMLPLE SAMPLE # DESCRIPTION # 149 DRAIN FLASKING ROOF			W EW
25 51 (5068000 masure)		PLM PLM-NOB TEM-N (4)2.62/CH (4)6.29/CH (4)6.29/CH	TEM-NOB
NCMITAL OF DEGLI TO			
STANDARD TELEPHONE #: STANDARD TELEPHONE #: STANDARD TELEPHONE #: FAX RESULTS TO FAX#: FAX#: FAX RESULTS TO FAX#: FAX#: FAX RESULTS TO FAX#:	ONE#:	BATCH#: 15 - /2	12-0W
RECEIVED BY: JURAJ BARDIOVSKY RECEIVED BY: A STRAIGHT OF STRAIGHT	DATE: 2 2015 TIME: DATE: 12 2 2015 TIME:	IE: /6:30 IE: /6:30	



BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 11104 PROJECT:	15-14 Cooper Ave Oneens
DATE OF ANALYSIS: 12/04/15	ATE OF DEPODT. 12/00/15

CLIENT ID# LABORATORY	STEREO	PY	SAMPLE DESCRIPTION	FIBROUS	NON	% SEPECTOS
ID#	RESULTS				MATERIAL	AND TYPE
01	COLOR	Brown	Brick Mortar, Interior/Exterior	%0	100%	NAD
15-12-032-01	#LAYERS	1				
	SCAN					
02	COLOR	Brown	Brick Mortar, Interior/Exterior	%0	100%	NAD
15-12-032-02	# LAYERS	1		9		
	SCAN					
03	COLOR	Brown	Brick Mortar, Interior/Exterior	%0	100%	NAD
15-12-032-03	# LAYERS	_				
	SCAN					
04	COLOR	Brown	Cinderblock Mortar,	%0	100%	NAD
15-12-032-04	# LAYERS	1	Interior/Exterior			
	SCAN					
05	COLOR	Brown	Cinderblock Mortar,	%0	100%	NAD
15-12-032-05	# LAYERS	1	Interior/Exterior			
	SCAN					
90	COLOR	Brown	Cinderblock Mortar,	%0	%001	NAD
15-12-032-06	# LAYERS	4	Interior/Exterior			
	SCAN					



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104
Ph.: (718) 389 3470, Fax: (718) 389 3471

BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

LIC, NY 11104 PROJECT: 15-14 Cooner Ave Oneens	DATE OF REPORT: 12/08/15
CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LI	DATE OF ANALYSIS: 12/04/15

ANALYTICAL RESULTS

CLIENT ID# LABORATORY ID#	STEREO MICROSCOPY RESULTS	OPY	SAMPLE DESCRIPTION	FIBROUS MATERIAL	NON FIBROUS MATERIAL	% ASBESTOS AND
						TYPE
60	COLOR	White/Brown	Wall Sheetrock, Interior	45%CELL	55%	NAD
15-12-032-09	#LAYERS	2				
	SCAN					
10	COLOR	White/Brown	Wall Sheetrock, Interior	60%CELL	40%	NAD
15-12-032-10	#LAYERS	2				
	SCAN					
11	COLOR	White/Brown	Ceiling Sheetrock, Interior	25%CELL	75%	NAD
15-12-032-11	# LAYERS	2				
	SCAN					
12	COLOR	White/Brown	Ceiling Sheetrock, Interior	20%CELL	%08	NAD
15-12-032-12	# LAYERS	2				
	SCAN					
23	COLOR	White	Door Mortar, Facades	%0	100%	NAD
15-12-032-23	# LAYERS	1				
	SCAN					
24	COLOR	White	Door Mortar, Facades	%0	100%	NAD
15-12-032-24	# LAYERS	1				
	SCAN					



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104 Ph.: (718) 389 3470, Fax: (718) 389 3471

BULK SAMPLE ANALYSIS BY POLARIZED LIGHT MICROSCOPY

CLIENT: Athenica Environmental Services Inc. / 45-09 Greenpoint Ave., LIC, NY 11104	NY 11104 PROJECT: 15-14 Cooper Ave Oneens
DATE OF ANALYSIS: 12/04/15	DATE OF REPORT: 12/08/15

E. Dimitrakas

Laboratory Director:

NAD: No Asbestos Detected, CELL: Cellulose, FBGL: Fiberglass, H: Hair, SY: Synthetics, CH: Chrysotile, AMOS: Amosite, TRE: Tremolite, ANTH: Anthophyllite, ACT: Actinolite, CRO: Crocidolite, VERM:

Analytical Methodologies: EPA 600/M4-82-020 (Point Count only) and ELAP Method 198.1.

K. Esnard

Analyst:

Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.

The liability of Laboratory Testing Services Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



LABORATORY TESTING SERVICES INC. Ph.: (718) 389 3470, Fax: (718) 389 3471 45-09 GREENPOINT AVE. LIC, NY 11104

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

ANALYT. METHODOLOGIES: ELAP 198.6, ELAP 198.4 DATES OF ANALYSIS: 12/04/15 DATE OF REPORT: 12/08/15	CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenmoint Avenue 11C NV 11104	PBO IECT. 15 14 6-1111
S: ELAP 198.6, ELAP 198.4 15	The state of the s	INCIECT: 13-14 Cooper Ave., Queens
115	P 198.6, ELAP 198.4	LARORATORY ID #: 15_12_032
15		13-12-032
	DATES OF ANALYSIS: 12/04/15	DATE OF REPORT: 12/08/15

LABORATORY RESULTS

NA NA NA NA Chrys.	LAB. ID #	LOCATION	%ORG	%ASI	%AII	PLM	TYPE OF	TEM	TYPE OF	POSIT. /
Under Blocks, 28.04 12.62 59.35 NAD NA Roof at Back 48.03 13.68 32.55 NAD NA Roof at Back 49.38 13.83 36.79 NAD NA coof at Back 45.21 7.31 43.69 3.80 Chrys. coof at Back 56.37 6.76 36.87 SAMPLE N		White Coating on Bricks/Under Blocks,	28.16	16.09	55.75	NAD	ASBEST. NA	NAD	ASBEST. NA	NEGAT.
Roof at Back 48.03 13.68 32.55 NAD NA Roof at Back 49.38 13.83 36.79 NAD NA Roof at Back 45.21 7.31 43.69 3.80 Chrys. Roof at Back 56.37 6.76 36.87 SAMPLE N		White Coating on Bricks/Under Blocks, Interior	28.04	12.62	59.35	NAD	NA	NAD	NA	Negat.
Roof at Back 49.38 13.83 36.79 NAD NA Roof at Back 45.21 7.31 43.69 3.80 Chrys. Roof at Back 56.37 6.76 36.87 SAMPLE N			48.03	13.68	32.55	NAD	NA	5.74	Chrys.	Posit.
45.21 7.31 43.69 3.80 56.37 6.76 36.87	-		49.38	13.83	36.79	NAD	NA	SAMPLE	SAMPLE NOT ANALYZED	LYZED
56.37 6.76 36.87	-	Roof Flashing, Small Roof at Back	45.21	7.31	43.69	3.80	Chrys.	NA	NA	Posit.
		Roof Flashing, Small Roof at Back	56.37	92.9	36.87		SAMPLE	NOT ANA	LYZED	

LABORATORY DIRECTOR

E. Dimitrakas

ANALYST

E. Loukianova

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104
Ph.: (718) 389 3470, Fax: (718) 389 3471

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

	43-09 Greenpoint Avenue, LIC, NY 11104 PROJECT: 15-14 Cooper Ave., Onegns	2	LABORATORV ID #: 15-12-032	12-17-17-17-17-17-17-17-17-17-17-17-17-17-	DATE OF DEDODT: 12/00/15	DATE OF NEIONIS
CITENT / ADDESC. Attoniog Par.	cinca Environmental /		ANALY I. METHODOLOGIES: ELAP 198.6, ELAP 198.4	The state of the s	DATES OF ANALYSIS: 12/04/15	

TYPE OF POSIT. / ASBEST NEGAT	Posit.	LYZED	Negat.	Negat.	Negat.	Posit.
TYPE OF ASBEST	Chrys.	NOT ANA	NA	NA	NA	Chrys.
TEM		SAMPLE NOT ANALYZED	NAD	NAD	NAD	6.20
TYPE OF ASBEST.	Chrys.	Chrrys.	NA	NA	NA	NA
PLM RESULTS	Trace	Trace	NAD	NAD	NAD	NAD
%AII	7.56	20.62	25.62	23.56	44.76	24.82
%ASI	13.19	1.41	4.68	5.94	2.38	5.71
%ORG	77.36	77.97	02.69	70.50	52.86	63.27
LOCATION	Roof Tar on Walls, Small Roof at Back	Roof Tar on Walls, Small Roof at Back	Tar Above Store Gate, Facades	Tar Above Store Gate, Facades	Tar/Paint (Purple) on Wall, Facades	Tar/Paint (Purple) on Wall, Facades
CLIENI LAB. ID # #	15-12- 032-17	15-12- 032-18	15-12- 032-19	15-12- 032-20	15-12- 032-21	15-12-
CCIEN!	17	18	19	20	21	22

ANALYST

E. Loukianova

LABORATORY DIRECTOR E. Dimitrakas

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the servic charged, shall in no event exceed the amount of the invoice.

		SENICES INC. ETHIOTETHICOTTHING AND	<u>ADDRESS</u> WOLFF-ALPORT CHEMICAL CO SITE, 15-14 COOPER AVE., QUEENS NY - LOT 48	<u>DATE</u> 10/24/2015	
NSPECTOR J. BARDIOVS	INSPECTOR J. BARDIOVSKY/ W. SIKORSKI		CLIENT CDM SMITH	PROJECT # IFB-3323-054-004-CS	# OF SAMPLES
COMMENTS		STOP AT FIRST POSITIVE		RLM NOB-PLM A	ILM NOB-TEM
HOM. AREA	SAMLPLE #	SAMPLE	SAMPLE	FIELD	BORATORY RE
-		ROLLIN MONTHO	INTERIOR POTTER 100	S.	PLM PLM-NOB TEM-NOB
_	2	1			1000
-	3				
7	5	LAINDERCHACK MARTHE			11/100
7	5			<u>-ر</u>	
7	9	0			
~	+	WHITE COATINGON	INTERIOR	7	1 4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
2	3	BALLUKS/LINDERBILLK			
5	CA	WALL SHEPTROOP		<u>-</u> J	1/40
h	0)	(8)			7.4
5	=	CELLING SAPENDON			CW 1
5	17	1	0		
STANDARD J TELEPHONE	TRANSMITTAL OF RESULTS: [] STANDARD [] TELEPHONE RESULTS TO	S: TO	TELEPHONE #:	† SLY	
TAN A	SOLIS IO		FAX#:	O RO	750-71 - CT :##
RELIN	RELINQUISHED BY:	JURAJ BARDIOVSKY	CHAIN OF CUSTODY RECORD	2015 TIME : 1 (U.	0.0
RECEIVED BY:	RECEIVED BY:	4 HOLLIND	1 CO11 20 DATE: 121 2		

		A THENICA ENVIRONMENTAL TAL SERVICES INC.	ADDRESS WOLFF-ALPORT CHEMICAL CO SITE, 15-14 COOPER AVE., QUEENS NY - LOT 48	<u>DATE</u> 10/24/2015	
INSPECTOR J. BARDIOV	INSPECTOR J. BARDIOVSKY/ W. SIKORSKI	ORSKI	CLIENT CDM SMITH	PROJECT # IFB-3323-054-004-CS	# OF SAMPLES
COMMENTS		STOP AT FIRST POSITIVE		PLM NOB-PLM NOB-PLM NOB-PLM	-PLM NOB-TEM
HOM. AREA	SAMLPLE #	SAMPLE DESCRIPTION	SAMPLE LOCATION	TS	LABOR
9	(3	ROOF MEMBRANE	SMAU ROOF AT BACK		(-) 1 AB
٥	2	9			0.1
+0	5	ROX tysting			(+)2,8/CH NA
+ 0	0 14	Novy TAD ANIMALS			C CAN IN THE STATE OF THE STATE
2	(3		-37		F / 18.1 (+) 1.81/
5	6)	TAR ABOVE STORE	FACADES		001(-) 001(-)
5 9	20	GATE			
25	20	TAR (PAINT (PIRPLE)			(-) CAN(-)
2 5	23	DOON MURTHIR	>		D/1.9(+) (+) 6.2/C
	24		Ű.		
TRANSMITTAL C []STANDARD []TELEPHONE	RANSMITTAL OF RESULTS: STANDARD TELEPHONE RESULTS TO	rs: s to	TELEPHONE #:		
I IFAX RE	SULTS TO		FAX#:	BAT	ВАТСН#: 15 - 12-032
RELING	RELINGUISHED BY	JURAJ BARDIOVSKY	CHAIN OF CUSTODY RECORD	TIME	
RECEIVED BY:	BY:	4 Agrino	12/2/	2015 TIME: (
LABORATORY A NVLAP# 101958	ပ္ခ	SREDITATION : / ELAP# 10955			



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. Ph.: (718) 389 3470, Fax: (718) 389 3471 LIC, NY 11104

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

ental / 45-09 Greenpoint Avenue, LIC, NY 11104 PROJECT: 15-14 Cooper Ave., Queens	LABORATORY ID #: 15-12-125	DATE OF REPORT: 12/10/15
CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY 11104	ANALY I. METHODOLOGIES: ELAP 198.6, ELAP 198.4	DATES OF ANALYSIS: 12/09/15

I ARADATADV PECITITE

POSIT. /	Posit.		Negat.	Negat.	Posit.	
TYPEOF	NA NA	YZED	Chrys.	Chrys.	NA	YZED
TEM	NA	SAMPLE NOT ANALYZED	Trace	0.43	NA	SAMPLE NOT ANALYZED
TYPE OF	Chrys.	SAMPLE	NA	NA	Chrys.	SAMPLE
PLM PESTIT TO	7.66		NAD	NAD	6.48	
%AJI	34.42	13.24	2.73	3.89	19.42	17.00
%ASI	5.79	1.47	17.49	16.67	2.31	2.50
%ORG	52.13	85.29	79.78	79.02	71.79	80.50
LOCATION	Roof Membrane (Bottom Layer), Roof	Roof Membrane (Bottom Layer), Roof	Roof Membrane (Top Layer), Roof	Roof Membrane (Top Layer), Roof	Parapet Wall Tar/Flashing, Roof	Parapet Wall Tar/Flashing, Roof
LAB. ID #	15-12- 125-01	15-12- 125-02	15-12- 125-03	15-12- 125-04	15-12- 125-05	15-12- 125-06
CLIENI #	25	26	27	28	29	30

by Biritmhas

LABORATORY DIRECTOR

E. Dimitrakas

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

A. Korionova ANALYST

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.

 Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. Ph.: (718) 389 3470, Fax: (718) 389 3471 LIC, NY 11104

BULK (NOB) ASBESTOS ANALYSIS BY POLARIZED LIGHT MICROSCOPY AND TRANSMISSION ELECTRON MICROSCOPY

CLIENT / ADDRESS: Athenica Environmental / 45-09 Greenpoint Avenue, LIC, NY 11104 PROJECT: 15-14 Cooper Ave., Que	PROJECT: 15-14 Cooper Ave., Queens
LAP 198.6, ELAP 198.4	LABORATORY ID #: 15-12-125
DATES OF ANALYSIS: 12/09/15	DATE OF REPORT: 12/10/15

I ARORATORV DECIN TO

1	Posit.		Posit.		Negat.	Negat.
TEM TYPE OF RESULTS ASBEST. NA NA		YZED	NA	YZED	NA	NA
		SAMPLE NOT ANALYZED	NA	SAMPLE NOT ANALYZED	NAD	NAD
TYPE OF	Chrys.	SAMPLE	Chrys.	SAMPLE	NA	NA
PLM RESULTS	5.78		85.9		NAD	NAD
%AII	24.66	69.42	24.60	1.00	21.40	16.01
%ASI	1.90 24.66	8.26	4.08	17.25	6.53	4.48
%ORG	%ORG 67.65		64.74	81.75	72.07	79.52
LOCATION	Coping Stone Tar, Roof	Coping Stone Tar, Roof	Vent Stack Tar/Flashing, Roof	Vent Stack Tar/Flashing, Roof	Gooseneck Flashing, Roof	Gooseneck Flashing, Roof
LAB. ID #	15-12- 125-07	15-12- 125-08	15-12- 125-09	15-12- 125-10	15-12- 125-11	15-12- 125-12
CLIENI #	31	32	33	34	35	36

LABORATORY DIRECTOR E. Dimitrakas

LABORATORY ACCREDITATION NUMBERS: NVLAP Lab Code 101958-0, ELAP 10955

A. Korionova ANALYST

- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.
- Above results relate only to samples submitted and analyzed. This report must not be used to claim product endorsement by NVLAP or any other agency of the U.S. Government. Test reports may not be reproduced except in full and with prior approval of LTS Inc.
 - NAD: No Asbestos Detected
- The liability of LTS Inc., with respect to the services charged, shall in no event exceed the amount of the invoice,

	# OF SAMPLES	TEM MALZZE BY	Y RESULTS	A) 7 CA YOA	/	G> 72 CA	(E) 0.45/1CH	(4) 6.48 JCH	14	12/24/CH	12	(T) 6:30 (. 7+	1000	(1) NAS							
<u>DATE</u> 12/4/2015	PROJECT # IFB-3323-054-004-CS	PLM NOB-PLM NOB-TEM	FIELD LABORATORY RESULTS												BATCH#: 15 -/ 8		2015 TIME: \\\ \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	1 2015 TIME: (3 3 5 S	Way 12-915	P	
ADDRESS WOLFF-ALPORT CHEMICAL COSITE, 15-14 COOPER AVE., QUEENS NY - 10148	CLIENT CDM SMITH		SAMPLE LOCATION	Roof							1			Ó	TELEPHONE #:	CHAIN OF CUSTODY RECORD	5	8121	red by A. Honiowova	,	
ATHENICA ENVIRONMENTAL TAL SERVICES INC.	SIKORSKI	STOP AT FIRST POSITIVE	SAMPLE DESCRIPTION	ROOF MEMBIZANE	(BOTTOM LAYER)	KLOUF MEMBAGAINE	のでである。	CIAN WALL TAIN	Cap No Shart	14P	VENT STACK THEY	によること	GOOSEMEN RASHING		JLTS: LTS TO			EDITATION:	analy		
	<u>INSPECTOR</u> J. BARDIOVSKY/ W. SIKORSKI	COMMENTS STO	HOM. SAMLPLE AREA #	12: 25	2000	12 5 Ct	16 5 30	14 6 30		15 8 32	16 9 33	75 01 9)	SC = [(7 12 36	TRANSMITTAL OF RESULTS: []STANDARD []TELEPHONE RESULTS TO []FAX RESULTS TO		RELINQUISHED BY:	LABORATORY ACCREDITATION:	NVLAP# 101958 EL		



LABORATORY TESTING SERVICES INC. 45-09 GREENPOINT AVE. LIC, NY 11104 Ph.: (718) 389 3470, Fax: (718) 389 3471

PAINT CHIP ANALYSIS FOR LEAD CONTENT BY ATOMIC ABSORPTION SPECTROPHOTOMETRY

CLIENT: Athenica Environmental Services

LABORATORY ID #: 15-11-046 DATE OF ANALYSIS: 12/05/15 DATE RECEIVED: 11/24/15 CLIENT ADDRESS: 45-09 Greenpoint Ave. L.I.C., NY 11104

PROJECT: 12-25 Irving Avenue

ANALYT. METHODOLOGY: ASTM D3335-85a

DATE OF REVISED REPORT: 12/17/15

LABORATORY RESULTS

CLIENT #	LAB. ID #	LOCATION	% Pb/weight
151110420-01	15-11-046-01	Terra Nova, Bay, Wall #2, Shelf #5, Purple	0.992
151110420-02	15-11-046-02	Terra Nova, Closet #3, Wall #3, Column #2, White	1.918

ANALYST

T. Balema

LABORATORY DIRECTOR

E. Dimitrakas

LABORATORY CERTIFICATION NUMBER: ELAP 10955

FOR TB

MDL= 5.7 µg Pb/sample

Reporting Limit = 20.0 µg Pb/sample

- Above results relate only to samples submitted and analyzed.
- Samples will be stored for sixty (60) days. LTS Inc. should be notified within this time frame for a true duplicate analysis.
- Laboratory Testing Services Inc. (LTS) cannot verify for results based on client information, but only for results as μgPb/samples.
- The liability of Laboratory Testing Services Inc., with respect to the services charged, shall in no event exceed the amount of the invoice.
- All QC requirements were met unless stated otherwise.
- Above results are corrected for contamination.

O	4	+
ATHENICA ENVIRONMENTAL	taylronmy its conscituints	

151110420-01 151110420-02

SAMLPLE #

COM SMRTH

15-111-0420 TYPE OF SAMPLE: PROJECT NO.:

PAINT CHIPS

SITE:

12-25 Irving Avenue, Queens, NY 11385

Jeffrey Strykowski 11/19/2015

DATE:

INSPECTOR:

			٠ آ.	*	2					
LAB RESULTS	% Pb (w)	10,99701	AND I OF	116 1. 15. 180%						
LABR	mdd		1.910.1	/ 1/18 /:						
COLOR		Purple	White			To the second se				
SAMPLE	Shelf #E	24 11015	Column #2							
SAMPLE	Terra Nova, Bay, Wall #2	Terra Nova. Closet #3 Wall #3	CHI III AND	The state of the s			2		r.	The state of the s

Q
E
*
2
**±

	TIME: [CONTINE	TIME: 14.6	
CHAIN OF GUSTODY RECORD	1241 2015	24/ 2015	NVLAP# 101958 FI AD# 1006E
RELINQUISHED BY:	RECEIVED BY:		The second secon

45-89 Greenpoint Avenue • LIC, NY 11104 • Tef. (718) 784,7490 • Fax: (718) 784-4085 • infoBathenica.com

APPENDIX B:

9.0 Personnel Certificates

NYC DEP ASBESTOS CONTROL PROGRAM ASBESTOS CERTIFICATE



SIKORSKI, WOJCIECH M INVESTIGATOR 128636

EXPIRES: 2/24/2017 DOB:2/24/1970 M.6' 00"

MUST BE CARRIED ON ALL ASBESTOS PROJECTS



DMV ID: 212715648

This certificate must be shown to a NYCDEP representative upon request. Report loss immediately to NYCDEP Asbestos Control Program, 8th floor 59-17 Junction Blvd., Flushing, NY 11373

01213 000469797 51

STATE OF NEW YORK - DEPARTMENT OF LABOR ASBESTOS CERTIFICATE





WOJCIECH SIKORSKI CLASS(EXPIRES) D INSP(02/16) I PD (02/15)


CERT# 09-08985

MUST BE CARRIED ON ASBESTOS PROJECTS

01213 090416576 75

EYES BRO HAIR GRY IF FOUND RETURN TO: MYSDOL - L&C UNIT ROOM 161A BUILDING 12 STATE OFFICE CAMPUS ALBANY NY 12240

e,e;








NICHOLAS DELGROSSO CLASS(EXPIRES) C ATEC(07/16) D INSP(07/16) H PM (07/16)

MUST BE CARRIED ON ASBESTOS PROJECTS

EYES BRO HAIR BRO HGT 5' 11" IF FOUND RETURN TO: NYSDOL - LEC UNIT ROOM 161A BUILDING 12 STATE OFFICE CAMPUS ALBANY NY 12240







JURAJ BARDIOVSKY CLASS(EXPIRES) D INSP(10/16)

> CERT# 08:04420 DMV# 874167328

MUST BE CARRIED ON ASBESTOS PROJECTS





IF FOUND RETURN TO:
MYSDOL - LEC UNIT
ROOM 161A BUILDING 12
STATE OFFICE CAMPUS
ALBANY NY 12240

United States Environmental Protection Agency

This is to certify that



Juraj Bardiovsky

UNITED STATE

has fulfilled the requirements of the Toxic Substances Control Act (TSCA) Section 402, and has received certification to conduct lead-based paint activities pursuant to 40 CFR Part 745.226 as:

Risk Assessor

In the Jurisdiction of:

New York

This certification is valid from the date of issuance and expires September 05, 2018

John Ham

John Gorman, Chief

Pesticides & Toxic Substances Branch

NY-R-18077-2

Certification #

September 02, 2015

Issued On



4anevement

This is to certify that

Athenica Environmental Services Juraj Bardiovsky


on the 21st day of July, 2011 successfully completed the factory training for

RMD's LPA-1 Lead Paint Inspection System

including, but not limited to the topics of Radiation Safety, DOT Regulations, and the Proper Use of the Instrument.

Sia Afshari Product Manager RMD

44 Hunt St, Watertown, Massachusetts



Certified Lead-Based Paint Professional

Certification No NY-R-113399-1

Date of Birth 08/24/1978 Expiration Date 10/18/2014

Address

69-08 38th Ave. Woodside, NY 11377

Badge Holder's Name
Jeffrey Paul Strykowski

Badge Holder's Signature

dedicate

If found, drop in any mailbox Postmaster: Please return to: US EPA 1200 Pennsylvania Ave, NW (MC-74040T) Washington, DC 20480 or call 1-800-424-LEAD

United States Environmental Protection Agency

This is to certify that

MAKED STATE

Jeffrey Strykowski



has fulfilled the requirements of the Toxic Substances Control Act (TSCA) Section 402, and has received certification to conduct lead-based paint activities pursuant to 40 CFR Part 745.226 as:

Risk Assessor

In the Jurisdiction of:

New York

This certification is valid from the date of issuance and expires November 01, 2017

Jan Land

John Gorman, Chief

Pesticides & Toxic Substances Branch

NY-R-113399-2

Certification #

September 10, 2014

Issued On

. Adrievement

This is to certify that

Jeff Strykowski

Athenica Environmental Services

on the 21st day of July, 2011 successfully completed the factory training for

RMD's LPA-1 Lead Paint Inspection System

including, but not limited to the topics of Radiation Safety, DOT Regulations, and the Proper Use of the Instrument.

44 Hunt St, Watertown, Massachusetts

APPENDIX C:

10.0 Consulting Company License

New York State - Department of Labor Division of Safety and Health,

Division of Safety and Health License and Certificate Unit State Campus, Building 12 Albany, NY 12240

ASBESTOS HANDLING LICENSE

Athenica Environmental Services Inc.

45-09 Greenpoint Avenue

Long Island Cty, NY 11104

FILE NUMBER: 99-0763

LICENSE NUMBER: 29663

LICENSE CLASS: RESTRICTED DATE OF ISSUE: 06/11/2015

EXPIRATION DATE: 07/31/2016

Duly Authorized Representative - Spiro Dongaris:

This license has been issued in accordance with applicable provisions of Article 30 of the Labor Law of New York State and of the New York State Codes, Rules and Regulations (12 NYCRR Part 56). It is subject to suspension or revocation for a (1) serious violation of state, federal or local laws with regard to the conduct of an asbestos project, or (2) demonstrated lack of responsibility in the conduct of any job involving asbestos or asbestos material.

This license is valid only for the contractor named above and this license of a photocopy must be prominently displayed at the asbestos project worksite. This license verifies that all persons employed by the licensee on an asbestos project in New York State have been issued an Asbestos Certificate, appropriate for the type of work they perform, by the New York State Department of Labor.

Eileen M. Franko, Director For the Commissioner of Labor

SH 432 (8/12)

United States Environmental Protection Agency

This is to certify that

WITED STATES

Athenica Environmental Services, Inc.

has fulfilled the requirements of the Toxic Substances Control Act (TSCA) Section 402, and has received certification to conduct lead-based paint activities pursuant to 40 CFR Part 745.226

In the Jurisdiction of:

New York

This certification is valid from the date of issuance and expires May 10, 2018

mile for

Michelle Price, Chief

Lead, Heavy Metals, and Inorganics Branch

NY-1731-5

Certification #

January 13, 2015

Issued On



APPENDIX D

11.0 Laboratory Accreditation

NEW YORK STATE DEPARTMENT OF HEALTH WADSWORTH CENTER



Expires 12:01 AM April 01, 2016 Issued April 01, 2015 Revised April 03, 2015

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York-State

MR. EMANUEL DIMITRAKAS LABORATORY TESTING SERVICES INC 45-09 GREENPOINT AVENUE LONG ISLAND CITY, NY 11104

NY Lab Id No. 10955

is hereby APPROVED as an Environmental Laboratory for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE All approved subcategories and/or analytes are listed below:

Miscellaneous_

Asbestos In Filable Material

Item 198.1 of Manual

EPA 600/M4/82/020

Asbestos In Non-Friable Material-PLM

Item 198.6 of Manual (NOB by PLM)

Asbestos in Non-Friable Material-TEM - Item 198.4 of Manual

Asbestos-Vermiculite-Containing Material Item 198.8 of Manual

Lead in Dust Wipes

EPA 7000B

Lead in Paint

ASTM D3335-85A

Sample Preparation Methods

ASTM E-1644-04

Serial No.: 52783

Property of the New York State Department of Health. Certificates are valid only at the address shown, must be conspicuously posted, and are printed on secure paper. Continued accreditation depends on successful orgoing participation in the Programs. Consumers are urged to call (518) 485-5570 to





SCOPE OF ACCREDITATION TO ISO/IEC 17025:2005

Laboratory Testing Services Inc.

45-09 Greenpoint Avenue Long Island City, NY 11104 Mr. Emanuel Dimitrakos

Phone: 718-389-3470 Fax: 718-389-3471 Email: edimitrakas@labtestingservices.com

ASBESTOS FIBER ANALYSIS

NVLAP LAB CODE 101958-0

Bulk Asbestos Analysis

Code

Description

18/A01

EPA 600/M4-82-020: Interim Method for the Determination of Asbestos in Bulk Insulation Samples

Airborne Asbestos Analysis

Code

Description

18/A02

U.S. EPA's "Interim Transmission Electron Microscopy Analytical Methods-Mandatory and Nonmandatory-and Mandatory Section to Determine Completion of Response Actions" as found in

40 CFR, Part 763, Subpart E, Appendix A.

For the National Voluntary Laboratory Accreditation Program

United States Department of Commerce National Institute of Standards and Technology



Certificate of Accreditation to ISO/IEC 17025:2005

NVLAP LAB CODE: 101958-0

Laboratory Testing Services Inc. Long Island City, NY is accredited by the National Voluntary Laboratory Accreditation Program for specific services, listed on the Scope of Accreditation, for:

Asbestos Fiber Analysis

This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2005. management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).

2015-06-29 through 2016-06-30

Effective Dates



How Program For the National Voluntary Laboratory Accreditation Program



July 31, 2015

Laboratory ID: 100287

Emanuel Dimitrakas Laboratory Testing Services, Inc. 45-09 Greenpoint Ave. Suite 204 Long Island City, NY 11104

Dear Mr. Dimitrakas:

Congratulations! The AIHA Laboratory Accreditation Programs (AIHA-LAP), LLC's Analytical Accreditation Board (AAB) has approved Laboratory Testing Services, Inc. as an accredited Industrial Hygiene and Environmental Lead laboratory.

Accreditation documentation includes the IHLAP and ELLAP accreditation certificate, scope of accreditation document and a copy of the current AIHA-LAP, LLC license agreement (if your completed agreement is not on file at AIHA-LAP, LLC). The accreditation symbol has been designed for use by all AIHA-LAP, LLC accredited laboratories. If your laboratory chooses to use the symbol in its advertising the laboratory's accreditation, you must complete and return the AIHA-LAP, LLC license agreement to a Laboratory Accreditation Specialist. Once submitted, an electronic copy of the accreditation symbol will be sent to you. Please inform us if your laboratory does not wish to use the symbol in advertising.

Laboratory accreditation shall be maintained by continued compliance with IHLAP and ELLAP requirements (see Policy Modules 2B, 2C, and 6), which includes proficient participation in AIHA-LAP, LLC approved proficiency testing, demonstration of competency, or round robin program as indicated on the AIHA-LAP "Approved PT and Round Robin" webpage, its associated Scope/PT table, and as required in Policy Module 6, for all Fields of Testing (FoTs) for which the laboratory is accredited. An accredited laboratory that wishes to expand into a new FoT must submit an updated accreditation application to AIHA-LAP, LLC for review by the AAB.

Any changes in ownership, laboratory location, personnel, FoTs/Methods, or significant procedural changes shall be reported to AIHA-LAP, LLC in writing within twenty (20) business days of the change.

The accreditation certificate is the property of AIHA-LAP, LLC and must be returned to us should your laboratory withdraw or be removed from the IHLAP and ELLAP.

Again, congratulations. If you have any questions, please contact Lauren Schnack, Laboratory Accreditation Specialist, at (703) 846-0716.

Sincerely,

Cheryl O. Morton Managing Director

AIHA Laboratory Accreditation Programs, LLC

Cheryl of martin

AlHA Laboratory Accreditation Programs, LLC
3141 Fairview Park Drive, Suite 777, Falls Church, VA 22042 USA
main +1 703-846-0736 fax +1 703-207-8558
Twitter: @AIHA_LAP_LLC
R3 05/05/2015
Page 1 of 1



AIHA Laboratory Accreditation Programs, LLC

acknowledges that

Laboratory Testing Services, Inc.

45-09 Greenpoint Ave., Suite 204, Long Island City, NY 11104

Laboratory ID: 100287

along with all premises from which key activities are performed, as listed above, has fulfilled the requirements of the AIHA Laboratory Accreditation Programs (AIHA-LAP), LLC accreditation to the ISO/IEC 17025:2005 international standard, General Requirements for the Competence of Testing and Calibration Laboratories in the following:

LABORATORY ACCREDITATION PROGRAMS

- INDUSTRIAL HYGIENE
 - ENVIRONMENTAL LEAD
- ENVIRONMENTAL MICROBIOLOGY
 - UNIQUE SCOPES

- Accreditation Expires: 08/01/2017 Accreditation Expires: 08/01/2017
 - Accreditation Expires: Accreditation Expires:
 - Accreditation Expires:

Specific Field(s) of Testing (FoT)/Method(s) within each Accreditation Program for which the above named laboratory maintains accreditation is

17025:2005 and AIHA-LAP, LLC requirements. This certificate is not valid without the attached Scope of Accreditation. Please review the AIHAoutlined on the attached Scope of Accreditation. Continued accreditation is contingent upon successful on-going compliance with ISO/IEC

Cheng G. Charten LAP, LLC website (www.aihaaccreditedlabs.org) for the most current Scope.

Gerald Schultz, CIH

Chairperson, Analytical Accreditation Board

Revision 14: 03/26/2014

Managing Director, AIHA Laboratory Accreditation Programs, LLC

Date Issued: 07/31/2015

APPENDIX E

12.0 Project Documents

CDM Federal Programs Corporation

555 17th Street Suite 1100 Denver, Colorado 80202 (303) 383-2300 / Fax (303) 308-3003

Rev. 1-8/07

SERVICE ORDER NO.: 3323-054-004-CS

Document Control No.: N/A **TRACKING NO.: 16910**

Page 1 of 1


Government Client:		U.S. Environmental I	e: All contact with client MUST									
Prime Contr	act No./WA/DO/TO No.:	EP-W-09	EP-W-09-002 be					through CDM Federal Programs				
Prime Contr	actor:	CDM Federal Progr	ams Corporation	on	unless	unless initiated by client.						
Service Prov	vider's Name & Address:											
45-09 Gree Long Islam Spiro Don Tele: (718)	Environmental Services, In enpoint Avenue dd City, NY 11104 garis (<u>sdongaris@athenica</u> 784-7490 ct-Engineer Contract Contract Act is applicable etermination is applicable of Professional E&O insurance	.com)		[X Fi	xed Unit I bor Hour (Price (lum Price (ID/ Not to Ex	IQ)					
*S.O. DATE	SUBCONTRACT AI	PEDIOD	OF PERF	Size: SB	CE	DAVA	MENT TERMS					
04/20/15	Raquel Ci			tion throug	O CA COLO		1811	NET 42				
ITEM NO.	DESCRI	PTION OF SERVICES		QTY.	UNIT	UNIT PRIC		EXT. PRICE				
	Provide Hazardous M support of the Wolff-A (WACC) Site located New York in accordar of Work and Price Shows an	Alport Chemical Comin Ridgewood, Queen ce with the attached eet. The Corporation Terms of the Conditions, Heal Specific Health and Wage Rates are hereby	npany ns County, Statement s and lth and Safety and									
NOTES: *Ord	er must be signed and returned	within 10 days of Service O	rder date.			TOT	AL:	\$8,745.00				
	ervice Provider Signature	2 4/23/ Date Date August	CDM Federal	Programs	Corporati	on Signati	- ire	Date				


ORIGINAL

APPENDIX F

13.0 Sample Location Drawings


INV. (INSP.: W. SIKERSKI, J. CAROIUVSKY, N. DELGRUSSU 11-33 IRVING AVE, QUEENS, NY 11385 ALM SAMPLE LOCATION OFA WINES pate: 11/20/15






11-33 IRVING AVE, CLEENS, NY 11585 ING. / INV.: W. SIKURSKI, J. BARDUOVSKY, N. OELGRASSO DATE: 11/20/15


INV. / INSP. : W. SIKORSKI, J. BARDIOVSKY, N. DELGROSSO ORTE: 12/4/15




INSP. /INV.: W. SIKURSKI, J.BARDIOVSKY, N. DELGROSSU DATE: NIZYLIS 11-29 IRVING AVE, QUEENE, MY 11385 Arm SAMALE LOCATIONS




ACM SAMPLE LOCATION DRAWINGS - 11-27 IRVING AVE, QUEENS, NY INSP. LINV. : W. SIKURSKI/J. BARDIOUSKY N. DELGROSSE DATE: 1244(L





INV. (INSP.: W. SIKORDKI (TIBARDIONSCH (N. OELGROSSO 11-25 IRVING AVE, QUEDUS, NY 11585 DATE: (2/4/1)




ALM SAMPLE LOCATAND

11-25 IRVING AVE, QUEFAS, NY 11885

INSP. / INV.: W. SIEURSKI, J. BARDOVSKY,


N. DELGRUSSU

OATE: # 11(24/15



INRP. /INV.: W. SKORSKI (J. BARDIOVSICY/ N. DELEROSSO DATE: 15-14 LOSPER AVENUE, QUECUS, NY (1385)

13-18



IN SP. (INV.: W.SIRURSKI, W.SIRURSKI, N. DEL GROSSS 15-14 COOPER AVE, QUEENS, NY (1325 ACM SAMPLE LUCATION

DATE: 11(24/15

Appendix C

Appendix C

March 2017 Structural Inspection Report





Memorandum

To: Mr. Thomas Mongelli, EPA Region 2

From: Ali Rahmani, CDM Smith

Project: EPA Region 2 RAC2 Contract No.: EP-W-009-02

Work Assignment No.: 054-RICO-A282

Document Control No.: 3323-054-03141

Date: March 8, 2017

Subject: Structural Foundation Inspection of Buildings at Wolf-Alport Chemical Company

Site

1.0 Introduction

CDM Federal Programs Corporation (CDM Smith) received Work Assignment (WA) 054-RICO-A282 from the United States Environmental Protection Agency (EPA), Region 2 under Remedial Action Contract (RAC) 2 to complete a remedial investigation (RI) and feasibility study (FS) for the Wolff-Alport Chemical Company (WACC) site (Site) located in Ridgewood, Queens County, New York. As part of that effort, EPA Region 2 asked CDM Smith to conduct a structural foundation inspection of the buildings located at the Site (**Figure 1**).

2.0 Background

The United States Environmental Protection Agency (EPA), New York State (NYS), and the City of New York (NYC) are working together to reduce potential exposure to radiation caused by contamination as a result of historical operations at the Site. A combination of concrete and lead floor shielding was installed in 2013 to reduce radiation exposures to the occupants of the buildings from the contaminated soils.

The purpose of the WA FS is to identify, develop, screen, and evaluate a range of remedial alternatives for the contaminated media and provide the regulatory agencies with sufficient information to select a feasible and cost-effective remedial alternative that protects public health and the environment from potential risks at the Site.

3.0 Inspection Objective

To help develop and evaluate remedial alternatives for the Site, an inspection of the existing structures at the Site was performed to determine the feasibility of over excavating additional contaminated soil within the buildings to provide additional shielding to reduce the radiation

exposure to building occupants. CDM Smith Structures Specialist Paul Blomberg reviewed the site structures on Lots 46, 44, 42, and 33 (**Figure 1**) on February 17, 2017.

The ability to over-excavate additional soils within the structures depends on the size, location and depth of the structural foundations that support the building superstructure. If the structures are supported on shallow foundations, then over-excavation to the base of those shallow foundations is feasible and economical. However, further excavation below the base of shallow foundations would require underpinning of the foundations and the added cost of that work. Should the building be founded on a deep foundation system such as piles or drilled shafts, then available excavation depths would be much deeper without the need for underpinning.

4.0 Structural Discussion, Inspection and Observations

The NYC provided available drawings of the subject buildings, however those drawings are tenant improvement drawings; no structural drawings or original construction drawings are available. To visually identify the foundation systems used for the buildings, a field inspection was performed. As the foundations are buried below grade, the inspection focused on finding areas around or within the building where the foundations were exposed to view. Additionally, a soil sampling auger was used to determine the concrete footing elevation below the surface where accessible.

Each building along Irvine Ave. was visited to determine foundation type, location and depth. Weather during the inspection was sunny, with temperatures in the 30's °F and 6 inches of snow on the ground. Based on inspection observations, building construction was estimated to have occurred before 1940 with some buildings dating back to the 1920s. Below is a description of the pertinent structural observations of each building.

Jarabacoa Deli Basement, 11-25 Irving Ave (Block 3725 Lot 46)

The structure at 11-25 Irving Avenue is a 2-story wood framed building approximately 25 feet (ft) x 100 ft with a full basement, a deli on the first floor and apartments on the second floor. The

basement consists of a brick foundation wall and concrete floor. The foundation for the brick foundation wall is unreinforced concrete and is partially exposed. After the building was constructed, it appears that the basement floor was dug out below the top of footing and a concrete slab on grade was cast approximately 8 inches below the adjacent top of footing. The foundation system for this building appears to be a shallow foundation with a continuous concrete strip footing below the unreinforced brick bearing walls. The height of the brick wall is 7 ft-2 inches with 2 inches x10 inches



wood floor framing bearing on top of the brick. The floor joists bear directly on the top of the brick wall without a sole plate. Thickness of the basement wall concrete footing could not be determined.

No wall or floor openings were observed that would allow observation of the foundation of the Celtic Custom Bike Shop, 11-27 Irving Ave (Block 3725 Lot 44).

Celtic Custom Bike Shop, 11-27 Irving Ave (Block 3725 Lot 44)

The structure at 11-27 Irving Avenue is a one-story building approximately 25 ft x 100 ft. The roof system is wood framed with brick walls on three sides, concrete masonry unit (CMU) walls to the rear and a concrete slab on grade floor. The floor is raised above the sidewalk level by 6 inches and provides shielding from the soil below. The building is surrounded on three sides by other buildings and open to the street at Irving Ave. The wall to the adjacent Deli (Lot 46) is built with only a several inch gap between the walls and shares a common wall to the southeast with Primo Auto Repair (Lot 42). The end of the building (northeast wall) abuts a one-story commercial building.

Ceilings and wall coverings covered the structural system so no additional observations of the structural system could be made. The foundation system is covered by the new floor slab installed in 2013. No footing information could be observed from the inside of the building. Adjacent buildings obscured any observations of the existing footings from the outside and the concrete sidewalk covered the grade in front of the building. In addition, no access to auger for foundation depth is possible for this building without concrete removal.

Primo Auto Repair, 11-29 Irving Ave (Block 3725 Lot 42)

The structure at 11-29 Irving Avenue is a 1-story building approximately 25 ft x 175 ft. The roof system is wood framed with brick walls and a concrete slab on grade floor. The floor is raised above the sidewalk level by 6 inches and provides shielding from the soil below. The building is surrounded on the two long sides by other buildings and open to the street at Irving Ave and open to the back at the former rail spur (Lot 31). The wall to the adjacent Bike Shop (Lot 44) and Terra Nova (Lot 42) share a common wall with this building. This building has pipe columns within the space along the long walls and steel wide flange beams supporting the roof joists. This indicates that individual footings may be cast below the columns and that the brick walls may not be load bearing. The brick walls likely provide lateral support for the structure. The end of the building (northeast wall) appears to be brick and is stucco covered.

Ceilings and wall coverings covered the structural system and additional observations were not possible. The foundation system is covered by the new floor slab installed in 2013. No footing information could be observed from the inside of the building. Adjacent buildings obscured any observations of the existing footings from the outside and the concrete sidewalk covered the grade in the front and rear of the building. No access to auger for foundation depth is possible for this building without concrete removal.

Terra Nova Restoration Corp., 11-33 Irving Ave (Block 3725 Lot 42)

The structure at 11-33 Irving Avenue is a 1-story building approximately 25 ft x 152ft. The roof system is wood framed with brick walls and a concrete slab on grade floor. The floor is raised above the sidewalk level by 6 inches and provides shielding from the soil below. The building shares a common wall to the northwest with Primo Auto Repair (Lot 42). There is a 5 ft long

walkway along the front half of the southeast wall that separates this building from the adjacent Warehouse (Lot 33).

The wall to the adjacent Primo Auto Repair (Lot 42) shares a common wall with this building. This building has pipe columns within the space along the long walls and steel wide flange beams supporting the roof joists. This indicates that individual footings may be cast below the columns and that the brick walls may not be load bearing. The brick walls likely provide lateral support for the structure. The end of the building (northeast wall) appears to be brick and is stucco covered.

Ceilings and wall coverings covered the structural system so no additional observations of the structural system could be made. Exterior access along the 5' walkway adjacent to the Warehouse (Lot 33) was inaccessible due to the area being barricaded, overgrown with vegetation and covered with snow. The foundation system is covered by the new floor slab installed in 2013. No footing information could be observed from inside the building. Adjacent buildings obscured any observations of the existing footings from the outside and the concrete sidewalk covered the grade in the front and rear of the building. No access to auger for foundation depth is possible for this building without concrete removal.

Warehouse, 11-33 to 11-99 Irving Ave (Block 3725 Lot 33)

The warehouse structure is a 1-story steel framed building with a triangular footprint. Frontage (Irving Ave.) dimension is approximately 150 ft by 150 ft deep to the north corner with the backwall curving along former rail spur (Lot 31) approximately 225 ft. The superstructure is steel wide

flange columns and masonry pilasters with steel wide flange roof framing and an unknown roof system. Exterior walls are CMU with some exterior brick façade. The floor is cast in place concrete and appeared to be original to the structure. The foundation system for this building was not visible from the interior. The rear of the building along the former rail spur (Lot 31) was accessed and a hand-held auger was used to core the soil along the exterior wall. Auger refusal occurred at 24 inches below grade and this appears to be the top of the concrete foundation for this building. The spoils from the core were placed back in the hole and the grade was re-covered with snow.



5.0 Conclusion

The ability to over-excavate additional soils within the structures depends on the size, location and depth of the structural foundations that support the building superstructure. Available building drawings were reviewed but none indicated original construction information nor any information on the existing foundations. Visual inspection of the subject buildings and the adjacent buildings were not able to identify the foundation systems, their size or elevations as all were buried beneath grade and inaccessible.

Foundation depth is currently required by the Building Code to be 48" below grade but this requirement may or may not have been in force when these buildings were constructed. Over-excavation of the existing soils below the building concrete slabs on grade is feasible as long as the excavation does not undermine the existing footings. Excavation to the bottom of the footing elevation is an available option but further testing would be needed to determine this elevation.

It appears that a reasonable assumption for FS alternative development is that depth of footing is 24 to 30 inches below grade as the adjacent Warehouse building occurs at that elevation. Any remedy that includes soil excavation to provide additional shielding to reduce the radiation exposure to building occupants will need footing size and elevations verified. This can be accomplished during pre-remedial design activities by coring/selective excavation or ground penetrating radar.

cc: Joel Singerman, EPA
Tony Isolda, CDM Smith
Paul Blomberg, CDM Smith
Jeanne Litwin, CDM Smith
Kavitha Subramaniam, CDM Smith
Document Control



Appendix D

Appendix D

Building Demolition Material Calculations





ROJECT:	Wolff-Alport CC Superfund Site	
IOB NO.:	226078-6460.F3001.002.DES95	
CLIENT:	USACE - KC	

COMPUTED BY: KK

DATE: 4/27/2018

CHECKED BY: MS

DATE CHECKED: 7/12/2018

Description

The measurements which were input into the dimensional / volumetric calculations below are based on the site survey. The determination of radiological waste was based on chip samples and gamma readings collected during the 2015 Remedial Investigation completed by CDM Smith. Walls are categorized based on the highest possible contaminated point on a wall except for walls on Lot 33.

Contamination Assumptions:

Walls are assumed to be radioactive if high gamma readings were detected during the remedial investigation and the gamma readings. Gamma readings within the range of background or twice background were not assumed to be contaminated.

Despite elevated gamma counts in a small area of the ceiling on Lot 44, ceilings and the roof were not assumed to be contaminated as the majority of gamma readings were within the range of background. Additionally, the ceiling and roof is not in contact with radioactive materials.

Areas of contamination with concentrations above 50 pCi/g were delineated based on the gamma scan results from the remedial investigation. For constructability, the assumption is made that the entire vertical portion of the wall in the area of an elevated gamma reading will be disposed of at a landfill accepting waste with concentrations greater than 50 pCi/g.

Building information from 2017 Structural Inspection:

Lot 33 is a one-story building with steel wide flange structural system, masonry pilaster walls, and some brick exterior façade.

Lot 42 is a one-story building split in two by a center wall to house two occupants. It's structural support system is pipe columns within the walls and steel wide flange beams supporting roof joists. All walls are constructed of bricks with the rear-wall covered in stucco. The roof is wood-framed.

Lot 44 is a one-story building with an unknown structural system. Three walls are constructed of brick and the rear wall is constructed of CMU. It has a shared wall with Lot 42.

Lot 46 is a two-story building with a full basement. It is wood-framed with a basement constructed of brick foundation walls. The walls are brick and stucco-covered brick.

Lot 48 is a one-story building with an unknown structural system. The walls are constructed of brick.

Building information assumptions:

All building roofing material is assumed to be plywood subroofing with a tar membrane.

Roof system on Lot 33 is assumed to be supported by steel joists. Roof system on Lots 42, 44, 46, and 48 are assumed be supported by wood joists.

All roof tar membrane contains asbestos and will be disposed of as ACM. Assumes plywood and tar membrane would be disposed of together as ACM instead of trying to separate the two materials.

Height of walls includes parapets. Wall thicknesses are based on general construction knowledge. Wall material tonnage is estimated based on approximate volumes of each component shown in table below calculations.

Glass in windows is assumed to be 1/8-inch thick.

Where walls contain doors and windows, the surface area of the doors and windows were subtracted from the surface area of the wall determined by length and height.

Structural steel, scrap metal (roll up doors), and windows on assumed radioactive walls are not assumed to be radioactive.

Building material percentage assumptions are as follows:

	Wall Materials Percentages											
Building Walls	Brick	CMU/Masonry	Steel	Wood								
Lot 42	90%		10%									
Lot 44	90%			10%								
Lot 44 rear wall		90%		10%								
Lot 46	90%			10%								
Lot 48	100%											
Lot 33	20%	70%	10%									

Material densities used for estimate are as follows:

Roof Joist Material	Joist Width (IN)	Joist Depth (IN)	Unit Weight (LBS/LF)
Steel Joist	6	24	20
2x10 Kiln Dried Wood Joist	1.50	9.25	3.4

Assume middle of road parallel cord steel joist
Assumed additional hardware would add 0.1 lbs/lf

Material	Density (lb/ft³)	Density (ton/CY)
CMU	120	1.62
Brick	112	1.51
Concrete	150	2.03
Steel	610	8.24
Wood	60	0.81
Plywood	29	0.39
Asphalt /tar roofing	108.1	1.46
Glass, window	157	2.12

Material	Thickness (IN)	Density (lb/ft ²)	Density (lb/ft3)	Density (ton/SY)	Density (ton/CY)
Sheet steel (22-ga)	0.0299	1.25	502	0.006	18.59
Caulking			59.84		2.22
Thermal insulation board			2.5		0.09
Panel board backing paper			40		1.48
ACM electrical panels			70		2.59
ACM electrical insulation			3		0.11
ACM surfacing materials			40		1.48

References

Cement Block Walls: Beall, Christine; Jaffe, Rochelle (2003). Concrete and Masonry Databook. McGraw-Hill.

Brick: Worell, W.A., Vesilind, P.A., and Ludwing, C. (2017). Solid Waste Engineering: A Global Perspective, 3rd Edition

 $Concrete:\ Avallone, Eugene\ A.\ Mark's\ Standard\ Handbook\ for\ Mechanical\ Engineers,\ 11 th\ Edition$

Steel and timber: Ahmend and Sturges (2015). Materials Science in Construction. Timber density is the median of the density range provided.

Plywood: Worell, W.A., Vesilind, P.A., and Ludwing, C. (2017). Solid Waste Engineering: A Global Perspective, 3rd Edition

Asphalt/tar roofing: Worell, W.A., Vesilind, P.A., and Ludwing, C. (2017). Solid Waste Engineering: A Global Perspective, 3rd Edition

Glass, window: Worell, W.A., Vesilind, P.A., and Ludwing, C. (2017). Solid Waste Engineering: A Global Perspective, 3rd Edition

Sheet steel: Engineering Toolbox Gauge and Weight Chart.

Density for caulking, thermal insulation board, panel backing paper, and ACM electrical panels, electrical insulation, and surfacing materials per engineer.

 CDM
 PROJECT:
 Wolff-Alport CC Superfund Site
 COMPUTED BY:
 KK
 CHECKED BY:
 MS

 JOB NO:
 226078-6460.F3001.002.DES95
 DATE:
 4/27/2018
 DATE CHECKED:
 7/12/2018

 CLIENT:
 USACE - KC
 USACE - KC
 COMPUTED BY:
 KK
 CHECKED BY:
 MS

			Roof Dimensions and Assumptions								
Lot	Roof Area (SF)	Plywood Thick. (IN)	Tar Memb. Thick. (IN)	Plywood Volume (CY)	Tar Memb. Volume (CY)	Plyood (CY)	Plywood (TN)	Tar Memb. (CY)	Tar Memb.** (TN)		
ot 33*	13,400	1	1	41	41	41	16	41	60		
ot 42	7,800	1	1	24	24	24	10	24	36		
ot 44	2,500	1	1	8	8	8	4	8	12		
ot 46	2,500	1	1	8	8	8	4	8	12		
ot 48	1,090	1	1	3	3	3	2	3	5		

**All tar membrane contains asbestos and will be disposed of as ACM. Assumes plywood and tar membrane would be disposed of together as ACM instead of trying to separate the two materials.

Irregularly Shaped Building

	Mat	erial Dimensions	and Assumptio	ns	Volume	e and Mass
Lot	Length (FT)	Width (IN)	Surface Area (SF)	General ACM Thick. (IN)	Volume (CY)	General ACM (TN)
Lot 33 - Tar on cinderblock wall			4,000	1	12	17.60
- Abandoned panel board backing paper			12	0.13	0.01	0.02
- Tar on front edge trim below roof			100	1	0.31	0.46
- Assumed ACM electrical panels			26	2	0.17	0.45
- Assumed ACM electrical wire insulation			1,500	0.13	0.61	0.07
- Flashing on roof fans/gooseneck flashing			40	1	0.13	0.00
Lot 42 - Roof flashing/parapet wall tar/flashing			1,720	1	5.31	0.01
- Coping stone tar			150	1	0.47	0.69
- Vent stack tar/flashing			40	1	0.13	0.00
Lot 44 - Roof flashing/parapet wall tar/flashing			500	1	1.55	2.27
- Vent stack tar/flashing			10	1	0.04	0.06
- Tar on beams			20	1	0.07	0.11
Lot 46 - Tar/Paint on gate			30	1	0.10	0.15
- Roof flashing/parapet wall tar/flashing			520	1	1.61	2.36
- Tar on beams			40	1	0.13	0.19
- Assumed asbestos-containing window caulking materials	12	0.5	0.5	0.5	0.01	0.03
- Assumed asbestos-containing surfacing materials throughout interior			3,000	0.5	4.63	6.86
- Assumed asbestos-containing thermal insulation materials throughout interior	120	0.5	5.0	0.5	0.01	0.01
- Assumed asbestos-containing miscellaneous materials throughout interior			2,000	0.5	3.09	4.58
Lot 48 - Roof flashing			40	1	0.13	0.00
- Tar on walls			10	1	0.04	0.06
- Tar/Purple paint on wall			320	1	0.99	1.45
- Parapet wall tar/roof flashing			520	1	1.61	2.36
- Coping stone tar			10	1	0.04	0.06
- Vent stack tar/flashing			10	1	0.04	0.06

Rounded up to nearest whole number

						Volume and I	Mass of Roofing	g Support Materials		
Lot	Apporx. Length (FT)	Approx. Width (FT)	Assumed Joist Spacing (FT)	No. of Joists (EA)	Steel (SF)	Steel (CY)	Steel (TN)	Wood (CY)	Wood (TN)	
Lot 33*	154	80	2	77	16,427	228	62	0	0	Assumes a 24-inch deep parallel cord steel joist. Surface area is assumed to equal total joist length times 2 t
Lot 42A	100	22	1	100	0	0	0	8	4	Assumes 2x10 wood joist
Lot 42B	55	25	1	55	0	0	0	5	3	Assumes 2x10 wood joist
Lot 44	100	25	1	100	0	0	0	9	5	Assumes 2x10 wood joist
Lot 46	100	25	1	100	0	0	0	9	5	Assumes 2x10 wood joist
Lot 48A	34	30	1	34	0	0	0	4	2	Assumes 2x10 wood joist
Lot 48B	15	15	1	15	0	0	0	1	1	Assumes 2x10 wood joist
		Total	quantity of roof sy	stem materials	16,427	228	62	36	20	

*Irregularly Shaped Building - used length to determine number of joists. Used mean width to approximate total joist length.



CDM	PROJECT:	Wolff-Alport CC Superfund Site	COMPUTED BY :	KK	CHECKED BY:	MS
CONTRACTOR	JOB NO.:	226078-6460.F3001.002.DES95	DATE:	4/27/2018	DATE CHECKED:	7/12/2018
Smith	CLIENT:	USACE - KC	_		_	

			Wall Dimens	ions			Volume and	Mass of Buildi	ng Materials by	Type										
									Concrete Masonry Unit/Masonr	Concrete Masonry Unit/Masonry				Scrap	Scrap	Scrap				
	Length	Height	Surface Area	Thickness	Volume	Volume	Brick	Brick	y Pilaster	Pilaster	Steel	Steel	Steel	Metal	Metal	Metal	Wood	Wood	Glass	Glass
Wall Categories Radioactive Walls	(FT)	(FT)	(SF)	(IN)	(CF)	(CY)	(CY)	(TN)	(CY)	(TN)	(SF)	(CY)	(TN)	(SF)	(CY)	(TN)	(CY)	(TN)	(CY)	(TN)
Areas with concentrations less than 50 pCi/g but greater	ter than backgroun	nd																		
Lot 33-1 (A) - lower potentially contaminated area	89	3	290	8	194	8	8	3	8	10							T -		-	
Lot 33-1 (B) - middle potentially contaminated area	30	3	98	8	66	3	3	1	3	4			1				-		-	
	53	3	173	8		_	5	2	5	6			See below.				-		-	
Lot 33-1 (B) - lower potentially contaminated area Lot 42-1 (A)	1.61	1.4	1.554	8	116 1,036	5 39	39	54					See							
Lot 42-1 (A) Lot 42-1 (B)	161 30	14 14	1,554 420	8	280	11	11	15	-				informatio				1		-	
Lot 42-1 (C)	150	14	1,932	8	1,288	48	48	66	-				n below in				<u> </u>			
Lot 42-1 (D) (for doors, see below)	22	14	69	8	46	2	2	3	-				nonradioac				_		-	
Lot 42-2 (A)	173	14	1,260	8	840	32	32	44	-				tive				-		_	
Lot 42-2 (B)	25	14	329	8	220	9	9	13	-				section.				-		-	
Lot 42-2 (C)	shared wall	I					-		-		ı				I	ı	-		-	
Lot 42-2 (D) (for doors, see below)	23	14	125	8	84	4	4	6	-				Caa balann				-		-	
Lot 42-2 (E)	14	14	0	8	0	0	0	0	-				See below.				-		-	
Lot 44 (A)	100	14	1,302	8	868	33	33	45	-								33	2.68	-	
Lot 44 (B)	25	14	210	8	140	6	-		6	9							6	0.49	-	
Lot 44 (C)	shared wall						-		-								-		-	
Lot 44 (D) (for doors, see below)	26	14	263	8	176	7	7	10	-								7	0.57	-	
Subtotal for radioactive materials less than 50 pCi/g						207	201	262	22	29							46	3.74		
Areas with concentrations greater than 50 pCi/g																				
Note: Lot 42-1 (A) and Lot 42-2 (C) is a shared wall. Lo									nid.			1	_		1	1	1			
Lot 42-1 (A) & Lot 42-2 (C)	50	14	700	8	467	18	18	25	-				See				-		-	
Lot 42-1 (C)	12	14	168	8	112	5	5	7	-				informatio				-		-	
Lot 42-1 (D)	7	14	98	8	66	3	3	5	-				n below in				-		-	
Lot 42-2 (A) & Lot 44 (C) Lot 42-2 (D)	83	14	1,162	8	775 38	29	29	40	-				nonradioac				-		-	
Lot 42-2 (B) Lot 42-2 (E)	4 14	14 14	56 196	8	131	5	5	7	-				tive section.				-		-	
Lot 44 (A)	7	14	98	8	66	3	3	5	-				section.				3	0.25	-	
Lot 44 (B)	10	14	140	8	94	4	-		4	6							4	0.23		
Subtotal for radioactive materials greater than 50 pC		1 1	140		J.	69	65	92	4	6							7.00	0.58		
8	78		Wall Dimens	ions		- 03		32		,			Building Mate	rials by Type			7.00	0.50		1
	Length	Height	Surface Area	Thickness	Volume	Volume	Brick	Brick	Concrete Masonry Unit/Masonr y Pilaster	Concrete Masonry Unit/Masonry Pilaster	Steel	Steel		Scrap metal	Scran motal	Scran motal	Wood	Wood	Glass	Glass
Wall Categories	(FT)	(FT)	(SF)	(IN)	(CF)	(CY)	(CY)	(TN)	(CY)	(TN)	(SF)	(CY)	(TN)	(SF)	(CY)	(TN)	(CY)	(TN)	(CY)	(TN)
Not radioactive materials located on radioactive wall		()	(0.7	()	(6.7	(0.7	(0.7	(,	(6.7	(,	(0.7	(9.7	()	(0.7	(4.7	(,	(0.7	(,	(0.7	(,
Structural steel	-								_											
Lot 33-1 (A) - lower potentially contaminated area							-			l.	290	8	7	-	-					
Lot 33-1 (B) - middle potentially contaminated area							-				98	3	3	-	-					
Lot 33-1 (B) - lower potentially contaminated area							-				173	5	5	-	-					
Lot 42-1 (A)							-				1,554	39	47	-	-					
Lot 42-1 (B)							-	See huild	ing materials inf	formation below	420	11	10	-	-	See building	materials in	nformation	helow ra	adioactive
Lot 42-1 (C)		See wall	information above ra	adioactive materi	als.		-	See balla	radioactive ma		1,932	48	44	-	-	Jee ballaling		aterials.	1 DCIOW 16	adioactive
Lot 42-1 (D) (for doors, see below)							-		radioactive ma	teriais.	69	2	5	-	-			accitats.		
Lot 42-2 (A)							-				1,260	32	51	-	-					
Lot 42-2 (B)							-				329	9	8	-	-	ļ				
Lot 42-2 (D)							-				0	0	5	-	-	•				
Lot 42-2 (E)							-				125	4	5	-	-					
Doors Lot 42-1 (D) - Roll-up door	10	12	120				-		_		-	-		120	0.130	0.080	Ι -		l _	
Lot 42-1 (D) - Roll-up door Lot 42-1 (D) - Door (smaller roll up)	3	7	21	1.75	3.063	0.114			-		-	-		21	0.130	0.080	0.114	0.093	-	
Lot 42-2 (B) - Door	3	7	21	1.75	3.063	0.114	-		-		-	-		-	0.114	0.014	0.114	0.093	-	
` '	10	12	120				_		-		_	_		120	0.130	0.080	-		_	
LOT 42-2 (D) - KOII-UD GOOF						0.114	_				_			21				0.093	_	
Lot 42-2 (D) - Roll-up door Lot 42-2 (D) - Door (smaller roll up)	3	/	21	1.75	3,063	0.114	-		-		-	-		21	0.114	0.014	0.114			
Lot 42-2 (D) - Roll-up door Lot 42-2 (D) - Door (smaller roll up) Lot 44 (D) - Roll-up door	3 10	7 8	21 80	1.75	3.063	0.114	-		-		-	-		80	0.114 0.090	0.014 0.054	0.114		-	
Lot 42-2 (D) - Door (smaller roll up)							1												-	



COMPUTED BY : MS CDM Smith Wolff-Alport CC Superfund Site KK CHECKED BY: PROJECT: DATE CHECKED: 7/12/2018 4/27/2018 JOB NO.: 226078-6460 E3001 002 DES95 DATE: CLIENT: USACE - KC Mass of Building Materials by Type Wall Dimensions Concrete Concrete Masonry Masonry Unit/Masonry Unit/Masonr Length Height Surface Area Thickness Brick Brick Pilaster Steel Steel Wood Wood Glass Glass y Pilaster Steel Scrap metal Scrap metal Scrap metal **Wall Categories** (IN) (CF) (CY) (TN) (TN) (SF) (CY) (TN) (TN) (CY) (TN) (CY) (TN) (FT) (FT) (SF) (CY) (CY) (SF) (CY) Not Radioactive Walls ot 33-1 (A) - upper uncontaminated area 153 14 1.852 8 1.235 46 46 14 46 53 1 852 46 38 ot 33-1 (B) - upper uncontaminated area 112 14 1,297 865 33 33 10 33 38 1,297 33 28 ot 33-1 (C) 60 14 840 560 21 21 7 21 24 840 18 8 21 ot 33-1 (D) 28 14 392 8 262 10 10 4 10 12 392 10 9 ot 33-1 (E) 14 294 8 10 294 21 196 8 8 8 8 ot 33-1 (F) 51 14 240 8 160 2 6 7 240 5 Roll-up door 26 13 338 338 0.370 0.226 Door (smaller roll up) 3 7 21 1.75 4 0.149 21 0.020 0.014 0.149 0.121 Windows 23 115 0.13 1.246 0.047 0.047 0.100 ot 33-2 (A) shared wall ot 33-2 (B) shared wall ot 33-2 (C) 21 294 294 14 196 8 8 10 8 8 8 ot 33-2 (D) 28 14 252 168 252 6 Windows 5 140 0.13 2 0.075 0.075 0.159 28 ot 33-3 (A) shared wall ot 33-3 (B) 14 448 299 12 12 12 448 12 10 32 14 18 ot 33-3 (C) 60 14 840 560 21 21 21 24 840 21 ot 33-3 (D) 25 14 147 8 98 4 4 2 4 5 147 4 4 Roll-up door 13 13 169 169 0.190 0.113 Door (smaller roll up) 21 1.75 0.149 21 0.020 0.014 0.149 0.121 0.13 0.141 0.006 0.013 Windows 5 13 0.006 3 ot 33-4 (A) shared wall ot 33-4 (B) 14 826 551 826 59 8 21 21 21 24 21 18 ot 33-4 (C) 19 14 259 8 173 7 7 3 7 8 259 7 6 279 11 418 11 10 ot 33-4 (D) 41 14 418 8 11 4 11 13 Roll-up door 13 12 156 156 0.170 0.104 btotal for Lot 33 Not Radioactive Walls 215.5 184 705 0.770 0.471 0.298 0.242 0.128 0.272 215 73 215 250 8.399 215 **Wall Dimensions** Mass of Building Materials by Type Concrete Masonry Concrete Masonry Unit/Masonry Unit/Masonr Glass Height Surface Area Thickness Brick Brick Wood Wood Glass Length Volume Volume y Pilaster Pilaster Steel Steel Steel Scrap metal Scrap metal Scrap metal **Wall Categories** (FT) (FT) (IN) (CF) (CY) (CY) (TN) (CY) (TN) (SF) (CY) (TN) (SF) (CY) (TN) (CY) (TN) (CY) (TN) (SF) Not Radioactive Walls ot 46-1 - first floor (A) (includes portion of 27 11 89 60 3 3 3 0.243 aboveground basement wall) Roll-up door 1 10 80 80 0.090 0.054 128 Roll-up door 2 (over windows) 16 128 0.140 0.086 8 Windows 16 128 0.13 1.387 0.052 0.111 0 ot 46-1 - first floor (B) (includes portion of 57 11 414 8 276 11 11 15 11 0.891 aboveground basement wall) Roll-up door 12 0.110 0.064 8 96 96 Door 21 1.75 3.063 0.114 0.010 12 0.039 Windows (store) 8 96 0.13 1.040 0.039 0.083 ot 46-1 - first floor (C) (includes portion of 27 11 297 8 198 8 8 11 8 0.648 --_ -aboveground basement wall) Lot 46-1 - first floor (D) (includes portion of shared wall aboveground basement wall)



Lot 46-1 - second floor (A)

ot 46-1 - second floor (B)

ot 46-1 - second floor (C)

ot 46-1 - second floor (D)

Windows (second floor apartment, 3 windows)

27

57

2.5

27

57

11

11

4

11

11

297

616

11

297

627

8

0.13

8

8

198

411

0.358

198

418

8

16

0.0140

8

16

8

16

16

11

22

11

22

8

16

8

16

0.648

1.296

0.648

1.296

0.014

0.030

	PROJECT:	Wolff-Alport	CC Superfund Site	_	COMPUTED BY :	KK	_	CHECKED BY:	MS	_										
CDIVILL	JOB NO.:	226078-6460	F3001.002.DES95	_	DATE:	4/27/2018	•	DATE CHECKED:	7/12/2018	_										
CDM Smith	CLIENT:	USA	ACE - KC	-	-		•			_										
Lot 46-2 (A)	42	11	237	8	158	6	6	9	-		_	-		T -	_		6	0.486	_	
Roll-up door (1)	9	9	81				-		_		-	-		81	0.090	0.054	-		-	
Door (half glass)	3	7	12	1.75	2	0.075	_		_		-	_		-	-		0	0.007	_	
Glass	2.5	4	9	0.13	0.098	0.004	-		-		-	-		_	_		-		0.004	0.009
Roll-up door (2)	9	8	72				_		-			_		72	0.080	0.048	_		-	
Door (half glass)	3	7	12	1.75	2	0.075	_		-		_	_			-		0	0.007	_	
Glass	2.5	4	9	0.13	0.098	0.004	-		-		-	-		_	_		-		0.004	0.009
Door (half glass)	3	7	12	1.75	2	0.075	-		-		-	-		-	_		0	0.007	-	
Glass	2.5	4	9	0.13	0.098	0.004	_		_		_	_		_	_		-		0.004	0.009
Door (half glass)	3	7	12	1.75	2	0.075	_		-		-	-		_	_		0	0.007	-	
Glass	2.5	4	9	0.13	0.098	0.004	_		-		-	-		_	_		-		0.004	0.009
Roll-up door (3)	9	8	72				-		-		-	-		72	0.080	0.048	-		-	
Door	3	7	21	1.75	4	0.149	_		-		-	-			-		0	0.013	-	
Window	6	7	42	0.13	0.455	0.017	_		_		_	_		-	_		-	0.013	0.017	0.037
Lot 46-2 (B)	27	11	297	8	198	8	8	11	_		-	-		_	_		8	0.648	-	
Lot 46-2 (C)	shared wall	11	237	8	130	8	-	11				-		_	<u> </u>		-	0.048	-	
Lot 46-2 (D)	shared wall											-					_			
Subtotal for Lot 46 Not Radioactive Walls	Silaieu Wali					84.8	84	117	0	0	0	0	0	529	0.590	0.354	84.563	6.855	0.138	0.297
Austotal for Lot 40 Not Radioactive Walls			Wall Dimens	ions		04.0	04	117		U				erials by Type	0.590	0.554	64.303	0.055	0.136	0.237
			VVali Dilliens	lulis					Comoveto			IVIASS OF B	unung wat							
	Length	Height	Surface Area	Thickness	Volume	Volume	Brick	Brick	Concrete Masonry Unit/Masonr y Pilaster	Concrete Masonry Unit/Masonry Pilaster	Steel	Steel	Steel		Scrap metal	Scrap metal		Wood	Glass	Glass
Wall Categories	(FT)	(FT)	(SF)	(IN)	(CF)	(CY)	(CY)	(TN)	(CY)	(TN)	(SF)	(CY)	(TN)	(SF)	(CY)	(TN)	(CY)	(TN)	(CY)	(TN)
Not Radioactive Walls																	_		•	
Lot 48-1 (A)	34	14	122	8	82	4	4	7	-		-	-		-	-		-		-	
Garage door	18	13	234				-		-		-	-		234	0.260	0.156	-		-	
Garage door	10	12	120				-		-		-	-		120	0.130	0.080	-		-	
Lot 48-1 (B)	28	14	392	8	262	10	10	16	-		-	-		-	-		-		-	
Lot 48-1 (C)	33	14	462	8	308	12	12	19	-		-	-		-	-		-		-	
Lot 48-1 (D)	78	14	1,092	8	728	27	27	41	-		-	-		-	-		-		-	
Lot 48-2 (A)	16	12	161	8	108	4	4	7	-		-	-		-	-		-		-	
Door	3	7	21	1.75	4	0.149	-		-		-	-		-	-		0.149	0.121	-	
Windows (2)	3	3	10	0.13	1.000	0.038	-		-		-	-		-	-		-		0.038	0.081
Lot 48-2 (B)	14	12	168	8	112	5	5	8	-		-	-		-	-		-		-	
Lot 48-2 (C)	15	12	180	8	120	5	5	8	-		-	-		-	-		-		-	
Lot 48-2 (D)	shared wall		•				-		-		•	-		-	-		-		-	
	15	12	180	8	120	5	5	8	-			-		-	-		-		-	
Lot 48-2 (E)																				
Lot 48-2 (E) Subtotal for Lot 48 Not Radioactive Walls						72.2	72	114	0	0	0	0	0	354	0.390	0.236	0.149	0.121	0.038	0.081
						72.2	72	114	0	0	0	0	0	354	0.390	0.236	0.149	0.121	0.038	0.081

Summary of Volumes (rounded to the nearest whole number)

Hazardous Building Materials

ACM (TN): 201
Mercury-containing lamps, 2 ft (each): 42
Mercury-containing lamps, 4 ft (each): 192
Mercury-containing thermostats (each): 4

Building Demolition Debris

Note: Salvageable material includes steel and scrap metal.

Radioactive Material, less than 50 pCi/g: 893 877
Radioactive Material, greater than 50 pCi/g: 76 99
Non-Porous (Salvageable) Material: 33,026 606 437



Appendix E

Appendix E

Backfill Volume Calculation



Appendix E
Backfill Volume Calculation
Wolff-Alport Chemical Company Site
Ridgewood, Queens, New York

CDM	
Smi	th

 PROJECT:
 Wolff-Alport

 JOB NO.:
 W912DQ18F3001

 CLIENT:
 USACE

COMPUTED BY : KK

DATE : 4/27/2018

CHECKED BY: ____

MS 6/11/2018

Description:

Determine the volume of backfill needed.

Assumptions:

- Basement height is from the basement floor to ground surface.
- The areas of exposed soil will be covered with 6 inches of crushed stone.
- The entire rail spur area will require backfill after demolition, segregation and transportation and disposal activities are completed.
- Sump hole dimensions are based on the upper range of typical sump construction dimensions.

Sump hole diameter and depth, IN: 3

	Area				Volume	
Category of Backfill Area	Length (feet)	Width (feet)	Area (feet²)	Depth (feet)	(feet³)	(CY)
Basement of Lot 46	62	26	1612	5	8,060	299
Gravel Cover over Geomembrane	62	26	1612	0.5	806	30
Area between Lot 33 and Lot 42 buildings	130	4.4	572	0.5	286	11
Sump in Lot 46	5			2.5	12.5	0.5
Sump in Lot 33	5			2.5	12.5	0.5
Backfill in rail spur area*	13,500			0.5	6,750	250
* Area of rail spur from AutoCAD measurement. Total						591



Appendix F

Appendix F

Permit Applications

NYCDEP-Asbestos

NYCDEP Water and Sewer

NYCDOB-Forms

NYCDOT



NYCDEP-Asbestos



New York City Department of Environmental Protection Bureau of Environmental Compliance

Asbestos Control Program

Asbestos Rules and Regulations

Title 15, Chapter 1 of the Rules of the City of New York

Revised: 02/03/2011

Chapter 1

Asbestos Control Program

Subchapter A Scope, Application, Definitions and Variances

B Certification Provisions

C Notifications, Permitting and Recordkeeping

D Air and Bulk Sampling, Monitoring and Analysis

E Personnel Protection and Equipment Specifications

F Asbestos Project Procedures

G Pre-Demolition Abatement Activity Procedures

Subchapter A

Scope, Application, Definitions and Variances

§ 1-01 Scope and Application

§ 1-02 Definitions

§ 1-03 Variances

- **§ 1-01 Scope and Application.** (a) The following asbestos control program rules, § 1-01 et seq., shall apply to all asbestos abatement activities occurring within the City of New York.
- (b) Every owner of a building where asbestos abatement activity occurs shall be responsible for the performance of the asbestos abatement activities by his/her agent, contractor, employee, or other representative.
- (c) Every contractor and worker engaged in asbestos abatement activities shall comply with the provisions of this chapter except as otherwise specified.
- (d) Every investigator engaged to identify the presence and evaluate the condition of asbestos in a building or structure shall comply with the provisions of this chapter except as otherwise specified.
- (e) No person shall knowingly make a false statement or submit a false document to the Department as to any matter concerning an asbestos project or any document required to be filed under these rules
- (f) The department may inspect at a reasonable time and in a reasonable manner anything which affects or may affect the emission or release of asbestos fibers or the disturbance of asbestos-containing material, including but not limited to the premises where an asbestos project is being conducted, or the premises for which a notification has been filed under § 1-21 § 1-26 of these Rules, or the premises where an application has been filed with the Department of Buildings for a plan or permit approval.
- (g) No person shall interfere with or obstruct any employee of the Department in the performance of their official duties, including but not limited to the performance of inspections.

- (h) No person who holds a certificate issued pursuant to these rules shall engage in unprofessional conduct. Unprofessional conduct shall include but is not limited to:
 - (1) Failure to comply with provisions of Federal, State or local laws, rules, or regulations.
 - (2) Conduct in asbestos inspections, assessment, abatement activities, air sampling, etc. which evidences moral unfitness.
 - (3) Making or filing a false report, or failing to file a report required by these rules or impeding or obstructing such filing, or inducing another person to do so.
- (i) The size (amount of material to be disturbed or, in the case of cleanups, the dimensions of the area to be cleaned) and scope of the overall project shall control the notification to be filed and work procedures to be followed. The requirements set forth in these rules may not be avoided or lessened through the performance of work in increments or piecemeal fashion.
- (j) (1) Any person, including but not limited to contractors, building owners, and air monitoring companies, who is in violation of or fails to comply with any provision of these rules or the terms and conditions of any variance issued pursuant to these rules shall be subject to the issuance of notice(s) of violation and other civil and criminal enforcement actions pursuant to Title 24, Chapter 1, Subchapter 9 of the Administrative Code of the City of New York.
 - (2) The maximum civil penalty for any violation of a lettered subsection of these rules, pursuant to a notice of violation returnable before the Environmental Control Board, shall be \$10,000, except that a violation of section 1-26 shall carry a maximum penalty of \$15,000.
 - (3) DEP may deny any application for an asbestos abatement permit pursuant to section 1-26 of these rules, or a variance application pursuant to section 1-03 of these rules, where any party to the asbestos project, including but not limited to the abatement contractor, building owner, and air monitoring company, has docketed, unpaid civil penalties imposed by the Environmental Control Board for violations of these rules, sections 24-146.1 and 24-146.3 of the Administrative Code, or NYSDOL ICR 56.

§ 1-02 Definitions.

Abatement. "Abatement" shall mean any and all procedures physically taken to control fiber release from asbestos-containing materials. This includes removal, encapsulation, enclosure, cleanup and repair.

Abatement activities. "Abatement activities" shall mean all activities from the initiation of work area preparation through successful clearance air monitoring performed at the conclusion of an asbestos project or minor project.

Adequately wet. "Adequately wet" shall mean the complete penetration of a material with amended water to prevent the release of particulates. If visible emissions are observed coming from asbestos-containing material, then the material has not been adequately wetted. However, the

absence of visible emissions is not evidence of being adequately wet. ACM must be fully penetrated with the wetting agent in order to be considered adequately wet. If the ACM being abated is resistant to amended water penetration, wetting agent shall be applied to the material prior to and during removal as necessary to minimize fiber release.

Aggressive sampling. "Aggressive sampling" shall mean a method of sampling in which the individual collecting the air sample creates activity by the use of mechanical equipment during the sampling period to stir up settled dust and simulate activity in that area of the building.

AHERA. "AHERA" shall mean the Asbestos Hazard Emergency Response Act of 1986.

AIHA. "AIHA" shall mean the American Industrial Hygiene Association.

Airlock. "Airlock" shall mean a system for permitting entrance and exit while restricting air movement between a contaminated area and an uncontaminated area. It consists of two curtained doorways separated by a distance of at least three feet such that one passes through one doorway into the airlock, allowing the doorway sheeting to overlap and close off the opening before proceeding through the second doorway, thereby preventing flow-through contamination.

Air sampling. "Air sampling" shall mean the process of measuring the fiber content of a known volume of air collected during a specific period of time. The procedure utilized for asbestos follows the NIOSH Standard Analytical Method 7400 or the provisional transmission electron microscopy methods developed by the USEPA and/or National Institute of Science and Technology which are utilized for lower detectability and specific fiber identification.

Ambient air monitoring. "Ambient air monitoring" shall mean measurement or determination of airborne asbestos fiber concentrations outside but in the general vicinity of the worksite.

Amended water. "Amended water" shall mean water to which a surfactant has been added.

ANSI. "ANSI" shall mean the American National Standards Institute.

Area air sampling. "Area air sampling" shall mean any form of air sampling or monitoring where the sampling device is placed at some stationary location.

Asbestos. "Asbestos" shall mean any hydrated mineral silicate separable into commercially usable fibers, including but not limited to chrysotile (serpentine), amosite (cumingtonite-grunerite), crocidolite (riebeckite), tremolite, anthrophyllite and actinolite.

Asbestos-containing material. "Asbestos-containing material" (ACM) shall mean asbestos or any material containing more than one percent asbestos.

Asbestos-containing waste material. "Asbestos-containing waste material" shall mean asbestos-containing material or asbestos-contaminated objects requiring disposal.

Asbestos-contaminated objects. "Asbestos-contaminated objects" shall mean any objects which have been contaminated by asbestos or asbestos-containing material.

Asbestos assessment report. "Asbestos assessment report" shall mean the "Form ACP-5" form, as approved by DEP, by which a DEP-certified asbestos investigator certifies that a building or structure (or portion thereof) is free of ACM or the amount of ACM to be abated constitutes a minor project.

Asbestos handler. "Asbestos handler" shall mean an individual certified by the Department who disturbs, removes, encapsulates, repairs, or encloses asbestos material.

Asbestos handler supervisor. "Asbestos handler supervisor" shall mean an individual certified by the Department who supervises the handlers during an asbestos project and ensures that proper asbestos abatement procedures as well as individual safety procedures are being adhered to.

Asbestos project notification. "Asbestos project notification" shall mean the "Form ACP-7" asbestos project notification form as approved by DEP.

Asbestos investigator. "Asbestos investigator" shall mean an individual certified by the Commissioner as having satisfactorily demonstrated his or her ability to identify the presence and evaluate the condition of asbestos in a building or structure.

Asbestos project. "Asbestos project" shall mean any form of work performed in a building or structure or in connection with the replacement or repair of equipment, pipes, or electrical equipment not located in a building or structure which will disturb (e.g., remove, enclose, encapsulate) more than 25 linear feet or more than 10 square feet of asbestos-containing material.

ASTM. "ASTM" shall mean the American Society For Testing and Materials.

Authorized visitor. "Authorized visitor" shall mean the building owner and his/her representative, and any representative of a regulatory or other agency having jurisdiction over the project.

Building owner. "Building owner" shall mean the person in whom legal title to the premises is vested unless the premises are held in land trust, in which instance building owner means the person in whom beneficial title is vested.

Building materials. "Building materials" shall mean any and all materials listed as Presumed Asbestos Containing Materials (PACM) and Suspect Miscellaneous ACM in NYSDOL ICR 56, including but not limited to interior and exterior finishes, equipment, plaster, roofing, flooring, caulking, sealants, tiles, insulation, and mortar and refractory bricks used in the construction of boilers.

Certified industrial hygienist. "Certified industrial hygienist" (CIH) shall mean an individual who is currently certified by] the American Board of Industrial Hygiene.

Certified safety professional (CSP). "Certified safety professional" (CSP) shall mean an individual having a bachelor's degree from an accredited college or university and a minimum of four years experience as a safety professional and who has successfully completed both levels of the examination administered by the Board of Certified Safety Professionals and who is currently certified by that Board.

Chain of custody. "Chain of custody" shall mean the form or set of forms that document the collection and transfer of a sample.

Clean room. "Clean room" shall mean an uncontaminated area or room which is part of the worker decontamination enclosure system with provisions for storage of workers' street clothes and protective equipment.

Clearance air monitoring. "Clearance air monitoring" shall mean the employment of aggressive sampling techniques with a volume of air collected to determine the airborne concentration of residual fibers, and shall be performed as the final abatement activity.

Commissioner. "Commissioner" shall mean the Commissioner of the New York City Department of Environmental Protection.

Contractor. "Contractor" shall mean a public authority or any other governmental agency or instrumentality thereof, self-employed person, company, unincorporated association, firm, partnership or corporation and any owner or operator thereof, which engages in an asbestos project or employs persons engaged in an asbestos project.

Curtained doorway. "Curtained doorway" shall mean a device which consists of at least three overlapping sheets of fire retardant plastic over an existing or temporarily framed doorway. One sheet shall be secured at the top and left side, the second sheet at the top and right side, and the third sheet at the top and left side. All sheets shall have weights attached to the bottom to ensure that the sheets hang straight and maintain a seal over the doorway when not in use.

Decontamination enclosure system. "Decontamination enclosure system" shall mean a series of connected rooms, separated from the work area and from each other by air locks, for the decontamination of workers, materials, waste containers, and equipment.

Demolition. "Demolition" shall mean the dismantling or razing of a building, including all operations incidental thereto (except for asbestos abatement activities), for which a demolition permit from the New York City Department of Buildings is required.

Department or DEP. "Department" or "DEP" shall mean the New York City Department of Environmental Protection.

Disturb. "Disturb" shall mean any action taken which may alter, change, or stir, such as but not limited to the removal, encapsulation, enclosure or repair of asbestos-containing material.

DOB. "DOB" shall mean the New York City Department of Buildings.

ELAP. "ELAP" shall mean the Environmental Laboratory Approval Program administered by the New York State Department of Health.

Encapsulant (sealant) or encapsulating agent. "Encapsulant (sealant) or encapsulating agent" shall mean liquid material which can be applied to asbestos-containing material which temporarily controls the possible release of asbestos fibers from the material or surface either by creating a membrane over the surface (bridging encapsulant) or by penetrating into the material and binding its components together (penetrating encapsulant). A thin coat of lockdown encapsulant shall be applied to all surfaces in the work area which were not the subject of removal or abatement, including the cleaned layer of the surface barriers, but excepting sprinklers, standpipes, and other active elements of the fire suppression system.

Encapsulation. "Encapsulation" shall mean the coating or spraying of asbestoscontaining material encapsulant. A thin coat of lockdown encapsulant shall be applied to all surfaces in the work area which were not the subject of removal or abatement, including the cleaned layer of the surface barriers, but excepting sprinklers, standpipes, and other active elements of the fire suppression system.

Enclosure. "Enclosure" shall mean the construction of airtight walls and ceilings between the ACM and the facility environment, or around surfaces coated with ACM, or any other appropriate procedure as determined by the Department which prevents the release of asbestos fibers.

EPA. "EPA" or "USEPA" shall mean the United States Environmental Protection Agency.

Equipment room. "Equipment room" shall mean a contaminated area or room which is part of the worker decontamination enclosure system with provisions for the storage of contaminated clothing and equipment.

Exit. "Exit" shall mean that portion of a means of egress system which is separated from other interior spaces of a building or structure by fire-resistance-rated construction to provide a protected path of egress travel between the exit access and the exit discharge.

FDNY. "FDNY" shall mean the Fire Department of the City of New York.

Fiber. "Fiber" shall mean an acicular single crystal or a similarity elongated polycrystalline aggregate which displays some resemblance to organic fibers by having such properties as flexibility, high aspect ratio, silky luster, axial lineation, and others, and which has attained its shape primarily through growth rather than cleavage.

Fixed object. "Fixed object" shall mean a unit of equipment, furniture, or other item in the work area which cannot be removed from the work area. Fixed objects shall include equipment, furniture, or other items that are attached, in whole or in part, to a floor, ceiling, wall, or other building structure or system or to another fixed object and cannot be reasonably removed from the work area. Fixed objects shall also include pipes and other equipment inside the work area which are not the subject of the asbestos project. Active fire suppression system components shall not be considered fixed objects.

Glovebag technique. "Glovebag technique" shall mean a method for removing asbestoscontaining material from heating, ventilation and air conditioning (HVAC) ducts, short piping runs, valves, joints, elbows, and other nonplanar surfaces. The glovebag assembly is a manufactured device consisting of a large bag (constructed of at least 6-mil transparent plastic), two inward-projecting long sleeve gloves, one inward-projecting waterwand sleeve, an internal tool pouch, and an attached, labeled receptacle for asbestos waste. The glovebag is constructed and installed in such a manner that it surrounds the object or area to be decontaminated and contains all asbestos fibers released during the removal process.

HEPA filter. "HEPA filter" shall mean a high efficiency particulate air filter capable of trapping and retaining 99.97 percent of particles (asbestos fibers) greater than 0.3 micrometers mass median aerodynamic equivalent diameter.

HEPA vacuum equipment. "HEPA vacuum equipment" shall mean vacuuming equipment with a HEPA filter.

Holding area. "Holding area" shall mean a chamber in the equipment decontamination enclosure located between the washroom and an uncontaminated area.

Homogeneous work area. "Homogeneous work area" shall mean a portion of the work area which contains one type of asbestos-containing material and/or where one type of abatement is used

Industrial hygiene. "Industrial hygiene" shall mean that science and art devoted to the recognition, evaluation and control of those environmental factors or stresses, arising in or from the work place, which may cause sickness, impaired health and well being, or significant discomfort and inefficiency among workers or among the citizens of the community.

Industrial hygienist. "Industrial hygienist" shall mean an individual having a college or university degree or degrees in engineering, chemistry, physics, or medicine or related biological sciences who, by virtue of special studies and training, has acquired competence in industrial hygiene.

Isolation barrier. "Isolation barrier" shall mean the construction of partitions, the placement of solid materials, and the plasticizing of apertures to seal off the work place from surrounding areas and to contain asbestos fibers in the work area.

Large asbestos project. "Large asbestos project" shall mean an asbestos project involving the disturbance (e.g., removal, enclosure, encapsulation) of 260 linear feet or more of asbestos-containing material or 160 square feet or more of asbestos-containing material.

Log. "Log" shall mean an official record, maintained by the abatement contractor, of all activities that occurred during the project. At a minimum, the log shall identify the building owner, agent, contractor, and workers, and other pertinent information including daily activities, cleanings and waste transfers, names and certificate numbers of asbestos handler supervisors and asbestos handlers; results of inspections of decontamination systems, barriers, and negative pressure ventilation equipment; summary of corrective actions and repairs; work stoppages with reason for stoppage; manometer readings at least twice per work shift; daily checks of emergency and fire exits and any unusual events.

Means of egress. "Means of egress" shall mean a continuous and unobstructed path of vertical and horizontal egress travel from any occupied portion of a building or structure to a public way. A means of egress consists of three separate and distinct parts: the exit access, the exit and the exit discharge.

Minor project. "Minor project" shall mean a project involving the disturbance (e.g. removal, enclosure, encapsulation, repair) of 25 linear feet or less of asbestos containing material or 10 square feet or less of asbestos containing material.

Movable object. "Movable object" shall mean a unit of equipment or furniture in the work area which can be removed from the work area.

Negative air pressure equipment. "Negative air pressure equipment" shall mean a portable local exhaust system equipped with HEPA filtration. The system shall be capable of creating a negative pressure differential between the outside and inside of the work area.

NFPA. "NFPA" shall mean the National Fire Protection Association.

NIOSH. "NIOSH" shall mean the National Institute for Occupational Safety and Health.

NYSDOL. "NYSDOL" shall mean the New York State Department of Labor.

NYSDOL ICR 56. "NYSDOL ICR 56" shall mean Part 56 of the Official Compilation of Codes, Rules and Regulations of the State of New York or 12 NYCRR Part 56.

NYSDOH. "NYSDOH" shall mean the New York State Department of Health.

Obstruction. "Obstruction" shall mean the blocking of a means of egress with any temporary structure or barrier. Polyethylene sheeting shall not be considered an obstruction when it is prominently marked with exit signage or paint and cutting tools (knife, razor) are attached to the work area side of the sheeting for use in the event that the sheeting must be cut to permit egress. A corridor shall not be considered obstructed when there is a clear path measuring at least three (3) feet wide.

Occupied Area. "Occupied area" shall mean an area of the worksite where abatement is not taking place and where personnel or occupants normally function or where workers are not required to use personal protective equipment.

OSHA. "OSHA" shall mean the United States Occupational Safety and Health Administration.

Outside air. "Outside air" shall mean the air outside the work place.

Person. "Person" means any individual, partnership, company, corporation, association, firm, organization, governmental agency, administration or department, or any other group of individuals, or any officer or employee thereof.

Personal air monitoring. "Personal air monitoring" shall mean a method used to determine employees' exposure to airborne fibers. The sample is collected outside the respirator in the worker's breathing zone.

Personal protective equipment. "Personal protective equipment" (PPE) shall mean appropriate protective clothing, gloves, eye protection, footwear, head gear.

Phase contrast microscopy. "Phase contrast microscopy" (PCM) shall mean the measurement protocol for the assessment of the fiber content of air. (NIOSH Method 7400).

Physician. "Physician" shall mean an individual licensed or otherwise authorized under Article 131 §65.22 of the New York State Education Law.

Plasticize. "Plasticize" shall mean to cover floors and walls with fire retardant plastic sheeting as herein specified or by using spray plastics as acceptable to the Department.

Polarized light microscopy. "Polarized light microscopy" (PLM) shall mean the measurement protocol for the assessment of the asbestos content of bulk materials. (Interim Method for the Determination of Asbestiform Materials in Bulk Insulation Samples- 40 CFR Part 763, Subpart F, Appendix A as amended on September 1, 1982)

Project designer. "Project designer" shall mean a person who holds a valid Project Designer Certificate issued by the New York State Department of Labor.

Project monitor. "Project monitor" shall mean a person who holds a valid Project Monitor Certificate issued by the New York State Department of Labor.

Qualitative fit test. "Qualitative fit test" shall mean the individual test subject's responding (either voluntarily or involuntarily) to a chemical challenge outside the respirator face piece. Acceptable methods include irritant smoke test, odorous vapor test, and taste test.

Quantitative fit test. "Quantitative fit test" shall mean exposing the respirator wearer to a test atmosphere containing an easily detectable, nontoxic aerosol, vapor or gas as the test agent. Instrumentation, which samples the test atmosphere and the air inside the face piece of the respirator, is used to measure quantitatively the leakage into the respirator. There are a number of test atmospheres, test agents, and exercises to perform during the tests.

Registered design professional. "Registered design professional" shall mean a person licensed and registered to practice the professions of architecture or engineering under the Education Law of the State of New York.

Removal. "Removal" shall mean the stripping of any asbestos-containing materials from surfaces or components of a facility or taking out structural components in accordance with 40 CFR 61 Subparts A and M.

Renovation. "Renovation" shall mean an addition or alteration or change or modification of a building or the service equipment thereof, that is not classified as an ordinary repair as defined in §27-125 of the Administrative Code of the City of New York.

Repair. "Repair" shall mean corrective action using specified work practices e.g. glovebag, plastic tent procedures, etc. to minimize the likelihood of fiber release from minimally damaged areas of ACM.

Replacement material. "Replacement material" shall mean any material used to replace ACM that contains less than .01 percent asbestos.

Shift. "Shift" shall mean a worker's, or simultaneous group of workers', complete daily term of work.

Shower room. "Shower room" shall mean a room between the clean room and the equipment room in the worker decontamination enclosure with hot and cold running water controllable at the tap and arranged for complete showering during decontamination.

Small asbestos project. "Small asbestos project" shall mean an asbestos project involving the disturbance (e.g., removal, enclosure, encapsulation) of more than 25 and less than 260 linear feet of asbestos-containing material or more than 10 and less than 160 square feet of asbestos-containing material.

Staging area. "Staging area" shall mean the work area near the waste transfer airlock where containerized asbestos waste has been placed prior to removal from the work area.

Strip. "Strip" shall mean to remove asbestos materials from any part of the facility.

Structural member. "Structural member" shall mean any load-supporting member of a facility, such as beams and load-supporting walls, or any nonload-supporting member, such as ceiling and nonload-supporting walls.

Surface barriers. "Surface barriers" shall mean the plasticizing of walls, floors, and fixed objects within the work area to prevent contamination from subsequent work.

Surfactant. "Surfactant" shall mean a chemical wetting agent added to water to improve penetration.

Transmission electron microscopy (TEM). "Transmission electron microscopy (TEM)" shall mean the measurement protocol for the assessment of the asbestos fiber content of air. (Interim Transmission Electron Microscopy Analytical Methods-40 CFR Part 763, Subpart E, Appendix A)

Visible emissions. "Visible emissions" shall mean any emissions containing particulate material that are visually detectable without the aid of instruments.

Washroom. "Washroom" shall mean a room between the work area and the holding area in the equipment decontamination enclosure system where equipment and waste containers are wet cleaned and/or HEPA vacuumed prior to disposal.

Waste decontamination enclosure system. "Waste decontamination enclosure system" shall mean the decontamination enclosure system designated for the controlled transfer of materials and equipment, consisting of a washroom and a holding area.

Wet cleaning. "Wet cleaning" shall mean the removal of asbestos fibers from building surfaces and objects by using cloths, mops, or other cleaning tools which have been dampened with water.

Wet methods. "Wet methods" shall mean the use of amended water or removal encapsulants to minimize the generation of fibers during ACM disturbance.

Work area. "Work area" shall mean designated rooms, spaces, or areas of the building or structure where asbestos abatement activities take place. For glovebag procedures, the work area shall also include the areas contiguous to where the procedure takes place

Worker. "Worker" shall mean asbestos handler and/or asbestos handler supervisor.

Worker decontamination enclosure system. "Worker decontamination enclosure system" shall mean that portion of a decontamination enclosure system designed for controlled passage of workers, and other individuals and authorized visitors, consisting of a clean room, a shower room, and an equipment room separated from each other and from the work area by airlocks and curtained doorways.

Work place. "Work place" shall mean the work area and the decontamination enclosure system(s).

Work place safety plan. "Work place safety plan" shall mean documents prepared by a registered design professional and submitted for review by DEP in order to obtain an asbestos abatement permit. Such plan shall include, but not be limited to, plans, sections, and details of the work area clearly showing the extent, sequence, and means and methods by which the work is to be performed.

Work site. "Work site" shall mean premises where asbestos abatement activity is taking place, and may be composed of one or more work areas.

§1-03 Variances. (a) Application for any variance from these rules or Part 56 of Title 12 of New York Codes, Rules and Regulations (Subparts 56-4 through 56-17) shall be made directly to the Department at least two weeks prior to the commencement of work. Work involving a variance may not commence prior to the receipt of the Department's approval of the application.

- (b) The Department's "Asbestos Variance Application" (ACP-9) form shall be prepared by a project designer and submitted by the building owner or authorized agent, and shall include the following information:
 - (1) Identification of those portions of the rules for which a variance is requested, providing each numbered section and subsection;
 - (2) Explanations as to why the procedures required by the rules cannot be used;
 - (3) A written proposal setting forth the alternative procedures the applicant will employ to satisfy each requirement as modified; and

- (4) A copy of any asbestos project notification previously filed. If the applicant has not previously filed an asbestos project notification, such notification shall be filed with the application together with the applicable fee specified in §1-25(c).
- (5) A sketch or drawing illustrating the proposed modification.
- (c) For each variance application where the combined amount (total of both square and linear feet on the ACP-7) of ACM is less than 5000 feet, payment of the variance processing fee shall accompany the application and shall conform with the payment schedule as follows:
 - 1) Request to modify no more than one lettered subsection in any section category listed in subsection (e) below: \$400 fee.
 - (2) For each additional subsection in any category listed in subsection (e): \$200 fee.
 - (3) The maximum fee: \$1200.
- (d) For each variance application where the combined amount (total of both square and linear feet on the ACP-7) of ACM is greater than or equal to 5000 feet, payment of the variance processing fee shall accompany the application and shall conform with the payment schedule as follows:
 - (1) Request to modify no more than one lettered subsection in any section category listed in subsection (e): \$600.
 - (2) For each additional subsection in any category listed in subsection (e): \$300.
 - (3) The maximum fee: \$1800.
 - (e) Section categories shall be as follows:

CATEGORY	NYC Asbestos Control Program Section #s	12 NYCRR Part 56 Section #s
Air Monitoring	31-45	56-4,6
Materials and Equipment	61	56-7
Work Place Preparation	81-84	56-7
Work Place Procedure	91-94	56-7
Abatement Procedures	101-110	56-8
Clean-up Procedures	111-112	56-9
Pre-Demolition Abatement Activity Procedures	120-129	

⁽f) Any variance from the prohibition on concurrent abatement and full demolition or story removal set forth in section 1-126 shall only be approved after notification and consultation with FDNY and DOB.

⁽g) Any violation of the terms of any variance issued under this section shall be considered a violation of the lettered subdivision modified by the variance.

Subchapter B

Certification Provisions

Part 1

Certification Procedures

- §1-11 Asbestos Handler Certificate
- §1-12 Renewal of Asbestos Handler Certificate
- §1-13 Restricted Asbestos Handler Certificate
- §1-14 Asbestos Handler Supervisor Certificate
- §1-15 Renewal of Asbestos Handler Supervisor Certificate
- §1-16 Asbestos Investigator Certificate
- §1-17 Renewal of Asbestos Investigator Certificate
- **§1-11 Asbestos Handler Certificate.** (a) No individual shall engage in an asbestos project or in asbestos abatement activities on a minor project, for compensation, unless that individual is certified as an asbestos handler by the department and has an "Asbestos Handler Certificate" issued by the department which shall be available at the work place.
- (b) The department shall issue an asbestos handler certificate in the form of a photo identification card which shall be valid for two years from the date of issuance to applicants who meet the following conditions:
 - (1) Applicant shall be at least eighteen (18) years of age at the date of application; and
 - (2) Applicant shall submit a completed application provided by the department accompanied by a fee of one hundred dollars (\$100); and
 - (3) Applicant shall submit documentation of successful completion within the prior 12 months of a NYSDOH-approved Asbestos Handler training course; and
 - (4) Applicant shall achieve a passing grade on a departmental examination.
- (c) An applicant denied a certificate on any grounds other than failure to complete a certificate application or failure to meet the minimum requirements set forth in these rules may request a hearing before the commissioner or his/her designee to contest said denial by submitting a written request for such hearing within ten days of receipt of denial.

- § 1-12 Renewal of Asbestos Handler Certificate. (a) The handler shall apply for renewal of the certificate at least 60 days prior to the date of its expiration.
- (b) Application for renewal shall be made on a form approved by the department and shall be accompanied by a fee of one hundred dollars (\$100) and proof of successful completion within the prior 12 months of a NYSDOH-approved Asbestos Handler Refresher training course; and
- (c) An applicant denied a certificate on any grounds other than failure to complete a certificate application or failure to meet the minimum requirements set forth in these rules may request a hearing before the commissioner or his/her designee to contest said denial by submitting a written request for such hearing within ten days of receipt of denial.
- (d) In the event that an asbestos handler certificate is lost or stolen, the certificate holder must immediately notify the department. An application for a replacement shall be made in writing and shall include a notarized statement that the certificate was lost or stolen, a statement that the applicant understands that submittal of a false statement shall subject him or her to penalties and other remedies under the law, and a fee of \$50.
- **§1-13 Restricted Asbestos Handler Certificate.** (a) This section shall apply to individuals involved in the construction of the containment barriers of a work area (e.g., carpenters), or who otherwise enter the contained work area for a limited period of time to perform certain specialized tasks in preparation for, or ancillary to, the actual abatement (e.g., electricians); and for whom asbestos handler certification would otherwise be required. This section shall not apply to individuals performing abatement handling of ACM.
- (b) The department shall issue a restricted asbestos handler certificate, in the form of a photo identification card which shall be valid for two years from the date of issuance to applicants who comply with the requirements of §1-11(b)(1)-(4), except that the fee shall be \$50.
- (c) An individual certified as a restricted asbestos handler by the department shall perform only those particular job functions specified by the department in the application for certification.
- **§1-14 Asbestos Handler Supervisor Certificate.** (a) No individual shall supervise asbestos handlers engaged in an asbestos project, for compensation, unless that individual is certified as an asbestos handler supervisor by the department.
- (b) The department shall issue an asbestos handler supervisor certificate, in the form of a photo identification card which shall be valid for two years from the date of issuance, to applicants who meet the following conditions:
 - (1) Applicant shall be at least twenty-one (21) years of age at the time of application; and
 - (2) Applicant shall submit a completed application provided by the department accompanied by a fee of one hundred dollars (\$100); and

- (3) Applicant shall submit documentation of successful completion within the prior 12 months of a NYSDOH-approved Asbestos Supervisor training course.
- (4) Applicant shall submit additional credentials as follows:
 - (i) A registered design professional, certified industrial hygienist, or certified safety professional shall submit a copy of the licensing credentials or certification, and documentation of one month post-graduate experience in asbestos abatement activities.
 - (ii) A graduate from an accredited college or university possessing a bachelor's or advanced degree in engineering, architecture, environmental health science, industrial hygiene, occupational health and safety or a related science shall submit a copy of the degree, and documentation of three months post graduate experience in asbestos abatement activities.
 - (iii)A graduate from an accredited college of university possessing an associate's degree in applied science and technology, environmental health science, public health, industrial health or a related science shall submit a copy of the degree, and documentation of six months post-graduate experience in asbestos abatement activities.
 - (iv)All other applicants shall submit documentation of one year of experience in asbestos abatement activities.

The applicant's experience in asbestos abatement activities shall be listed chronologically and shall include each contractor's name/address/phone number; the number of hours worked per week on asbestos abatement activities; the applicant's job title and a brief description of duties; and

- (5) Applicant shall achieve a passing grade on a departmental examination.
- (c) The department may consider applicants who submit additional credentials which are not identical to the categories specified in subdivision (b)(4) above, but who present an equivalent combination of familiarity with abatement activities and demonstrated competence.
- (d) An applicant denied a certificate on any grounds other than failure to complete a certificate application or failure to meet the minimum requirements set forth in these rules may request a hearing before the commissioner or his/her designee to contest said denial by submitting a written request for such hearing within ten days of receipt of denial.

- **§1-15** Renewal of Asbestos Handler Supervisor Certificate. (a) The supervisor shall apply for renewal of the certificate at least 60 days prior to the date of its expiration.
 - (b) The supervisor shall submit the following items for renewal:
 - (1) A completed application provided by the department accompanied by a fee of \$100; and
 - (2) Documentation of successful completion within the prior 12 months of a NYSDOH-approved Asbestos Handler Supervisor Refresher training course.
- (c) An applicant denied a certificate on any grounds other than failure to complete a certificate application or failure to meet the minimum requirements set forth in these rules may request a hearing before the commissioner or his/her designee to contest said denial by submitting a written request for such hearing within ten days of receipt of denial.
- (d) In the event that an asbestos handler supervisor certificate is lost or stolen, the certificate holder must immediately notify the department. An application for a replacement shall be made in writing and shall include a notarized statement that the certificate was lost or stolen, a statement that the applicant understands that submittal of a false statement shall subject him or her to penalties and other remedies under the law, and a fee of \$50.
- **§1-16 Asbestos Investigator Certificate.** (a) (1) No individual shall engage in building survey and hazard assessment for asbestos unless that individual is certified as an asbestos investigator by the department.
 - (2) A non-certified individual may participate in an asbestos survey being conducted by a NYC certified investigator only if such individual works in the presence of the investigator and under his/her direct and continuing supervision.
 - (3) The investigator shall assume that some or all of the areas investigated contain ACM, and for each area that is not assumed to contain ACM, collect and submit for analysis bulk samples in accordance with §§1-36, 1-37 and 1-44 and EPA publications 560/5-85-024 and 560/5-85-030A, and 40 CFR Part 763.86.
- (b) The department shall qualify applicants to be asbestos investigators. The applicant shall satisfy one of the following five sets of conditions:
 - (1) A registered design professional, a certified industrial hygienist or a certified safety professional shall submit a copy of licensing credentials or certification.
 - (2) A graduate from an accredited college or university possessing a doctorate or master's degree in architecture, engineering, environmental science, environmental health science, occupational health and safety, industrial hygiene or related environmental science shall submit a copy of the degree and documentation of six months post-graduate experience in building survey/hazard assessment for asbestos.

- (3) A graduate from an accredited college or university possessing a bachelor's degree in architecture, engineering, environmental science, environmental health science, occupational health and safety, industrial hygiene or a related environmental science shall submit a copy of the degree and documentation of one year post-graduate experience in building survey/hazard assessment for asbestos.
- (4) A graduate from an accredited college or university possessing an associate's degree in architecture, engineering technology, environmental health, public health, industrial health, applied science and technology or a related environmental science shall submit a copy of the degree and documentation of one year post-graduate experience in building survey/hazard assessment for asbestos and an additional two years of building survey-related experience.
- (5) An individual with extensive experience in asbestos investigation on a professional level shall submit documentation demonstrating two years of experience in building survey/hazard assessment for asbestos and an additional three years of other building survey-related experience.
- (c) The department shall issue an asbestos investigator certificate in the form of a photo identification card which shall be valid for two years from the date of issuance to qualified applicants who submit the following:
 - (1) A completed application provided by the Department accompanied by a fee of two hundred fifty dollars (\$250); and
 - (2) Documentation of successful completion within the prior 12 months of a New York State Restricted Asbestos Handler-III Inspector Training course, and a passing grade on the required investigator training course; and
 - (3) Documentation of a medical examination performed by a physician within the prior 12 months, which shall include at a minimum a pulmonary function test, evaluation of a recent chest x-ray and a physician's recommendation as to whether the applicant is able to wear a respirator in the performance of his/her job; and
 - (4) Documentation of a qualitative or quantitative fit test performed within the prior three months, which shall include brand name and type of respirator, date and location of test, and the signature of the industrial hygienist administering the test.
 - (i) Qualitative fit test may be used only for fit testing of half-mask negative pressure respirators.
 - (ii) Quantitative fit test shall be performed on all full-face negative pressure respirators.
 - (d) Applicant shall achieve a passing grade on a departmental examination.

- (e) Under special circumstances the department may consider applicants who submit additional credentials which are not identical to the categories specified in subdivision (b) (1) through (5) above.
- (f) An applicant denied a certificate on any grounds other than failure to complete a certificate application or failure to meet the minimum requirements set forth in these rules may request a hearing before the commissioner or his/her designee to contest said denial by submitting a written request for such hearing within ten days of receipt of denial.
- (g) A person who possesses an asbestos investigator certificate shall be responsible for the proper execution of his or her duties. Unprofessional conduct is prohibited. Unprofessional conduct shall include but is not limited to:
 - (1) Failing to comply with the provisions of Federal, State, or local laws, rules or regulations.
 - (2) Making or filing a false report, or failing to file a report required by Federal, State, or local laws, rules, or regulations.
 - (3) Delegating professional responsibilities to a person who is not qualified to perform them.
- (h) *Investigator's seal requirement*. (1) No NYC-certified asbestos investigator shall submit any plan or report to any client or any city, state, or federal agency that does not have the investigator's seal and signature affixed to it. Photocopies of the seal and signature are not acceptable.
 - (2) Seals used by certified asbestos investigators shall be circular in shape, approximately one and three quarter inches in diameter, with three concentric circles. The inner circle shall contain an accurate representation of the great seal of the City of New York. The legend at the top of the outer band shall read "CITY OF NEW YORK" and at the bottom "CERTIFIED ASBESTOS INVESTIGATOR". In the inner circle above the great seal of the City of New York shall be shown the name of the certified asbestos investigator.
 - (3) Any plan or report submitted without the investigator's seal and signature shall be considered invalid.
- **§1-17 Renewal of Asbestos Investigator Certificate.** (a) The investigator shall apply for renewal of the certificate at least 60 days prior to the date of its expiration.
 - (b) The investigator shall submit the following items for renewal:
 - (1) A completed application provided by the Department accompanied by a fee of \$250 payable to the Department; and
 - (2) Documentation of successful completion within the prior 12 months of a NYSDOH-approved Asbestos Inspector Refresher course; and

- (3) Documentation of a medical examination performed by a physician within the prior 12 months, which shall include at a minimum a pulmonary function test, evaluation of a recent chest x-ray and a physician's recommendation as to whether the applicant is able to wear a respirator in the performance of his/her job; and
- (4) Documentation of a qualitative or quantitative fit test performed within the prior three months, which shall include brand name and type of respirator, date and location of test, and the signature of the industrial hygienist administering the test.
 - (i) Qualitative fit test may be used only for fit testing of half-mask negative pressure respirators.
 - (ii) Quantitative fit test shall be performed on all full-face negative pressure respirators.
- (c) An applicant denied a certificate on any grounds other than failure to complete a certificate application or failure to meet the minimum requirements set forth in these rules may request a hearing before the commissioner or his/her designee to contest said denial by submitting a written request for such hearing within ten days of receipt of denial.
- (d) In the event that an asbestos investigator certificate is lost or stolen, the certificate holder must immediately notify the department. An application for a replacement shall be made in writing and shall include a notarized statement that the certificate was lost or stolen, a statement that the applicant understands that submittal of a false statement shall subject him or her to penalties and other remedies under the law, and a fee of \$50.

Subchapter C

Notifications, Permitting and Recordkeeping

- **§1-21 Size and Scope of Asbestos Project Projects Requiring Certification to the Department of Buildings §1-22 §1-23 Alterations/Renovations/Modifications §1-24** Reserved **§1-25 Asbestos Project Notifications §1-26 Asbestos Abatement Permits §1-27 Emergency Asbestos Project Notification §1-28 Record Keeping Requirements for Investigators §1-29 Maintenance of Project Record and Project Summary**
- §1-21 Size and Scope of Asbestos Project. (a) For the purpose of determining whether there has been compliance with any reporting or filing requirement established in §§1-22 through 1-27, the size and scope of the overall project shall control, with particular reference to the total amount of asbestos-containing material which will be disturbed. Such requirements may not lawfully be avoided or lessened through the performance of work in incremental or piecemeal fashion.

- (b) When alternative calculations (i.e., linear feet and square feet) of the size and scope of an asbestos project result in that project coming within the definition of more than one subclassification of asbestos project, the calculation with the higher absolute number shall determine the sub-classification of asbestos project procedures to be followed.
- (c) For the purpose of §§1-21 through 1-27, the term "work" shall be understood as in the common construction usage, i.e. not specifically related to asbestos abatement activities.
- **§1-22 Projects Requiring Certification to the Department of Buildings.** (a) This section shall apply to applications for the following projects requiring permits to be issued by the Department of Buildings:
 - (1) Full demolitions.
 - (2) Alterations, renovations, or modifications.
 - (3) Plumbing work, except that applications for limited plumbing alterations shall be subject to this section only when the application is for the installation, alteration, or removal of fuel-burning equipment.
- (b) In accordance with section 28-106.1 of the Administrative Code, the building owner or his/her authorized agent shall submit one of the following certifications to the Department of Buildings except as set forth below:
 - (1) Asbestos Assessment Report. If the building (or portions thereof) affected by the work are free of asbestos-containing material or the amount of ACM to be abated constitutes a minor project, an asbestos assessment report (Form ACP-5) completed, signed, and sealed by a DEP-certified asbestos investigator, along with a fee of \$47.00 shall be submitted to DEP prior to construction document approval and to any amendment of the construction document approval which increases the scope of the project to include (a) work area(s) not previously covered.
 - (2) Asbestos Exemption Certification. If the work is exempt pursuant to section 1-23(b) of these rules, an asbestos exemption certification (Form ASB4) completed, signed, and sealed by the applicant for a DOB permit shall be submitted to DOB prior to construction document approval and to any amendment of the construction document approval which increases the scope of the project to include (a) work area(s) not previously covered.
 - (3) Asbestos Project Completion Form. If an asbestos project has been performed and satisfactorily completed in accordance with these rules, a copy of the asbestos project completion form issued to the building owner or its authorized representative by DEP shall be submitted to DOB prior to the issuance of a DOB permit and to any amendment of the underlying construction document approval which increases the scope of the project to include (a) work area(s) not previously covered.

- (4) An Asbestos Project Conditional Completion Form. If an asbestos project has been performed but would be subject to the procedures of section 1-26(c)(2)(ii), a copy of the asbestos project conditional completion form issued to the building owner or its authorized representative by DEP shall be submitted to DOB prior to the issuance of a DOB permit and to any amendment of the underlying construction document approval which increases the scope of the project to include (a) work area(s) not previously covered.
- **§1-23 Alterations/Renovations/Modifications.** (a) As early as possible before an alteration, renovation, modification, demolition, or plumbing work takes place, or changes in such work occur, the building owner shall be responsible for having an asbestos survey performed by a DEP-certified asbestos investigator to determine the absence or presence of asbestos-containing material which may be disturbed during the course of the work. The owner of the building or authorized agent shall comply with the notification requirements of section 1-25 regarding asbestos-containing material.
- (b) Asbestos Exemption Certification (ASB4 Form). Where the work to be performed requires a permit to be issued by the Department of Buildings, an asbestos exemption certification (ASB4 Form) may be submitted to the Department of Buildings in accordance with section 1-22(b)(2) of these rules where the applicant for construction document approval certifies that:
 - (1) the permit sought does not involve the performance of any physical work, such as permits for zoning lot subdivisions, zoning lot reapportionment, or changes in the certificate of occupancy; or
 - (2) no existing building materials are to be disturbed by the proposed work; or
 - (3) the activities being performed include work on one of the following:

Awnings

Cranes not anchored to building or structure

Emergency power not involving hard wiring, e.g. battery packs

Exterior concrete work (e.g. sidewalks, curb cuts, traffic islands) except if waterproofing compound is present

Exterior scaffolding not anchored to building or structure

Exterior trenching and drainage

Ground-mounted flagpoles

New storefronts in existing masonry openings (no disturbance of existing building)

Radio antennas (free-standing towers)

Relocating free-standing parking lot sheds

Replacing rooftop air conditioning (no modification of ductwork or disturbance of building)

Roadway asphalt

Sealing unsafe or abandoned buildings with cinderblock and mortar

Sidewalk sheds, bridges, fences, elevators, hoists and café signs (no penetration of building materials)

Street furniture, e.g. candy or newsstands, bus shelters, kiosks

Installation of new outdoor swimming pool

Free-standing tents

Erection of temporary structures (e.g. trailers) with electric/water lines only

- (c) Asbestos Assessment Report (ACP-5 Form). If, after a survey performed by a DEP-certified asbestos investigator, it is determined that the building (or portion thereof) affected by the work is free of asbestos-containing material or the amount of ACM to be abated constitutes a minor project, said asbestos investigator shall complete, sign, and affix his or her seal to the asbestos assessment report (ACP-5 Form) which shall be submitted with a fee of \$47.00 to DEP in accordance with section 1-22(b)(1) of these rules.
- (d) Asbestos Project Completion Form. Where the work to be performed constitutes an asbestos project, an asbestos project notification (ACP-7 Form) shall be submitted to DEP in accordance with the provisions of section 1-25 of these rules. Upon completion of the asbestos project and submission of all required documentation to DEP, DEP shall issue an asbestos project completion form to the building owner or its authorized representative.

§1-24 Reserved

§1-25 Asbestos Project Notifications.

- (a) This section shall apply to the following categories:
 - (1) Removal, encapsulation, enclosure or replacement of asbestos-containing materials (including insulation); and
 - (2) Work in or into plenum spaces of existing buildings (e.g. electrical, ventilation, cable, sheet metal work, etc.); and
 - (3) Removal of asbestos-covered structures and equipment such as boilers, pipes, etc.; and
 - (4) Other miscellaneous activities not previously exempted.

- (b) Work constituting a minor project. If the work is a minor project, no notification or fee payable to the department shall be required, unless notification and fees are otherwise required by these regulations.
- (c) Asbestos Projects. If the cumulative total of all surfaces affected by the work is an asbestos project, the department's asbestos project notification (ACP-7 Form) completed by the building owner or authorized agent, and listing each work area within the building separately, shall be submitted directly to the department one week in advance of the start of the work along with a filing fee in the following amounts:
 - (1) For work which will disturb more than 25 linear feet but less than 100 linear feet, or more than 10 square feet but less than 50 square feet, of asbestos-containing material, the fee shall be \$200.
 - (2) For work which will disturb at least 100 linear feet and less than 260 linear feet, or at least 50 square feet and less than 160 square feet, of asbestos-containing material, the fee shall be \$400.
 - (3) For work which will disturb at least 260 linear feet and less than 1,000 linear feet, or at least 160 square feet and less than 1,000 square feet, of asbestos-containing material, the fee shall be \$800.
 - (4) For work which will disturb 1,000 linear feet or more, or 1,000 square feet or more, of asbestos-containing materials, the fee shall be \$1,200.
- (d) Modification of or deviation from the information provided in any notification submitted to the DEP under this section shall immediately be reported in writing directly to DEP if the change refers to the identity of the building owner or ACM removal contractor or the air monitoring firm; or the amount of ACM to be removed; or the dates of the project; or the specific project location. A notification may be modified no more than twice, however, a modification related to the extension or reinstatement of an asbestos abatement permit shall not count towards this total. A modification is valid only if it is received by the DEP prior to the previously filed date of completion, except for start date changes which must be received by the original start date. Thereafter, a new notification submitted directly to the department will be required. Additional work, identified after the completion of the work indicated on the asbestos project notification and successful clearance air monitoring, shall require a new notification. A notification to DEP shall be valid for one year from the date of original filing.
- § 1-26 Asbestos Abatement Permit. (a) *Permit required*. An asbestos abatement permit authorizing the performance of construction work shall be required for asbestos projects involving one or more of the following activities:
 - (1) Obstruction of an exit door leading to an exit stair or the exterior of the building;
 - (2) Obstruction of an exterior fire escape or access to that fire escape;
 - (3) Obstruction of a fire-rated corridor leading to an exit door;

- (4) Removal of handrails in an exit stair or ramp within the work area;
- (5) Removal or dismantling of any fire alarm system component including any fire alarm-initiating device (e.g., smoke detectors, manual pull station) within the work area;
- (6) Removal or dismantling of any exit sign, including directional signs, or any component of the exit lighting system, including photoluminescent exit path markings within the work area;
- (7) Removal or dismantling of any part of a sprinkler system including piping or sprinkler heads within the work area;
- (8) Removal or dismantling of any part of a standpipe system including fire pumps or valves within the work area;
- (9) Any abatement activity to be performed within a building concurrently with the full demolition of such building or concurrently with the removal of one or more stories of such building;
- (10) Removal of any non-load bearing / non-fire-resistance rated wall (greater than 45 square feet or 50 per cent of a given wall) within the work area;
- (11) Any plumbing work other than the repair or replacement of plumbing fixtures within the work area;
- (12) Removal of any fire-resistance rated portions of a wall, ceiling, floor, door, corridor, partition, or structural element enclosure including spray-on fire-resistance rated materials within the work area;
- (13) Removal of any fire damper, smoke damper, firestopping material, fireblocking, or draft stopping within fire-resistance rated assemblies or within concealed spaces;

(b) Work Place Safety Plan.

- (1) Plan required. For projects requiring an asbestos abatement permit due to one or more of the activities listed in (a)(1-9), the building owner or its authorized representative shall submit, together with the asbestos project notification, a work place safety plan (WPSP) and any other applicable construction documents, which shall be prepared by a registered design professional, and a permit fee as specified in subsection (g).
- (2) Plan not required. For projects requiring an asbestos abatement permit due to one or more of the activities listed in (a)(10-13), the building owner or its authorized representative shall submit, together with the asbestos project notification, all applicable asbestos abatement permit construction documents, and a permit fee as specified in subsection (g).

- (i) If the WPSP is being submitted pursuant to subsection (a)(9), it shall also set forth the sequencing of the proposed work. The WPSP shall not be approved unless it provides for a buffer of four floors or an adequate buffer as determined by the commissioner between the abatement and the demolition or floor removal work.
- (3) Plan requirements. The WPSP shall include, but not be limited to, the following items, depending on the size and scope of the asbestos project:
 - i. Floor plans showing the locations of all asbestos project work areas in the building.
 - ii. Floor plans indicating the locations of any components of the fire alarm system which have been deactivated, and setting forth mitigation measures to be implemented for the duration of the project.
 - iii. Floor plans indicating the locations of obstructed or removed exit signage and lighting and setting forth mitigation measures to be implemented for the duration of the project.
 - iv. Floor plans indicating the locations of any obstructed means of egress or required exit and setting forth mitigation measures to be implemented for the duration of the project.
 - v. Floor plans or riser diagrams indicating the locations of any disengaged or removed components of the fire protection system and setting forth mitigation measures to be undertaken for the duration of the project.
 - vi. A written description of all measures taken to mitigate compromised fire protection systems or means of egress, including but not limited to surveillance by a fire watch and an action plan setting forth procedures to be taken for the safety of building occupants in the event of an emergency.
 - vii. If the asbestos project is being performed in a building where any dwelling unit is to be occupied for the duration of the permit, the WPSP shall include a tenant protection plan as required by chapter 1 of Title 28 of the Administrative Code.
 - viii. A list of all non asbestos contractors who will perform work on the project.
- (4) Approval. The documents submitted pursuant to subsection (b) will be reviewed by DEP's asbestos technical review unit (A-TRU) and by any other relevant city agencies. Upon approval by A-TRU, DEP will issue an asbestos abatement permit to the building owner or its authorized representative.
- (c) *Inspections required.* (1) All inspections required pursuant to Title 28 of the Administrative Code, including but not limited to special inspections required by Chapter 17 of the Building Code, shall be performed by a registered design professional who is independent of the abatement contractor.
 - (2) A final inspection shall be performed by a registered design professional after all work authorized by the asbestos abatement permit is completed. The person

performing the inspection shall note all failures to comply with the provisions of the Building Code or approved asbestos abatement permit and shall promptly notify the owner in writing. All defects noted in such inspection shall be corrected.

The final inspection report shall either:

(i) confirm:

- (A) that the construction work is complete, including the reinstallation or reactivation of any building fire safety or life safety component; and
- (B) that any defects previously noted have been corrected; and
- (C) that all required inspections were performed; and
- (D) that the work is in substantial compliance with the approved asbestos abatement permit construction documents, the Building Code, and other applicable laws and rules; or

(ii) confirm:

- (A) that the construction work does not return the building (or portion thereof) affected by the abatement project to a condition compliant with the building code and other applicable laws and rules, but that the registered design professional has reviewed an application for asbestos abatement permit construction documents approval that has been approved by the department of buildings, and the subsequent scope of work as approved will, upon completion, render all areas affected by the asbestos project in full compliance with the building code and all applicable laws and rules; and
- (B) that any defects previously noted that are not addressed by the subsequent scope of work as approved by the department of buildings, have been corrected; and
- (C) that all required inspections that are not addressed by the subsequent scope of work as approved by the department of buildings were performed; and
- (D) that all completed work pursuant to an asbestos abatement permit is in substantial compliance with the approved asbestos abatement permit construction documents.

- (3) Final inspection reports shall be filed with DEP on A-TR1 form. Records of final inspections made by registered design professionals shall be maintained by such persons for a period of six years after final inspection or for such other period as the commissioner shall require and shall be made available to the department upon request.
- (d) *Duration of Permit*. An asbestos abatement permit shall expire upon the earlier of one year from the date of issuance or when terminated pursuant to either of the following:
 - (1) The holder of an asbestos abatement permit submits a final inspection report pursuant to (c)(2)(i).
 - (2) The holder of an asbestos abatement permit submits a final inspection report pursuant to (c)(2)(ii) and obtains a Department of Buildings permit for work which, when completed, will render all areas affected by the project fully compliant with the building code and all other applicable rules and laws.
- (e) Failure to terminate asbestos abatement permit within year. (1) Failure to terminate an asbestos abatement permit pursuant to subsection (d) within a year from the date of issuance of said permit shall be a violation subject to fine unless the applicant obtains a renewal pursuant to paragraph (2) of this subdivision. Each 60-day period during which such violation continues to occur constitutes a separate offense that may be subject to a separate fine.
- (2) The holder of an asbestos abatement permit may extend the term of such permit for additional six month periods upon the submission, within 30 days before the expiration of said permit, of an amendment on a form prescribed by DEP and the payment of a fee in the same amount as the fee paid for the original permit.
- (3) If the holder of an asbestos abatement permit fails to terminate an asbestos abatement permit within a year from the date of issuance, the holder shall maintain the work area in a safe manner including but not limited to any mitigation measures set forth in the WPSP and shall not perform work unless the holder reinstates the permit upon submission of an amendment on the forms prescribed by the Department and the payment of a new fee in the same amount as the fee paid for the original permit. Such reinstatement shall be valid for a period of six months from issuance. If the asbestos abatement permit is not terminated during a six-month reinstatement period, the holder of a reinstated asbestos abatement permit must submit a subsequent amendment and fee to reinstate the permit for another six-month period.
- (f) *Insurance*. Entities other than NYSDOL-licensed asbestos contractors performing work pursuant to an asbestos abatement permit which does not involve the disturbance of asbestos-containing materials shall maintain insurance of the same type and amount as would be required if the entity were working pursuant to a permit issued by the Department of Buildings.
- (g) *Permit fee*. The WPSP, asbestos abatement permit construction documents, as applicable, shall be accompanied by a filing fee, as follows:

<u>Project Size</u>	<u>Fee</u>
Small projects up to 99 linear feet or 49 square feet of ACM	\$100
100 to 259 linear feet or 50 to 159 square feet of ACM	\$300
Large projects up to 1000 square/linear feet of ACM	\$500
1000 to 4999 square/linear feet of ACM	\$700
5000 to 9999 square/linear feet of ACM	\$1100
10,000 or more square/linear feet of ACM	\$1300

- (h) Work covered by the asbestos abatement permit shall not commence until said permit is issued.
- **§1-27 Emergency Asbestos Project Notification.** (a) An emergency asbestos project involves the removal, enclosure or encapsulation of asbestos-containing material that was not planned but is undertaken when sudden unexpected event(s) result in a situation in which any delay in abatement would pose an immediate danger to public safety and health.
- (b) When such an emergency asbestos project occurs, immediate telephone notification shall be provided to DEP's asbestos control program. Telephone notification shall include:
 - (1) Name, affiliation and telephone number of caller;
 - (2) Nature of the emergency;
 - (3) Type of asbestos work to be performed and the quantity of ACM to be abated;
 - (4) Exact location of the project including street address and borough;
 - (5) Name, address, and telephone number of the asbestos abatement contractor and the air monitoring company; and
 - (6) Starting and projected completion dates.
 - (7) Such other factors as the department may determine are relevant for that project.
- (c) An asbestos project notification (ACP-7 Form) shall be submitted to DEP in accordance with the provisions of section 1-25 of these rules as soon as possible, but not later than 48 hours after the project begins. In such cases, the ACP-7 Form shall be accompanied by a cover letter including the following information:
 - (1) that the project is an emergency asbestos project;
 - (2) the nature of the emergency;
 - (3) the DEP emergency control number issued at the time of the telephone notification; and
 - (4) a description of the scope of work.

With respect to projects commenced under this section, the department, based on inspection by the department and other relevant agencies, may exempt the emergency project from the requirements of section 1-26. Any such exemption will be confirmed in writing by the department.

- **§1-28 Record Keeping Requirements for Investigators.** (a) The asbestos investigator shall maintain a permanent record as required under this section for every building survey/hazard assessment for asbestos that is conducted pursuant to or submitted in accordance with §§1-22 through 1-27 of this chapter.
- (b) For each building survey/hazard assessment conducted prior to preparation of either the asbestos project notification (ACP-7) or asbestos assessment report (ACP-5), the investigator shall compile a record which shall include at a minimum:
 - (1) A survey report that reflects the condition of the work area at the time of the investigator's inspection. The report is to include, at a minimum, the building's address and the name and address of the building owner, as well as the locations, quantities, and condition of all building materials in the affected portion(s) of the building or structure relative to the ACM contained therein; the building or structure's address; and the name and address of the building owner; and
 - (2) A blueprint, diagram, drawing, or written description of each building or portion thereof inspected by the investigator that identifies clearly each location and approximate linear or square footage of any area where material was sampled for ACM, and the exact locations where bulk samples were collected, the date of collection, and location of any areas assumed to have ACM; and
 - (3) The printed name and signature of any and all persons who collect bulk samples for the purpose of determining the presence of ACM, a copy of the current DEP asbestos handler certificate and NYSDOL asbestos handler certificate of each such person, the name of the firm performing the survey and a copy of its current NYSDOL asbestos handling license, the name and address of the laboratory analyzing the samples, the date of analysis, the results of the analysis, the method of analysis and the name and signature of the person performing the analysis; and
 - (4) A detailed written description of any proposed demolition, renovation, alteration or modification work to be performed, including the techniques to be used and a description of affected facility components; and
 - (5) A chain of custody for all bulk samples collected as part of the survey.
- (c) The investigator shall indicate in each record all instances in which work was performed by a non-certified individual pursuant to §1-16(a)(2), and shall include such individual's name, address, telephone number, and a specific description of all activities performed by such individual.
 - (d) The investigator shall maintain these records for thirty (30) years.
- (e) The investigator shall make these records available during normal business hours without cost or restriction for inspection by a representative of the Department.

- §1-29 Maintenance of Project Record and Project Summary (a) A project record shall be maintained for all small and large asbestos projects. During the project, the project record shall be kept on site at all times and may be maintained by the building owner or his authorized representative, which may be the asbestos abatement contractor or the air monitoring company. Upon completion of the project, the project record shall be maintained by the building owner. The project record shall be produced upon verbal or written request by any DEP inspector. Upon transfer of ownership of the building, all project records for past asbestos projects shall be turned over to the new owner. The project record shall consist of:
 - (1) Copies of licenses of all contractors involved in the project.
 - (2) Copies of DEP and NYSDOL supervisor and handler certificates for all workers engaged in the project;
 - (3) Copies of all project notifications and reports filed with DEP and NYSDOL for the project, with any amendments or variances;
 - (4) Copies of all asbestos abatement permits, including associated approved plans and work place safety plan;
 - (5) A copy of the air sampling log and all air sampling results;
 - (6) A copy of the abatement contractor's daily log book;
 - (7) All data related to bulk sampling including the results of any asbestos surveys performed by an asbestos investigator;
 - (8) Copies of all waste manifests;
 - (9) A copy of all project monitor's reports.
- (b) In addition to the project record required in subsection (a), the asbestos abatement contractor shall maintain, for at least thirty (30) years after the end of the project, a project summary for each asbestos project in which they engage, consisting of the following:
 - (1) Name, address, and DEP certificate number of all individuals who worked on the project;
 - (2) Location and general description of the project;
 - (3) Amount of ACM abated;
 - (4) Start and completion dates;
 - (5) Name, address, and NYSDOL asbestos handling license number of the air monitoring company;

- (6) Name, address, and ELAP registration number of the laboratory used for air sample analysis;
- (7) Name and address of the site used for disposal of the ACM waste generated by the project;
- (8) Name and address of the asbestos hauler;
- (9) Copy of the project log.
- (c) The building owner or contractor, as applicable, must make the project record or project summary required by this section available for inspection by DEP within 72 hours of request, except that during the project the project record must be made available immediately upon request.

Subchapter D

Air and Bulk Sampling, Monitoring and Analysis

- Part 1 Applicability
 - **2** Personnel Qualifications and Equipment Specifications
 - **3 Monitoring Procedures**

Part 1 Applicability

§1-31 Performance of Air and Bulk Sampling, Monitoring and Analysis

§1-31 Performance of Air and Bulk Sampling, Monitoring and Analysis. Air sampling, monitoring, and analysis on asbestos projects, and bulk sampling and analysis to determine asbestos content, shall be performed in accordance with the provisions of the following §§1-31 through 1-45 inclusive.

Part 2

Personnel Qualifications and Equipment Specifications

- §1-36 Persons Qualified to Perform Sampling and Analysis
- §1-37 Sampling Equipment Requirements

§1-36 Persons Qualified to Perform Sampling and Analysis.

- (a) Sampling and analysis shall be performed by:
 - (1) a third party who is contracted by the building owner, holds a current NYSDOL asbestos handling license, and is completely independent of all parties involved in the asbestos project. The third party who conducts air sampling on an asbestos project shall not be a subcontractor of the abatement contractor, and shall not have any business, personal, or other relationship with the abatement contractor. The building owner shall select and hire the air monitoring firm without recommendation or reference from the abatement contractor. It shall be a violation of this subsection, chargeable against the abatement contractor, the air monitoring firm, and the building owner, for an air monitoring firm to conduct air monitoring on an asbestos project where there is a business or personal relationship between the abatement contractor and the air monitoring firm. It shall be considered prima facie evidence of a business or personal relationship between an abatement contractor and an air monitoring firm when the same firm performs air monitoring on all or virtually all of a given abatement contractor's projects. The person who conducts sampling shall be currently certified as a New York State Asbestos Project Air Sampling Technician when performing air sampling. Failure to produce the certificate upon request shall be a violation chargeable against the individual conducting the sampling; or
 - (2) Sampling and analysis staff which may not be independent of the building owner but are independent of the abatement contractor involved in the asbestos project, but only if such staff:
 - (i) performs in conjunction with a third party quality assurance program in which 10 percent of the samples, except for bulk samples initially found to contain ACM, from each project are randomly selected and will be analyzed by both entities; and
 - (ii) in the case of air sampling, possesses valid New York State Asbestos Project Air Sampling Technician Certification.
 - (3) Sampling and analysis staff of a public service corporation with respect to asbestos projects that involve electric, steam or gas generation, distribution or transmission facilities provided that the requirements of subparagraphs (i) and (ii) of paragraph 2 of this section are complied with.

- (4) Only persons certified by the Department as asbestos investigators or by New York State Department of Labor as Asbestos Inspectors may select and collect bulk samples for analysis.
- (b) An air sampling technician shall be present at the work site to observe and maintain air sampling equipment for the duration of the air sample collection.
- (c) Bulk sample analysis (PLM or gravimetric reduction and TEM analysis) shall be performed by laboratories with the appropriate accreditation in the ELAP.
- (d) Air Sample Analysis (PCM) shall be performed by laboratories with the following qualifications:
 - (1) Successful completion by the laboratory's active analysts of the NIOSH 582 training course which outlines the NIOSH 7400 method; and
 - (2) Analysts with skills in the appropriate methodology and proficiency in the NIOSH PAT Program for PCM analysis; and
 - (3) Accreditation in ELAP.
- (e) Air Sample Analysis (TEM) shall be performed by analysts who possess skills in TEM analysis, are accredited in ELAP, and participate in an in-house quality assurance program using the National Institute of Standards and Technology (NIST SRM 1876 b) or traceable standard.

§1-37 Sampling Equipment Requirements.

- (a) *Bulk sampling requirements*. (1) Bulk samples shall be taken by whatever method minimizes the potential for fiber release.
 - (2) Any material which remains exposed as a result of the sampling procedure shall be sealed.
- (b) Area air sampling equipment for Phase Contrast Microscopy (PCM) shall be utilized in accordance with the equipment and sampling procedures specified within the NIOSH 7400 Method modified for area sampling.
- (c) Area air sampling equipment for Transmission Electron Microscopy (TEM) shall be utilized in accordance with the sampling procedures specified within 40 CFR Part 763, Subpart E, Appendix A Section II Mandatory Transmission Electron Microscopy Method, Subsection B-Sampling.
- (d) Air sampling pumps shall have a constant controlled flow and shall have the flow rate capacity to perform sampling as specified in these rules. A properly calibrated rotometer shall be used to check the flow rate. A rotometer shall be available at the work place for the duration of air sample collection. Primary and secondary calibration devices shall be calibrated as per NYSDOH ELAP requirements.

- (e) Sampling pumps, cassettes, and tubing shall be checked before, during and after use. The sampling assembly shall be checked for leaks and occlusions.
- (f) A project air sampling log shall be created and maintained in a bound notebook by the air monitoring company. The project air sampling log shall be available at the work site. A copy of the log shall be submitted to the department within 24 hours of request. The log shall contain the following information for all area air samples collected on the asbestos project:
 - (1) Name of the firm and the certified air sampling technician performing the project air sampling, per work shift or day for all area air samples collected.
 - (2) Dates of project air sample collection, per work shift or day of area air samples, with appropriate reference to the work area to which the air samples apply.
 - (3) Sample location sketch, identifying all project air sample locations, per work shift or day of area air samples.
 - (4) Flow rate primary or secondary calibration device identification number, method of flow rate primary or secondary device calibration and date of last calibration, per work shift or day of area air samples.
 - (5) Flow rate of sampling pumps with pre and post calibration listed for each area air sample collected.

Part 3 Monitoring Procedures

- **§1-41 Air Sampling Schedule**
- §1-42 Monitoring Requirements
- §1-43 Post-Abatement Clearance Air Monitoring
- §1-44 Analysis and Reporting Results
- §1-45 Action Criteria

§1-41 Air Sampling Schedule. (a) At a minimum, air sampling shall be conducted in accordance with the following schedule:

Abatement During Activity **Pre-Abatement** Abatement **Post-Abatement** Equal to or Greater than PCM **PCM** TEM 10,000 ft.² or 10,000 linear ft. of ACM per work area

Less than 10,000 ft.² or 10,000 linear ft. of ACM

PCM

PCM

PCM

			During	Post
		Pre-Abatement	Abatement	Abatement
	Large Asbestos Projects			
1.	Full Containment	10	5	10
2.	Glovebag inside Tent	5 ^a	5 ^a	5 ^a
3.	Exterior Foam and Vertical Surfaces		5°	5 ^d
4.	Interior Foam	10	5 ^c	10 ^d
	Small Asbestos Projects			
1.	Full Containment	6	3	6
2.	Glovebag inside Tent	3 ^b	3 ^b	3 ^b
3.	Tent	3 ^b	3 ^b	3 ^b
4.	Exterior Foam and Vertical Surfaces		3°	3 ^d
5.	Interior Foam	6	3 ^c	6 ^d
	Minor Projects			
1.	Glovebag inside Tent			1 ^d
2.	Tent			1 ^d
3.	Exterior Foam and Vertical Surfaces			1 ^d
4.	Interior Foam			1 ^d

if more than three (3) tents then two (2) samples required per enclosure. if more than three (3) tents then one (1) sample required per enclosure.

visible emissions are detected during the project

Note: TEM is acceptable wherever PCM is required.

samples shall be taken within the work area(s).

area sampling is required only if:

during-abatement area sampling results exceeded 0.01 f/cc or the pre-abatement area sampling result(s) for interior projects where applicable.

work area to be reoccupied is an interior space at a school, healthcare, or daycare facility.

- (b) *Pre-Abatement*. Prior to commencement of abatement activities, the number of samples specified below shall be taken during normal occupancy activities and circumstances at the work site. Samples shall be taken at the following locations:
 - (1) For large full-containment and interior foam method asbestos projects, a minimum of five samples inside and five samples outside the proposed work area.
 - (2) For small full-containment and interior foam method asbestos projects, a minimum of three samples inside and three outside the proposed work area.
 - (3) For large and small asbestos projects employing the glovebag procedure within a tent, a minimum of five and three samples, respectively, or two samples per enclosure if more than three enclosures.
 - (4) For small asbestos projects solely employing tent procedure, a minimum of three samples inside each proposed work area, or two samples per enclosure if more than three enclosures.
 - (5) For all exterior projects (foam or vertical surface), no pre-abatement sampling is required.
- (c) *During abatement*. Frequency and duration of the air sampling during abatement shall be representative of the actual conditions during the abatement. Area sampling shall be conducted daily and continuously during a work shift. If more than one daily work shift is required to accomplish the work, area sampling shall be performed on each work shift. Area sampling is not required on days when there are no abatement activities. For project air samples collected during the abatement, the period of time permitted between completion of air sample collection and receipt of results on the job site shall not exceed 48 hours. The following minimum schedule of samples shall be required during the work shift.
 - (1) For large asbestos projects employing full containment, area air sampling shall be performed at the following locations:
 - (i) Two area samples outside the asbestos project work area in uncontaminated areas of the building, remote from the decontamination facilities.
 - (A) Primary location selection shall be within 10 feet of isolation barriers.
 - (B) Where negative ventilation exhaust ducting runs through uncontaminated building areas, one area sample will be required in these areas to monitor any potential fiber release.
 - (C) Where exhaust tubes have been grouped together in banks of up to five (5) tubes, with each tube exhausting separately and the bank of tubes terminating together at the same controlled area, one area air sample shall be taken.

- (ii) One area sample within five feet of the uncontaminated entrance to each worker decontamination and waste decontamination enclosure system, or parallel worker and waste decontamination system, if applicable; and
- (iii) One area sample within 5 feet of the unobstructed exhaust from a negative pressure ventilation system exhausting indoors but not within a duct.
- (iv)One area sample outside, but within 25 feet of, the building or structure, if the entire building or structure is the work area.
- (2) For large asbestos projects involving interior foam method, area air sampling shall be performed at the following sampling locations:
 - (i) One area sample taken outside the work area within 10 feet of isolation barriers.
 - (ii) One area sample taken within five feet of the uncontaminated entrance to each worker decontamination and waste decontamination enclosure system, or parallel worker and waste decontamination system, if applicable.
 - (iii) One area sample within 5 feet of the unobstructed exhaust from a negative pressure ventilation system exhausting indoors but not within a duct, if applicable.
 - (iv) Three area samples inside the work area.
 - (v) One area sample where the negative ventilation exhaust ducting runs through uncontaminated building areas, if applicable.
- (3) For large asbestos projects involving exterior foam method or removal of ACM from vertical surfaces, a minimum of five continuous area samples shall be taken concurrently with the abatement for each work area using the following minimum requirements:
 - (i) Four area samples inside the work area and remote from the decontamination systems.
 - (ii) One area sample within five feet of the uncontaminated entrance to each worker and waste decontamination enclosure system, or parallel worker and waste decontamination system, if applicable.
 - (iii) One area sample outside the work area within 25 feet of the building or structure, if the entire building or structure is the work area.
 - (iv) One area sample inside the building or structure at the egress point to the work area, if applicable.

- (4) For large asbestos projects employing the glovebag procedure within a tent, a minimum of five continuous air samples shall be taken concurrently with the abatement for each work area, unless there are more than three enclosures, in which case two area samples per enclosure are required.
 - (i) Four area samples taken outside the work area within ten feet of tent enclosure(s).
 - (ii) One area sample taken within five feet of the uncontaminated entrance to each worker and waste decontamination enclosure system, or parallel worker and waste decontamination system, if applicable.
 - (iii) One area sample within five feet of the unobstructed exhaust from a negative pressure ventilation system exhausting indoors, but not within a duct, if applicable.
 - (iv) One area sample where negative ventilation exhaust ducting runs through uncontaminated building areas, if applicable.
- (5) For small asbestos projects employing full containment, a minimum of three continuous area samples shall be taken concurrently with the abatement for each work area at the following locations:
 - (i) Two area samples taken outside the work area within ten feet of the isolation barriers
 - (ii) One area sample within five feet of the uncontaminated entrance to each worker or waste decontamination enclosure system, or parallel worker and waste decontamination system, if applicable.
 - (iii) One area sample within five feet of the unobstructed exhaust from a negative pressure ventilation system exhausting indoors, but not within a duct, if applicable.
 - (iv) One area sample where negative ventilation exhaust ducting runs through an uncontaminated building area, if applicable.
- (6) For small asbestos projects involving the use of foam method on the exterior of a building or the removal of ACM from exterior surfaces, a minimum of three continuous area samples shall be taken concurrently with the abatement for each work area at the following locations:
 - (i) Two area samples inside the work area and remote from the decontamination systems.
 - (ii) One area sample within five feet of the uncontaminated entrance to each worker and waste decontamination enclosure system, or parallel worker and waste decontamination system, if applicable.

- (iii) One area sample inside the building or structure at the egress point to the work area, if applicable.
- (7) For small asbestos projects using the tent procedure (with or without the use of glovebags), a minimum of three area samples shall be taken concurrently with the abatement for each work area unless there are more than two enclosures, in which case one sample per enclosure is required.
 - (i) Two area samples taken outside of the work area within ten feet of the tent.
 - (ii) One area sample within five feet of the uncontaminated entrance to each worker and waste decontamination system, or parallel worker and waste decontamination system, if applicable.
 - (iii) One area sample within five feet of the unobstructed exhaust from a negative pressure ventilation system exhausting indoors, but not within a duct, if applicable.
 - (iv) One area sample where negative ventilation exhaust ducting runs through uncontaminated building areas, if applicable.
- (8) For small asbestos projects employing interior foam procedures, a minimum of three continuous area samples shall be taken concurrently with the abatement for each work area at the following locations:
 - (i) One area samples taken inside the work area.
 - (ii) One area sample taken within five feet of the uncontaminated entrance to each worker and waste decontamination enclosure system, or parallel worker and waste decontamination system, if applicable.
 - (iii) One area sample taken outside the work area within ten feet of the isolation barriers.
 - (iv) One area sample where negative ventilation exhaust ducting runs through uncontaminated building areas, if applicable.
- (d) *Post-abatement*. Post-abatement clearance air monitoring shall include at a minimum the number of area samples specified below, to be taken for each homogeneous work area.
 - (1) For small asbestos projects:
 - (i) involving full containment or interior foam method, three area samples inside and three outside the work area;
 - (ii) involving tent procedure (with or without the use of glovebags), three area samples inside each work area or one area sample inside each tent if there are more than three tents;

- (iii) involving exterior foam method or removal from vertical surfaces, three area samples inside the restricted area beneath and/or immediately adjacent to the work area, only if visible emissions were detected during the project, or abatement area samples exceeded 0.01 f/cc.
- (2) For large asbestos projects,
 - (i) a minimum of five area samples inside and five outside the work area, for projects involving full containment or interior foam method. In addition to the 5 sample minimum, one representative area sample shall be collected both inside and outside the work area for every 5,000 square feet above 25,000 square feet of floor space when ACM has been abated.
 - (ii) a minimum of five area samples inside each tent enclosure where glovebag procedures are being used, or two area samples inside each tent where glovebag procedures are being used if there are more than three tents;
 - (iii) involving exterior foam method or removal from vertical surfaces, five area samples inside the restricted area beneath and/or immediately adjacent to the work area, only if visible emissions were detected during the project, or abatement area samples exceeded 0.01 f/cc.
- (3) When TEM analysis is employed a minimum of 5 samples from outside the work area shall also be collected.
- (4) For minor projects post-abatement clearance air monitoring is not required, unless visible emissions were detected outside the work area and/or levels exceeded 0.01 f/cc during abatement, or the project was conducted inside a school, daycare, or healthcare institution. In such cases, one area sample shall be taken.
- **§1-42 Monitoring Requirements.** Monitoring requirements and procedures for other than post-abatement clearance air monitoring are as follows:
- (a) The sampling zone for indoor air samples shall be representative of the building occupants' breathing zone. However, at no time shall the sampling cassette be placed less than 4 feet from the ground. Air samplers shall be placed so that they are not influenced by unusual air circulation patterns or by the configuration of the space or by each other. Air sampling cassettes shall be mounted upon commercially-available aluminum tripods and shall not be placed within two feet of walls or obstructions such as the corners of rooms or furniture.
- (b) If possible, ambient samplers should be placed about 6 feet above the ground surface in reasonable proximity to the building and away from obstructions and drafts that may unduly affect airflow.

For outdoor samples, if access to electricity and concerns about security dictate a rooftop site, locations near vents and other structures on the roof which would unduly affect airflow shall be avoided.

- (c) Samples shall have a chain of custody record. The project air sampling log required pursuant to section 1-37(f) of these rules does not satisfy the chain of custody requirement.
- (d) In accordance with the above criteria, area samples (see §1-41) shall conform to the following schedule:

Area Samples for Analysis by	Minimum Volume	Flow
PCM 25 mm	560	5 to 15 liters/min.
TEM 25 mm	560	1 to 10 liters/min.
TEM 37 mm	1,250	1 to 10 liters/min.

- (e) For small projects including tent procedures, sampling shall start with the installation of the containment and shall run concurrently with the procedure.
- **§1-43 Post-Abatement Clearance Air Monitoring.** Post-abatement clearance air monitoring requirements are as follows:
- (a) (1) Sampling shall not begin until a visual inspection, conducted by a project monitor who is independent of the abatement contractor and by the asbestos handler supervisor, confirms that all containerized waste has been removed from work and holding areas and there is no visible ACM debris or residue on or about all abated surfaces; and
 - (2) Sampling shall not begin until at least 1 hour after the area is dry from the third cleaning (see §1-112(e)) and no visible pools of water or condensation remain.

For pre-demolition asbestos abatement activity, sampling shall begin 2 hours after the area is dry and no visible pools of water or condensation remain.

- (b) Samplers shall be placed at random around the work area. If the work area contains the number of rooms equivalent to the number of required samples based on floor area, a sampler shall be placed in each room. When the number of rooms is greater than the required number of samples a representative sample of rooms shall be selected.
- (c) The representative samplers placed outside the work area but within the building shall be located to avoid any air that might escape through the isolation barriers and shall be approximately 50 feet from the entrance to the work area, and 25 feet from the isolation barriers.
- (d) The following aggressive sampling procedures shall be used within the work area during all clearance air monitoring:

- (1) Before starting the sampling pumps, use forced air equipment (such as a 1 horsepower leaf blower) to direct exhaust air against all walls, ceilings, floors, ledges and other surfaces in the work area.
 - (i) For asbestos projects: this pre-sampling procedure shall take at least 5 minutes per 1,000 sq. ft. of floor area; then install one 20-inch fan per 10,000 cubic feet of room space. Then immediately place the fan on slow speed and point it toward the ceiling.
 - (ii) For pre-demolition asbestos abatement activity, this pre-sampling procedure shall take at least three minutes, after which the 20-inch fan shall be left running unattended in the work area throughout sampling. This procedure shall be acceptable when the floor area of the work area is less than 500 square feet. At or above 500 square feet of floor area within the work area, the aggressive sampling procedures specified in this subdivision (d) for asbestos projects shall be conducted.
- (2) Start the sampling pumps and sample for the required time or volume.
- (3) Turn off the pump and then the fan(s) when sampling is completed.
- (e) For post-abatement monitoring, area samples shall conform to the following schedule:

Area Samples for Analysis by	Minimum Volume	Flow
PCM	1,800 Liters	5 to 15 liters/min.
TEM	1,250 Liters	1 to 10 liters/min.

- (f) Each homogeneous work area which does not meet the clearance criteria shall be thoroughly recleaned using wet methods, with the negative pressure ventilation system in operation. New samples shall be collected in the work area as described above. The process shall be repeated until the work site passes the test.
- (g) For an asbestos project with more than one homogenous work area, the release criterion shall be applied independently to each work area.
- **§1-44** Analysis and Reporting Results. Laboratory analyses and reporting shall be considered evidence of compliance with this chapter only if they conform to the following requirements:
- (a) PCM area air samples shall be analyzed and reported in accordance with the NIOSH 7400 method using "A" Counting Rules.
- (b) TEM area air samples shall be analyzed and reported in accordance with the mandatory or non-mandatory Electron Microscopy Methods set forth at 40 CFR Part 763, Subpart E, Appendix A.

- (c) Bulk samples shall be analyzed and reported in accordance with Interim Method for the Determination of Asbestiform Materials in Bulk Insulation Samples found in 40 CFR Part 763, Subpart F, Appendix A as amended on September 1, 1982, or other methods approved by the National Institute of Standards and Technology, the National Institute of Occupational Safety and Health, the United States Environmental Protection Agency, or New York State Department of Health.
- (d) Bulk and air sampling results/reports shall be submitted directly to the Department upon request within five calendar days.
- **§1-45** Action Criteria. (a) When visible emissions occur outside the work area, or any area air sample has indicated a determinant level of fiber concentrations greater than the larger of baseline levels or 0.01 f/cc, work shall stop for inspection.
 - (1) For large or small asbestos projects, the integrity of barriers, if disturbed, shall be restored. Clean-up of surfaces outside of the work area using HEPA vacuums or wet cleaning techniques shall be done prior to resuming abatement activities.
 - (2) For tent procedures, HVAC systems to or in the work area shall be shut down and the work area shall be wet cleaned or HEPA vacuumed until the area air samples indicate the fiber concentration is below the determinant level. If fiber concentrations remain above the determinant level for longer than 24 hours, isolation barriers and engineering controls shall be installed and maintained.
- (b) Clearance and/or reoccupancy criteria. (1) The clearance criteria shall be applied to each homogeneous work area independently.
 - (2) For PCM analysis involved in alteration or renovation projects, the clearance air monitoring shall be considered satisfactory when every sample is less than or equal to 0.01 f/cc or less than the ambient concentration, whichever is larger.
 - (3) For TEM analysis, the clearance monitoring will be considered satisfactory if conducted in accordance with 40 CFR Part 763, Subpart E, Appendix A Section IV— Mandatory Interpretation of Transmission Electron Microscopy Results to Determine Completion of Response Actions.
 - (4) Clearance air monitoring results shall be submitted directly to the Department within 24 hours of request.

Subchapter E

Personnel Protection and Equipment Specifications

Part 1 Worker Protection

2 Equipment Specifications

Part 1

Worker Protection

- **§1-51 Worker Protection Requirements.** (a) Prior to project initiation, all workers engaged in abatement activities on an asbestos project or minor project must be certified by DEP.
- (b) At least one asbestos handler supervisor shall be present at the work site while abatement activities are being conducted on an asbestos project or minor project, except that during minor projects the supervisor does not have to be physically present at all times but must be readily available.
- (c) Personal protective equipment shall be worn by all individuals inside the work place during abatement activities, except that gloves need not be worn during those work place preparation activities which do not involve the disturbance of ACM.

Personal protective equipment shall meet the following specifications:

- (1) Disposable clothing including head, hand, foot and full body protection shall be provided by the contractor in sufficient quantities and adequate sizes for all workers and authorized visitors.
- (2) Hard hats, protective eyewear, gloves, rubber boots and/or other footwear shall be provided by the contractor as required for workers and authorized visitors. Safety shoes and hard hats shall be in accordance with ANSI Z89.1 (1969) and ANSI Z41.1 (1967).
- (3) Contaminated clothing shall be sealed in impermeable bags and the bags shall be appropriately labeled.
- (d) Personal air monitoring shall be performed in accordance with current OSHA regulations. Such records shall be made available upon request to authorized Department representatives upon request.
 - (e) Personal Hygiene at the work site shall meet the following requirements:
 - (1) There shall be no smoking on any floor of the building where abatement activities are taking place.

- (2) Jewelry, watches, and cellular telephones shall not be worn, carried, or kept in contaminated areas.
- (3) The contractor shall provide clean change areas for the workers. Change areas shall be equipped with separate storage facilities for protective clothing and street clothing.
- (4) If lunch areas are provided, they shall be located outside the work place in an area in which the airborne concentrations are below 0.01 f/cc.
- (5) There shall be no eating, drinking, application of cosmetics, or chewing of gum or tobacco inside the work place. There shall be no food or beverages present in the work place.
- (6) There shall be no lighters or matches in the work place.
- (f) The contractor shall have available the following information at the work place:
 - (1) A copy of the U.S. Environmental Protection Agency Regulations for Asbestos, 40 CFR 61 Subparts A and M and a copy of OSHA Asbestos Regulations, 29 CFR 1926.1101, and 12 NYCRR Part 56; and
 - (2) A list of telephone numbers for local hospital, location of hospital and/or emergency squad, local fire department, the building owner (or representative) and the N.Y.C. Asbestos Control Program, and
 - (3) A copy of these Rules, the most recent Asbestos Abatement Notice (Form ACP-13), permits, any variance application (Form ACP-9) and DEP approval thereof, and
 - (4) A copy of all Material Safety Data Sheets (MSDS) for chemicals used during the asbestos project, and
 - (5) New York City Asbestos handler and supervisor certificates of all workers in the work site, and
 - (6) A copy of the current New York State Department of Labor asbestos handling license of the abatement contractor and air monitoring company.
 - (7) A copy of any asbestos survey performed in the affected building in accordance with these rules.
- (g) The contractor shall post signs during all abatement activities. Signs shall be posted at all approaches to the work place including internal doorways which provide access to the work place. These signs shall bear the following information:

DANGER ASBESTOS CANCER AND LUNG DISEASE HAZARD AUTHORIZED PERSONNEL ONLY RESPIRATORS AND PROTECTIVE CLOTHING ARE REQUIRED IN THIS AREA

(h) Warning labels shall be affixed to all waste containers containing asbestos material in and shall bear the following information:

DANGER CONTAINS ASBESTOS FIBERS AVOID CREATING DUST CANCER AND LUNG DISEASE HAZARD

Part 2

Equipment Specifications

- **§1-61 Materials and Equipment.** The materials and equipment used during all abatement activities shall conform with the following:
- (a) During abatement activities, replacement materials shall be stored outside the work area in a manner to prevent contamination. Materials required for the asbestos project (i.e. plastic sheeting, replacement filters, duct tape, etc.) shall be stored to prevent damage or contamination.
- (b) When asbestos-containing material that has been used for fireproofing or insulation is removed, the replacement material shall comply with all applicable provisions of the New York City Administrative Code and regulations.
- (c) For plasticizing, fire-retardant polyethylene sheeting with 6-mil thickness or greater, in sizes to minimize the frequency of joints, shall be employed.
- (d) Duct tape and selected adhesive shall be capable of sealing joints of adjacent sheets of polyethylene, facilitating attachment of polyethylene sheets to finished or unfinished surfaces, and of adhering under both dry and wet conditions, including during the use of amended water.
- (e) Airtight and watertight containers shall be provided to receive and retain any asbestos-containing waste materials. Plastic bags used for waste storage or disposal shall be a minimum of 6-mil in thickness. All containers shall be labeled in accordance with OSHA Regulation 29 CFR 1926.58K(2)(ii) and (iii).

- (f) Materials used to enclose ACM shall be impact resistant and assembled to be airtight Gypsum panels taped at the seams, tongue and groove boards, and boards with spline joints all qualify.
- (g) Power tools used to drill, cut into, or otherwise disturb ACM shall be manufacturer-equipped with HEPA filtered local exhaust ventilation. Abrasive removal methods, including the use of beadblasters, are prohibited.
- (h) Ladders or scaffolds of sufficient dimension and quantity shall be available so that all work surfaces can be easily and safely reached by inspectors. Scaffold joints and ends shall be sealed with tape to prevent incursion of asbestos fibers.
 - (i) Electrical equipment shall be Underwriters Laboratory listed and approved.
- (j) Surfactants, strippers, sealers, or any other chemicals used during the asbestos project shall be non-carcinogenic and non-toxic.
- (k) Plastic sheeting used in the construction of temporary enclosures shall be fire-retardant in accordance with NFPA 701. Wood or other materials used in the construction of temporary enclosures shall be noncombustible or fire-retardant in accordance with NFPA 255, ASTM D-2898, ASTM E84, and UL 723.
- (l) Equipment and materials may be substituted for those specified in this chapter only if determined to be equivalent after review by the Department.

Subchapter F

Asbestos Project Procedures

- Part 1 Applicability
 - 2 Work Place Preparation
 - **3 Work Place Procedures**
 - **4** Abatement Procedures
 - **5** Clean-up Procedures

Part 1

§1-71 Applicability. In addition to §§1-01 through 1-61, the following sections 1-81 through 1-83, 1-91 through 1-94 and 1-111 and 1-112 shall apply to all asbestos projects. Sections 1-101 through 1-110 shall apply to all asbestos abatement activities.

Part 2

Work Place Preparation

- §1-81 General Work Place Preparation Requirements
- §1-82 Worker Decontamination Enclosure System
- §1-83 Waste Decontamination Enclosure System
- §1-84 Small Asbestos Project Worker and Waste Decontamination Enclosure System

§1-81 General Work Place Preparation Requirements.

The following procedures shall be followed during the conduct of abatement activities on asbestos projects. The procedures set forth in this subdivision shall be performed in the order set forth below:

(a) The building owner or designated representative shall provide notification to all occupants of the work place and immediate adjacent areas of the asbestos project. Information provided in the notification shall include contractor, project location and size, amount and type of ACM, abatement procedure, dates of expected occurrence and the Call Center "311" for government information and services. Postings of this notification shall be in English and Spanish, at eye level, in a conspicuous, well-lit place, at the entrances to the work place and immediate adjacent areas. The notice shall have the following heading: **NOTICE OF ASBESTOS ABATEMENT**, in a minimum of one inch sans serif, gothic or block style lettering, with the balance of the lettering of the notice to be of the same type lettering in a minimum of one quarter inch size. The notices shall be posted 7 calendar days prior to the start of the project and shall remain posted until clearance air monitoring is satisfactorily concluded. A lessee initiating an asbestos project shall give 10 calendar days notice to the owner of the subject building.

- (b) A floor plan showing the areas of the building under abatement and the location of all fire exits in said areas shall be prominently posted in the building lobby or comparable location, along with a notice stating the location within the building of the negative air cutoff switch required under section 1-91(f) of these rules, if applicable.
- (c) The work place shall be vacated by the occupants prior to work place preparation and until successful clearance air monitoring.
- (d) Electric power to all work areas shall be shut down and locked out except for electrical equipment that must remain in service. Safe temporary power and lighting shall be provided in accordance with all applicable codes. Existing light sources (e.g. house lights) shall not be utilized. All power to work areas shall be brought in from outside the area through ground-fault circuit interrupter at the source.
 - (1) If electrical circuits, machinery, and other electrical systems in or passing though the work area must stay in operation due to health and safety requirements, the following precautions must be taken:
 - (i) All unprotected cables, except low-voltage (less than 24 volts) communication and control system cables, panel boxes of cables and joints in live conduit that run through the work area shall be covered with three (3) independent layers of six (6) mil fire retardant polyethylene. Each layer shall be individually duct taped and sealed. All three (3) layers of polyethylene sheeting shall be left in place until satisfactory clearance air sampling results have been obtained.
 - (ii) Any energized circuits remaining in the work area shall be posted with a minimum two (2) inch high lettering warning sign which reads: DANGER LIVE ELECTRICAL KEEP CLEAR. A sign shall be placed on all live covered barriers at a maximum of ten (10) foot intervals. These signs shall be posted in sufficient numbers to warn all persons authorized to enter the work area of the existence of the energized circuits.
- (e) The worker decontamination enclosure system shall be installed or constructed prior to plasticizing the work area or before disturbing ACM.
 - (f) (1) Prior to erection of partitions, ACM that may be disturbed during this activity shall be:
 - (i) removed using a tent procedure (including engineering controls); and/or
 - (ii) treated via wet methods.
 - (2) Removal by the above procedures shall be limited to a maximum of a one foot wide strip running the length and/or height of the partition and is allowed only to facilitate erection of the partitions.
- (g) All boilers and other equipment within the work area shall be shut down, locked out, and tagged out and the burner/boiler/equipment accesses and openings shall be sealed in accordance with §1-81(n) until abatement activities are complete. If the boiler or other exhausted

equipment will be subject to abatement, all breeching, stacks, columns, flues, shafts, and double-walled enclosures serving as exhausts or vents shall be segregated from the affected boiler or equipment and sealed airtight to eliminate potential chimney effects within the work area. Heating, Ventilation and Air Conditioning (HVAC) System Isolation methods are listed below in order of preference; the more complex and potentially problematic methods maybe used when the more preferred procedures are impractical.

- (1) shut down and lock out HVAC systems and install isolation barriers (see §1-81(n)) to prevent contamination and fiber dispersal to other areas of the structure, or
- (2) isolate locally and provide temporary HVAC, or
- (3) positive pressurization of the HVAC system. This procedure shall be applied only under the direction and control of a professional engineer, or other knowledgeable licensed professional.
- (h) Abatement shall not commence until work place preparation has been completed.
- (i) Movable objects within the proposed work areas shall be pre-cleaned (i.e., prior to commencing general abatement) using HEPA filtered vacuum equipment and/or wet cleaning methods and such objects shall be removed from the work area. If carpeting is left in place, it shall be covered with fire retardant 6-mil plastic sheeting, and then 3/8 in. rigid flooring prior to normal plasticizing.
- (j) All flammable materials shall be removed from the work area and all sources of ignition (including but not limited to pilot lights) shall be extinguished.
- (k) Fixed objects which will remain within the proposed work areas shall be pre-cleaned using HEPA filtered vacuum equipment and/or wet cleaning methods as appropriate, and enclosed with two layers of fire retardant 6-mil plastic sheeting sealed to protect from re-contamination. Sprinklers, standpipes, and other fire suppression systems shall remain in service and shall not be plasticized.
- (l) Any source of emergency lighting which is temporarily blocked as a result of work place preparation shall be replaced for the duration of the project by battery operated or temporary exit signs, exit lights, or exit path markings.
- (m) Prior to plasticizing, the proposed work areas shall be pre-cleaned using HEPA filtered vacuum equipment and/or wet cleaning methods. Methods that raise dust, such as sweeping or vacuuming with equipment not equipped with HEPA filters, are prohibited.
- (n) The isolation barriers (i.e., sealing off of all openings, including but not limited to windows, corridors, doorways, barriers, skylights, ducts, grills, diffusers, and any other penetrations of the work place) shall be installed with two layers of fire retardant 6-mil plastic sheeting sealed with tape. All seams of HVAC or other system components that pass through the work place shall also be sealed.
- (o) The work area shall be segregated from the remainder of the work site by construction of temporary structural partitions as follows:

- (1) Partitions shall be constructed of conventional 2 x 3 (minimum) wood or metal stud framing, 16"CC maximum, to support barriers in all openings larger than 32ft², except where any one dimension is 1 foot or less, or where openings are exits covered in subdivision (p) below.
- (2) A solid construction material (e.g. fire rated plywood) of at least 3/8" thickness shall be applied to the work side of the framing. In secure interior areas where partitions are not subject to access from the public, an additional layer of fire retardant 6-mil plastic sheeting may be substituted for the solid construction material.
- (3) The partitions shall be caulked/sealed at the floor, ceiling, walls, joints and fixtures to form an airtight seal.
- (4) Where the opening is an exit covered in subdivision (s) below, or where the partition would block egress, the partition shall consist of two sheets of fire-retardant 6-mil plastic, prominently marked as an exit with signage so as to be visible both in normal light and in the event of a power failure. Cutting tools (e.g., knife, razor) shall be attached to the work area side of the sheeting for use in the event that the barrier must be cut open to allow egress.
- (5) Means of egress shall not be obstructed by hardwall barriers.
- (p) In addition to the isolation barriers, floor and wall surfaces shall be sealed with a minimum of two layers of fire retardant 6-mil plastic sheeting, except where the only ACM being abated in the project is vinyl asbestos floor tile or other flooring material, in which case the floor need not be sealed; or the only material being abated in the project is wall plaster or other wall material, in which case the walls need not be sealed. The plastic layers on the floor shall extend 6 inches up the walls. Walls shall be covered with plastic sheeting down to the floor level, thus overlapping the floor material by a minimum of 6 inches. There shall be a distance of at least 6 inches between seams of adjacent layers.
- (q) After isolation barriers are in place, ceiling-mounted objects not previously sealed that will interfere with ACM abatement shall be removed and cleaned. Amended water spraying or HEPA filtered vacuum equipment shall be used during fixture removal to reduce fiber dispersal.
- (r) Suspended ceiling tiles and T-grid components, contaminated by ACM, shall remain in place until the work area has been fully prepared as outlined in this section and electrical and HVAC systems have been shutdown. Suspended ceiling components shall be removed and disposed of as asbestos-containing waste or, if non-porous, retained for reuse after wet cleaning/HEPA vacuuming. Isolation barriers shall be installed in all openings above the ceiling before disturbance of ACM commences.
- (s) Entrances to the work place that will not be used for worker entry or emergency exits shall be locked to prevent unauthorized entry.
- (t) Exits from the work area shall be maintained, or alternative exits shall be established, in accordance with section 1027 of the New York City Fire Code. Exits shall be checked at the beginning and end of each work shift against blockage or impediments to exiting.

- (u) Signs clearly indicating the direction of exits shall be maintained and prominently displayed within the work area. The signs shall bear a horizontal arrow or arrows indicating the direction to the exit, above which the word "EXIT" shall be printed in minimum 5" letter size.
- (v) No smoking signs shall be maintained and prominently displayed within the work place. The signs shall be a minimum of 10 by 14 inches and shall bear the International "No Smoking" symbol, under which the words "NO SMOKING" shall be printed in minimum 2" letter size.
- (w) Floor drains shall be sealed individually with two layers of fire retardant 6-mil plastic sheeting and tape, and then covered as all other floor surfaces. Pits, sumps, etc., shall be covered with adequate fire rated plywood sheeting and secured to floor slabs in a manner which prevents a tripping hazard, prior to required plasticizing.
 - (x) Elevators running through the work area shall conform to the following:
 - (1) The elevator door in the work area shall be enclosed with conventional 2 x 4 stud framing, covered with 3/8" fire rated plywood sheeting and sealed at all edges and seams. The barrier shall be covered and lapped for 8 inches with two layers of fire retardant 6-mil plastic sheeting adhered individually with edges taped for air tightness.
 - (2) Elevators not remaining in service shall have the fuses removed and the power switch locked in the open position.
 - (3) Elevators that remain in operation shall conform to the following additional procedures to minimize the piston effect that results:
 - (i) Elevator control shall be modified to bypass the work area.
 - (ii) A final larger layer of fire retardant 6-mil plastic sheeting is to be taped airtight but with slack forming a larger perimeter diaphragm. Air leakage across the barrier shall be corrected upon discovery, and the elevator shaft shall be checked for airborne asbestos contamination.
 - (iii) This system shall be smoke tested daily.
 - (4) Elevator shafts shall not be used as waste chutes.
- (y) Adequate toilet facilities shall be provided in the vicinity of the clean room external to the work place. Where such facilities so not exist, portable service shall be provided.
- (z) At least one functional fire extinguisher with a minimum rating 2-A:10-B:C shall be required for each work place. In the case of large asbestos projects, at least two such fire extinguishers shall be required.

- **§1-82 Worker Decontamination Enclosure System.** The following procedures shall be followed during the conduct of abatement activities on asbestos projects:
- (a) Worker decontamination enclosure systems shall be located outside the work area and attached to all locations where workers will enter or exit the work area. One system at a single location for each contained work area is preferred. These systems may consist of existing rooms outside of the work area, that offer direct access to the work area and general egress from the work place. When this situation does not exist, enclosure systems may be constructed or may consist of prefabricated or trailer units. Adequate heat and light shall be safely provided.
- (b) The worker decontamination enclosure system shall consist of a clean room, a shower room, and an equipment room, in series, separated from each other by airlocks and from the work area and non-work place by curtained doors (see Illustration I).
- (c) Worker decontamination enclosure systems shall be fully lined utilizing two layers of fire retardant 6-mil opaque plastic sheeting at a minimum, or the equivalent.
- (d) When the decontamination enclosure is constructed outdoors or in areas with public access it shall be fully framed and fire retardant plywood sheathed or equivalent to prevent unauthorized entry. When located outdoors, it shall be waterproof and windproof.
 - (e) Prefabricated or trailer decontamination units:
 - (1) shall at a minimum, have functionality and security equivalent to constructed decontamination enclosure facilities, and
 - (2) shall be completely decontaminated prior to removal from the work site.
 - (f) The clean room:
 - (1) shall contain secure crew lockers or shelves, and clean sealable plastic bags for storage of street clothes, and
 - (2) shall contain shelves or appropriate facilities for storage of respirators, and
 - (3) shall contain clean disposable clothing, replacement filters for respirators, towels and other necessary personal protective equipment, and
 - (4) shall not be used for storage of tools, equipment or materials, other than personal protective equipment, nor used as office space, and
 - (5) shall be equipped with a lockable door to secure the work place during off-shift hours.
 - (g) The shower room:
 - (1) shall contain a minimum of one (1) shower per 6 workers calculated on the basis of the largest shift, and

- (2) shall have shower heads supplied with hot and cold water adjustable at the shower, and
- (3) shall be constructed to ensure against water leakage, and shall contain a rigid catch basin at least six (6) inches deep, and
- (4) shall contain liquid bath soap, shampoo, and clean dry towels in sufficient quantity for each worker for each showering.
- (h) Shower water shall be continuously drained, collected and filtered through a system with a least 5.0 micron particle size collection capability. A system containing a series of several filters with progressively smaller pore sizes shall be used to avoid rapid clogging of the filtration system by large particles. Pumps shall be installed, maintained and utilized in accordance with manufacturer's recommendations.
 - (1) Filtered wastewater shall be discharged either to a sewer or drummed and then properly disposed.
 - (2) Used filters shall be disposed of as asbestos-containing waste material.
 - (i) The equipment room:
 - (1) shall be used for storage of equipment and tools used on the job that have been cleaned previously in the work area, and
 - (2) may contain a limited supply of replacement filters (in sealed containers until used) for HEPA vacuums and pressure ventilation equipment, extra tools, containers of surfactant and other materials and equipment that may be required during the abatement activity, and
 - (3) shall contain labeled 6-mil plastic bags for collection of disposable clothing, and
 - (4) shall be used to store contaminated footwear (e.g. rubber boots and other reusable footwear) and contaminated clothing for reuse for the duration of the abatement activity or until disposed.
- **§1-83 Waste Decontamination Enclosure System.** The following procedures shall be followed for removal of asbestos-containing waste material and equipment during the conduct of abatement activities on asbestos projects:
- (a) The waste decontamination enclosure system shall be located outside the work area and attached to all locations through which ACM waste will be removed from the work area. A waste decontamination enclosure system shall consist of two totally enclosed chambers and shall also comply with the following requirements:
 - (1) the washroom shall be constructed with a curtained doorway to the work area and an airlock doorway to the holding area (see Illustration II); and be equipped with a

- catch basin and a drain installed to collect and deliver wastewater to either the shower drain or to a separate holding vessel where it is filtered;
- (2) the holding area shall be constructed with a curtained doorway to the washroom and a lockable door to the outside (see Illustration II); if remote from the washroom, it shall comply with all applicable NYC Department of Sanitation regulations pursuant to Local Laws 70 of 1985 and 21 of 1987.
- (b) Where there is only one means of egress from the work area:
 - (1) the holding area of the waste decontamination enclosure system may branch off from the equipment/decontamination room (see Illustration III). Thus constructed, the equipment room alternates as a waste washroom. In this case the waste washroom shall be equipped with a catch basin and a drain, installed to collect and deliver wastewater to either the shower drain or a separate holding vessel from where it is filtered, or
 - (2) where total asbestos-containing material disturbed in the asbestos project is less than 1,000 linear feet or 1,000 square feet, the shower room may be used as a waste washroom and shall be equipped as set forth in section 1-83(b)(1), and
 - (i) the clean room, in the configuration shown in Illustration I, may not be used for waste storage but may be used for waste transfer to carts, which are stored outside the clean room in a designated holding area.
- (c) The waste decontamination enclosure system shall be constructed to meet the requirements of $\S\S1-82$ (a), (c), (d), (e), (g)(3) and (h).

§1-84 Small Asbestos Project Worker and Waste Decontamination Enclosure System. The following alternative to §§1-82 and 1-83 shall be applicable for small projects only:

- (a) The worker decontamination enclosure system shall consist of, as a minimum, an equipment room, a shower room, and a clean room separated from each other and from the work area by curtained doorways. Equipment storage, personal gross decontamination and removal of disposable clothing shall occur in the equipment room prior to entering the shower. All other requirements set forth in §1-82 and §1-92 shall apply.
- (b) For small asbestos projects with only one exit from the work area, the shower room may be used as a waste washroom. The clean room shall not be used for waste storage. All other requirements set forth in §§1-83 and 1-93 shall apply.

Part 3

Work Place Procedures

§1-91	Engineering Controls
§1-92	Work Place Entry and Exit Procedures
§1-93	Equipment and Waste Container Decontamination and
	Removal Procedures
§1-94	Maintenance of Decontamination Enclosure Systems
	and Barriers

- **§1-91 Engineering Controls.** The following procedures shall be followed during the conduct of abatement activities on asbestos projects:
 - (a) All asbestos projects shall utilize negative pressure ventilation equipment.
 - (1) On all asbestos projects, a manometer shall be used to document the pressure differential. The manometer shall be installed and made operational once the negative pressure has been established in the work area. Magnahelic manometers shall be calibrated at least every six months, and a copy of the current calibration certification shall be available at the work site.
- (b) The negative pressure ventilation equipment shall operate continuously, 24 hours a day, from the establishment of isolation barriers through successful clearance air monitoring. If such equipment shuts off, adjacent areas shall be monitored for asbestos fibers.
- (c) A static negative air pressure of 0.02 inches (minimum) water column shall be maintained at all times in the work place during abatement to ensure that contaminated air in the work area does not filter back to uncontaminated areas.
- (d) If more than one ventilation unit is installed, units shall be turned on one at a time while checking the integrity of all barriers for secure attachment and the need for additional reinforcement.
- (e) A dedicated power supply for the negative pressure ventilating units shall be utilized. The negative air equipment shall be on a ground fault circuit interrupter (GFCI) protected circuit separate from the remainder of the work area temporary power circuits.
- (f) If the containment area of an asbestos project covers the entire floor of the affected building, or an area greater than 15,000 square feet on any given floor, the installation of a negative air cut off switch or switches shall be required at a single location outside the work place, such as inside a stairwell, or at a secured location in the ground floor lobby when conditions warrant. The required switch or switches shall be installed by a licensed electrician pursuant to a permit issued by the Department of Buildings. If negative pressure ventilation equipment is used on multiple floors the cut off switch shall be able to turn off the equipment on all floors

- (g) On loss of negative pressure or electric power to the negative pressure ventilating units, abatement shall stop immediately and shall not resume until power is restored and negative pressure ventilation equipment is operating again. When power failure or loss of negative pressure equipment lasts or is expected to last longer than one-half hour:
 - (1) the make-up air inlets shall be sealed airtight, and
 - (2) the decontamination systems shall be sealed airtight after the evacuation of workers and/or authorized visitors from the work area, and
 - (3) all adjacent areas shall be monitored for asbestos fiber concentration upon discovery of, and subsequently throughout, the power failure.
- (h) Negative pressure ventilation equipment shall be installed and operated to provide at least one air change in the work area every 15 minutes. Where there are no floor or wall barriers because floor or wall material is being abated, there shall be at least one air change in the work area every ten minutes.
- (i) Openings made in the isolation barrier to accommodate these units shall be made airtight. The units shall remain within the work area unless located securely outside the building.
- (j) Negative air pressure equipment shall be in compliance with ANSI Z9.2 (2006), Local Exhaust Ventilation.
- (k) Negative air pressure systems shall be operated in accordance with "Specifications and Operating Procedures for the Use of Negative Pressure Systems for Asbestos Abatement, Guidance for Controlling Asbestos-Containing Materials in Buildings", EPA Report Number 560/5-85-024 (1985).
- (l) Negative pressure ventilation equipment shall be exhausted to the outside of the building away from occupied areas.
 - (1) All openings (including but not limited to operable windows, doors, vents, air intakes or exhausts of any mechanical devices) less than 15 feet from the exterior exhaust duct termination location shall be plasticized or made airtight, or a second negative pressure ventilation unit with the primary unit's capacity shall be connected in series prior to exhausting to the outside.
 - (2) Negative pressure ventilation equipment shall exhaust away from areas accessible to the public.
 - (3) All ducting shall be sealed and braced or supported to maintain airtight joints. Ducts shall be reinforced and shall be installed so as to prevent breakage. Damage to ducts must be repaired immediately.

- (m) Where ducting to the outside is not possible, a second negative pressure ventilation unit compatible with the primary unit's capacity shall be connected in series. The area receiving the exhaust shall have sufficient, non-recycling exhaust capacity to the outside of the structure, and must be a normally non-occupied area.
- (n) Careful installation shall be done to ensure that the ducting does not release fibers into uncontaminated building areas.
- (o) Routine smoke testing, air monitoring and daily inspections shall be performed by the Asbestos Handler Supervisor to ensure that the ducting does not release fibers into uncontaminated building areas.
- **§1-92** Work Place Entry and Exit Procedures. The following procedures shall be followed during the conduct of abatement activities on asbestos projects:
- (a) *Entrance procedures*. (1) All workers and authorized visitors shall enter the work area through the worker decontamination enclosure system.
 - (2) All individuals who enter the work area shall sign the log located in the clean room, upon each entry and exit. The log shall be permanently bound and shall identify fully the facility, owner, agents, contractor(s), the project, each work area and worker respiratory protection employed. The log shall be available for examination during abatement activities by the Department, the owner and the workers. A copy of the log shall be submitted directly to the Department within 48 hours of request.
 - (3) All individuals before entering the work area, shall be familiar with all posted regulations, personal protection requirements and emergency procedures. The log headings shall indicate, and the signatures shall be used to acknowledge, that the regulations and procedures have been reviewed and understood by all persons prior to entering the work area. The postings and log headings shall be in English and in the language of the majority of the asbestos handlers.
 - (4) All individuals shall proceed first to the clean room, remove all street clothing, store these items in clean sealable plastic bags or a locker and don personal protective equipment. Clean personal protective equipment shall be provided and utilized by each individual for each separate entry into the work area.
- (b) *Exit procedures*. (1) Before leaving the work area, each individual shall remove the gross contamination from the outside of the respirators and protective clothing by wet cleaning, and/or HEPA vacuuming.
 - (2) In the equipment room, all personal protective equipment except respirators shall be removed. Disposable clothing shall be deposited into labeled containers for disposal. Reusable contaminated clothing, footwear, and/or head gear shall be stored in the equipment room when not in use.

- (3) Still wearing a respirator, each person shall proceed to the shower room, clean the outside of the respirator and the exposed face area under running water prior to removal of the respirator, and then fully and vigorously shower and shampoo to remove residual asbestos contamination. Respirators shall be washed thoroughly with soap and water or a suitable sanitizing agent. Various types of respirators may require slight modification of these procedures.
- (4) After showering and drying, personnel shall proceed to the clean room and don clean disposable clothing if returning to the work area or street clothing if remaining outside the work area.

§1-93 Equipment and Waste Container Decontamination and Removal Procedures.

The following procedures shall be followed whenever equipment or containers are removed from the work area during an asbestos project:

- (a) When the worker decontamination enclosure system shown in Illustration I alternates as a waste decontamination enclosure system, the clean room shall be considered a holding area during the period of active waste transfer only for the purpose of the loading of carts. Storage of waste and carts in the clean room is prohibited.
- (b) Where the waste decontamination enclosure system is part of the worker decontamination enclosure system (see Illustration III), waste removal shall not occur during worker shift changes or when workers are showering or changing. Care shall be taken to prevent short circuiting and cycling of air outward through the shower and clean room.
- (c) Where only one means of egress exists and the shower room is used as a waste washroom, workers are to be stationed in each room/area of the decontamination enclosure to transfer/process (see subdivisions (d), (h) and (I) of this section) the containers and equipment to or from adjacent sections. These workers are not to cross into the adjacent areas/rooms until the waste/equipment transfer is finished for that period and the workers have gone through decontaminations required by §1-92 of this chapter. The clean room/holding area workers shall have entered from uncontaminated areas with appropriate personal protective equipment; or prior to the start of waste transfer, these workers shall have exited the work area, fully decontaminated, and subsequently donned clean personal protective equipment.
- (d) External surfaces of contaminated containers and equipment shall be cleaned by wet cleaning and/or HEPA vacuuming in the work area before transferring such items into the decontamination enclosure system. Contaminated workers shall not enter the washroom during this procedure.
- (e) The cleaned containers of ACM and equipment shall be recontainerized (double-bagged) by either placing them in uncontaminated leak-tight plastic bags or sheeting as the item's physical characteristics demand while in the washroom of the waste decontamination enclosure system. Air volume shall be minimized and the bags or sheeting shall be sealed. Items that may puncture or tear the plastic bags or sheeting shall be placed in a hardwall container and sealed.

- (f) The clean recontainerized items shall be moved into the airlock for subsequent transfer to the holding area. The washroom workers shall not enter this airlock or the work area until waste removal is finished for that period.
- (g) Recontainerized items and cleaned equipment shall be removed from the airlock to the holding area by workers who have entered from uncontaminated areas with appropriate personal protective equipment.
- (h) The recontainerized items of ACM and cleaned, bagged equipment shall be placed in open top, watertight plastic carts. These carts shall be held in the holding area pending removal. The carts shall be HEPA vacuumed or wet-cleaned following the removal of the containers of ACM from them.
- (i) The exit from the waste decontamination enclosure system shall be secured to prevent unauthorized entry.
 - (j) The carts shall be stored in a holding area of the work site.
- **§1-94 Maintenance of Decontamination Enclosure Systems and Barriers.** The following procedures shall be followed during the conduct of abatement activities on asbestos projects:
- (a) All plastic barriers inside the work place and partitions constructed to isolate the work area from occupied areas shall be inspected by the asbestos handler supervisor at least twice per shift.
- (b) Smoke tubes shall be used to test the integrity of the work area barriers and the decontamination enclosure systems daily at a minimum both before abatement activity begins and at the end of each shift. A visual inspection of the barriers, including the use of differential manometers, shall be considered acceptable as a back-up test.
- (c) Damage and defects in the decontamination enclosure system shall be repaired immediately. The decontamination enclosure system shall be maintained in a clean and sanitary condition at all times.
- (d) At any time during the abatement activity, if visible emissions are observed, or elevated asbestos fiber counts outside the work area are measured, or if damage occurs to barriers, abatement shall stop. The source of the contamination shall be located, the integrity of the barriers shall be restored, and visible residue shall be cleaned up using appropriate HEPA vacuuming and wet cleaning procedures immediately.
- (e) Inspections, observations, and unusual incidents (e.g. barrier damage, contamination beyond the work area, etc.) shall be documented in the log by the asbestos handler supervisor.
- (f) The daily inspection to ensure that exits have been checked against exterior blockage or impediments to exiting as per section 1-81(t) shall be documented in the log book.
 - (g) If exits are found blocked, abatement activities shall stop until the blockage is cleared.

Part 4

Abatement Procedures

§1-101	Applicability
§1-102	ACM Disturbance, Handling and Removal Procedures
§1-103	Encapsulation Procedures
§1-104	Enclosure Procedures
§1-105	Glovebag Procedures
§1-106	Tent Procedures
§1-107	Foam Procedure for Roof Removal
§1-108	Foam/Viscous Liquid Use in Flooring Removal
§1-109	Abatement from Vertical Exterior Surfaces
§1-110	Controlled Demolition With Asbestos In Place

§1-101 Applicability. The following §§1-102 through 1-110 inclusive shall apply to all abatement activities.

- **§1-102 ACM Disturbance, Handling and Removal Procedures.** The following procedures shall be followed during the conduct of abatement activities:
- (a) Abatement of asbestos-containing materials shall be by wet methods. ACM shall not be removed or disturbed without being adequately wet. Dry removal of asbestos-containing material is prohibited, unless EPA approval has been obtained. The EPA-approved alternate removal plan shall be submitted to the Department for approval a minimum of 15 days before work is scheduled to begin or begins. The plan shall explain and justify why ACM must be removed dry and how asbestos fibers will be controlled to prevent their release.
- (b) When amended water is used, the ACM shall be sprayed with sufficient frequency and quantity for enhanced penetration. Sufficient time shall be allowed for penetration to occur prior to removal action or other disturbance taking place. Accumulation of standing or free water is prohibited. Fluffy materials shall be saturated. Non-hygroscopic materials, such as tremolite or amosite, shall be thoroughly wetted on all surfaces while work is being conducted.
- (c) When used, removal encapsulants that minimize fiber generation and enhance penetration, shall be applied per manufacturer's specifications and in accordance with federal guidelines.
- (d) ACM on detachment from the substrate is to be bagged directly or dropped onto a flexible catch basin and promptly bagged. Detached ACM is not permitted to lie on the floor for any period of time. Excess air in the bag shall be minimized and the bag shall be sealed. Non-hygroscopic materials shall not be dropped. ACM shall not be dropped from a height greater than 10 feet. Above 10 feet in height dust-free enclosed inclined chutes may be used. Vertical chutes are prohibited. Maximum inclination from horizontal shall be 60 degrees.
- (e) Large components removed intact that cannot be containerized shall be maintained wet, wrapped (minimizing excess air) in at least one layer of fire retardant 6-mil polyethylene sheeting, and secured by sealing with tape.

- (f) After completion of all stripping work, surfaces from which asbestos-containing materials have been removed shall be cleaned (e.g. wet-brushed and/or wet-cleaned) to remove all visible residue.
- **§1-103** Encapsulation Procedures. The following procedures shall be followed for the encapsulation of ACM:
- (a) All material used for repair or encapsulation of asbestos-containing material shall have a flame spread rating, fireproofing, and smoke characteristics similar to the material being encapsulated. The encapsulate shall not alter the insulating characteristics of the material subject to encapsulation, and shall comply with current fire proofing standards and the encapsulate shall not add excess weight to the material increasing the potential that the material may lose cohesion or adhesion.
- (b) Loose or hanging asbestos-containing materials shall be removed in accordance with the requirements of §1-102: "Disturbance, Handling, and Removal."
- (c) Only pigmented (non-transparent) encapsulants shown to be ratable as acceptable or marginally acceptable on the basis of Battelle Columbus Laboratory test procedures and rating requirements developed under the 1978 USEPA contract shall be used for encapsulation.
 - (d) The encapsulant solvent or vehicle shall not contain a volatile hydrocarbon.
- (e) Latex Paint with solids content greater than 15 percent may be used as an encapsulant only as follows:
 - (1) as a lockdown sealant for coating all non-metallic surfaces, or
 - (2) for sealing of cementitious ACM.
- (f) Encapsulants shall be field tested prior to use by applying each to a small area to determine suitability of the material to be encapsulated.
 - (1) Testing is to occur only after the isolation barriers are in place.
 - (2) Testing shall be by the USEPA method specified in the appendix of "Guidelines for the Use of Encapsulants on Asbestos-Containing Materials" (June, 1981) or ASTM Standard Test Method E736-80. The encapsulated materials shall achieve a cohesive/adhesive strength of 100 lb/ft perpendicular to the surface.
- (g) Application of bridging encapsulants over ACM shall provide the manufacturer's specified number of inches or minimum dry film thickness.
- (h) A different color for each coat of encapsulant (per manufacturer's specifications) shall be used.
- (i) Penetrating encapsulants shall be applied to penetrate existing asbestos-containing materials to the substrate. During treatment with a penetrating encapsulant, selected random core

samples of the asbestos-containing materials shall be removed to check the depth of penetration. The resulting space shall be treated as outlined (in subdivision (a)) above and re-encapsulated.

- (j) Encapsulants shall be applied using airless spray equipment.
 - (1) Spraying shall occur at the lowest pressure range possible to minimize fiber release from encapsulant impact at the surface. It shall be applied with a consistent horizontal or vertical motion.
 - (2) Each subsequent coat of encapsulant shall be applied at a right angle to the preceding coat application or per manufacturer's specifications.
- (k) Encapsulated asbestos-containing materials shall be identified (e.g. using labels, signs or color coding) in order to warn building maintenance personnel in the event encapsulated materials must be disturbed.
 - (l) The following maintenance procedures are recommended:
 - (1) A periodic inspection and maintenance program, consisting of an inspection at least annually to check for damage to all encapsulated surfaces. Recoating and repairs are to be performed according to procedures in this section.
 - (2) Maintenance of records by the building owner, on the locations and condition of the encapsulated material and on alteration, renovation, modification, or other procedures that resulted in disturbance of the encapsulated material.
 - (3) When conditions change and encapsulation is no longer an appropriate method, additional abatement methods should be conducted.
- **§1-104 Enclosure Procedures.** The following procedures shall be followed for the enclosure of ACM:
- (a) Loose and hanging asbestos-containing materials that may be disturbed during the installation of hangers or other support/framing materials for the enclosure shall be removed by wet methods in accordance with §1-102: "Disturbance, Handling, and Removal".
- (b) After installation of hangers, brackets or other enclosure supports and before installation of enclosure materials, damaged areas of fireproofing/thermal insulation shall be repaired using a replacement material.
- (c) Utilities' service components shall be lowered or removed as necessary and reinstalled in a manner which permits proper utilization and does not disturb the integrity of the enclosures.
- (d) Enclosed asbestos-containing materials shall be identified (e.g., using a sign, label, or color coding) in order to warn building maintenance personnel in the event that the enclosure must be disturbed.

- (e) The following maintenance procedures are recommended:
 - (1) A periodic inspection and maintenance program, consisting of an inspection at least annually to check for damage to all enclosed surfaces. Re-enclosure and repairs are to be performed according to NYC Work Site Procedure regulations.
 - (2) Maintenance of records by the building owner, on the locations and condition of the enclosed material and on alteration, renovation, modification, or other procedures resulting in disturbance of the enclosed material.
 - (3) When conditions change and enclosure is no longer an appropriate method of asbestos abatement, additional abatement methods should be conducted.
- **§1-105** Glovebag Procedures. The following procedures shall be followed during the conduct of abatement activities:
- (a) Glovebag procedures shall be done using commercially available glovebags of 6-mil clear plastic, appropriately sized for the project. Glovebag procedures may only be used in conjunction with the full containment of the work area (see §1-81) or the tent procedure (see §1-106). Glovebags may not be shifted and shall not be moved from the initial surface to another surface, or reinstalled on the initial surface once removed.
 - (b) The glovebag procedure shall be performed in accordance with the following:
 - (1) All necessary tools and materials shall be brought into the work area before the glovebag procedure begins.
 - (2) Air monitoring shall be conducted in accordance with §§1-31 through 1-45.
 - (3) Glovebag procedures shall be conducted by workers specifically trained in glovebag procedures and equipped with appropriate personal protective equipment.
 - (4) The insulation diameter worked shall not exceed one half the bag working length above the attached gloves.
 - (5) The ACM within the secured glovebag shall be wetted with amended water prior to stripping.
 - (6) The bag shall be attached over duct tape which has been placed securely around the insulation, forming a smooth seal. The bag shall be securely attached to the insulation in a manner to prevent air transfer.
 - (7) After placement, each glovebag must pass a smoke test. The glovebag shall be placed under negative pressure utilizing a HEPA vacuum, and a smoke tube shall then be aspirated to direct smoke at all seams and seals from outside the glovebag. Any leaks detected by the smoke test shall be duct taped airtight.

- (8) If the insulation adjacent to the section which will be worked on is damaged, or if the insulation terminates or is jointed or contains an elbow adjacent to the work section, the adjacent insulation shall be wrapped in fire retardant 6-mil polyethylene sheeting and sealed airtight with duct tape.
- (9) After the insulation has been removed, the surface shall be sprayed with amended water and brush-scrubbed to remove all visible ACM. The surface, the interior of the bag, the insulation and the tools shall then be sprayed with amended water. The enclosed volume shall be misted and time allowed for the mist to settle out before breaking the seal to remove the glovebag.
- (10) Any insulation ends created by this procedure shall be:
 - (i) sealed with encapsulant prior to bag removal, or
 - (ii) thoroughly wetted before bag removal and sealed with wettable cloth end caps and spray glue or any combination of these materials immediately following bag removal.
- (11) The tool pouch shall be separated from the bag prior to disposal by twisting it and the wall to which it is attached several times, and taping the twist to hold it in place, thus sealing the bag and the pouch which are severed at the midpoint of the twist. Alternatively, the tools can be pulled through with one or both glove inserts, thus turning the gloves inside out. The glove(s) is/are then twist sealed forming a new pouch, taped and several mid-seal forming two separate bags.
- (12) A HEPA vacuum shall be used for evacuation of the glovebag in preparation for removal of the bag from the surface for clean-up in the event of a spill, and for post project clean-up.
- (13) With the glovebag collapsed and the ACM in the bottom of the bag, the bag shall be twisted several times and taped to seal that section during bag removal.
- (14) A 6-mil plastic bag shall be slipped around the glovebag while it is still attached to the surface. The bag shall be detached from the surface by removing the tape or cutting the top with blunt scissors.
- (15) The asbestos-containing waste, the clean-up materials, and protective clothing shall be wetted sufficiently, double-bagged minimizing air content, sealed separately, and disposed of in conformance with §§1-93 and 1-102 of this chapter.
- (c) Reserved.
- (d) Glovebag procedures may only be utilized as part of a large or small asbestos project within full containment as set forth in section 1-81 of this chapter, or inside a tent constructed in accordance with section 1-106 of this chapter.

§1-106 Tent Procedures. Tent Procedures shall be conducted as follows:

- (a) Tent procedures shall be limited to the removal of less than 260 linear feet and 160 square feet of ACM and shall not result in disturbance of ACM during tent erection. Tent procedures may be used as part of a large asbestos project only as provided for in section 1-81(f) or in conjunction with the glovebag procedure set forth in section 1-105 of these rules. Multiple tent enclosures may be used as part of a large asbestos project only in conjunction with the use of the glovebag procedure.
- (b) Tent procedures shall be accomplished in a constructed or commercially available fire retardant plastic tent, plasticizing and sealing all surfaces not being abated within the tent periphery forming an enclosure. The tent shall be of fire retardant 6-mil plastic at a minimum, with seams heat-sealed, or double-folded, stapled and taped airtight and then taped flush with the adjacent tent wall. This is a single use barrier that shall not be reused once dismantled or collapsed.
- (c) There shall be an airlock at the entrance to the tent, unless there is an attached worker or waste decontamination system.
- (d) Asbestos handlers involved in the tent procedure shall wear personal protective equipment as specified in §1-51(c), plus a second disposable suit. All street clothes shall be removed and stored in a clean room within the work site. The personal protective equipment with two disposable suits shall be used for installation of the tent and throughout the procedure if a decontamination unit with a shower is not contiguous to the work area. If a decontamination unit (with shower and clean room at a minimum) is contiguous to the work area, only one disposable suit shall be required; in this case, prior to exiting the tent the worker shall HEPA vacuum and wet clean the disposable suit.
- (e) The tent shall be attached to the surface to produce an airtight seal except for an appropriate section to allow for make-up air into the tent.
- (f) Negative pressure ventilation equipment shall be used to continuously exhaust the enclosed area as specified under §1-91, Engineering Controls.
 - (g) Removal of ACM shall be by wet methods in accordance with §1-102.
 - (h) ACM removed shall be placed in a leak-tight container without dropping it.
 - (i) Upon completion of abatement, and prior to tent collapse, the enclosed surfaces shall:
 - (1) be wet cleaned using rags, mops or sponges; and
 - (2) be permitted sufficient time to dry, prior to HEPA vacuuming all substrates; and
 - (3) be lightly encapsulated to lockdown residual asbestos.
- (j) Upon barrier disturbance, loss of engineering controls, or termination of tent usage, the tent and the enclosed surfaces shall be treated according to subdivision (i) above.

- (k) The bagged waste shall be wet cleaned or HEPA vacuumed and then transferred outside the tent, double bagged, and appropriately handled prior to disposal.
- (l) The outer disposable suit (if 2 suits are worn) shall be HEPA vacuumed in the tent prior to exiting. The outer disposable suit shall be removed in the airlock and a clean suit shall be worn over the inner suit. The workers shall immediately proceed to a shower at the work site. The inner disposable suit and respirator shall be removed in the shower after appropriate wetting. The disposable clothing shall be disposed of as asbestos-containing waste material. The workers shall then fully and vigorously shower with supplied liquid bath soap, shampoo, and clean dry towels.
- (m) The negative pressure ventilation equipment shall be used to filter a minimum of 4 volume changes through the tent after completion of abatement but prior to collapse of the tent/barrier. All required air monitoring must be successfully completed before the tent/barrier is collapsed.
- (n) The tent shall be collapsed inward, enclosing the contaminated clothing. This contaminated material shall be disposed of in another plastic bag. The HEPA vacuum shall be decontaminated and sealed.
- (o) Glovebag procedures for removal of material within the tent for any sized project shall follow the rules set forth in §1-105.

§ 1-107 Foam Procedure for Roof Removal

- (a) These procedures apply only to the removal of asbestos-containing roofing material (ACRM) from exterior roof surfaces. The work area on the roof shall be cordoned off with clearly visible barriers such as caution tape, and only authorized persons shall have access. All sections of these rules shall be followed in conjunction with this section with the exception of §1-81(m), §1-81(p), §1-91, §1-102(b), §1-112(d), and §1-112(e).
- (b) The foam or viscous liquid shall be non-toxic, shall not require special respiratory protection for handling, and shall not affect the handling and disposal of the waste.
- (c) The foam or viscous liquid shall coat and maintain a stable blanket (minimum 1" thickness) for the duration of the removal process and shall leave an identifiable colored residue when it dissipates.
- (d) The foam or viscous liquid shall wet the ACRM. The ACRM shall be kept wet through the bagging process.
 - (e) Persons entering the work area shall wear correctly-fitting, good traction rubber boots.
- (f) Abatement shall not be carried out during adverse weather conditions (e.g. precipitation, high winds, ambient temperature below 32 degrees Fahrenheit, etc.).
- (g) The worker decontamination unit may be attached to each work area at an entry/exit from each work area in accordance with section 1-82, or may be remote, in which case the work

area shall be equipped with an airlock at the entrance. In addition to the shower head(s), the shower room shall be equipped with a flexible hose for waste decontamination for removal of less than 1,000 square feet of ACRM. For 1,000 square feet or more of ACRM removal, a separate waste decontamination facility as per section 1-83 shall be located at an entry/exit from each work area. Remote holding areas for the asbestos containing waste shall comply with Title 16, Chapter 8, Rules of the City of New York (16 RCNY 8 et seq.)

- (h) Movable objects shall be removed from the work area, or kept in place and wrapped in one sheet of fire retardant 6 mil plastic sheeting.
- (i) Provisions shall be made to ensure a safe and adequate air supply to affected building(s). All vents, skylights, air intakes, windows and doors opening onto the roof, and all other openings shall be sealed with 2 layers of fire retardant 6 mil plastic or fitting with HEPA-filters when appropriate. Temporary extensions may be installed to a height of 10 feet to ensure adequate air exchange instead of sealing vents, air intakes, etc, with 2 layers of plastic or HEPA-filters. Drains may be equipped with 5 micron filtering system in lieu of being sealed.
- (j) Fixed objects including perimeter walls, bulkheads, cooling towers, ducts and other rooftop appurtenances shall be covered in one sheet of fire retardant 6 mil plastic up to a height of at least six feet
- (k) Prior to actual removal, the built-up roofing shall be blanketed and wetted with a minimum 1" coating of the acceptable foam or viscous liquid which shall be maintained for the duration of the removal until the material is bagged. The foam or viscous liquid shall be confined to the work area.
- (l) Power tools used to drill, cut into, or otherwise disturb the ACRM shall be equipped with HEPA-filtered local exhaust ventilation and operated to prevent potential fiber release.
- (m) Clean-up procedures shall include the removal and bagging of ACRM, the removal of all visible accumulations of asbestos containing waste, and the removal of all excess foam or similar viscous liquids. Following the removal of all debris, the work area shall be thoroughly wet cleaned.
- (n) The work area shall be allowed to dry completely before the visual inspection is conducted. The project monitor and asbestos handler supervisor shall confirm the absence in the work area of ACM, asbestos-containing waste or debris, and foam or other viscous liquid.
 - (o) Upon successful visual inspection, all installed plastic sheeting shall be removed.
- (p) Air monitoring shall be conducted in accordance with the relevant provisions of subchapter D of these rules.

§1-108 Foam/Viscous Liquid Use in Flooring Removal

(a) These procedures only apply to the removal of surface flooring material including vinyl asbestos floor tiles (VAT), ACM floor coverings (e.g., linoleum) and associated mastics and

adhesives, where the only ACM being abated in the work area is flooring material. All sections of these rules shall be followed in conjunction with this section with the exception of §1-81(m), §1-81(p), §1-91(c), §1-91(h), §1-102(b), §1-112(d), and §1-112(e).

- (b) The foam or viscous liquid shall be non-toxic, shall not require special respiratory protection for handling, and shall not affect the handling and disposal of the waste.
- (c) The foam or viscous liquid shall coat and maintain a stable blanket (minimum 1" thickness) for the duration of the removal process and shall leave an identifiable colored residue when it dissipates. The acceptable foam or viscous liquid shall be maintained for the duration of the removal until the material is bagged.
- (d) The foam or viscous liquid shall coat and wet the ACM. The ACM shall be kept wet through the bagging process.
 - (e) Persons entering the work area shall wear correctly-fitting, good-traction rubber boots.
- (f) Baseboards and wall surfaces up to a minimum height of four feet above the floor shall be covered with a layer of fire retardant 6-mil plastic sheeting. If hand power tools are used during the abatement, wall surfaces shall be covered with a layer of 6-mil polyethylene sheeting to a minimum height of six feet.
- (g) Negative air pressure ventilation shall be provided to allow make-up air into the work area, and the air outlet from the work area shall be at or near the floor level.
- (h) Clean-up procedures shall involve removal and bagging of the ACM, of visible accumulations of asbestos containing waste, and of all traces of foam or similar viscous liquid. Following the removal of all debris, the work area shall be thoroughly wet cleaned and HEPA-vacuumed.
- (i) The work area shall be allowed to dry completely before the visual inspection is conducted. The project monitor and asbestos handler supervisor shall confirm the absence in the work area of ACM, asbestos-containing waste or debris, and foam or other viscous liquid.
- (j) Upon successful visual inspection, plastic sheeting shall be removed from baseboards and wall surfaces. Isolation barriers shall remain in place.
- (k) Air monitoring shall be conducted in accordance with the relevant provisions of subchapter D of these rules.

§ 1-109 Abatement from Vertical Exterior Surfaces

This section shall apply to projects involving the abatement of asbestos-containing materials from the vertical exterior surfaces (and associated horizontal surfaces, e.g. coping stones on top of a parapet wall) of a building or structure, including but not limited to the following materials:

Caulking or glazing compounds
Asphaltic mastic or tar (e.g., flashing on parapet walls)

Cement siding or shingles (including Transite)
Paints
Sealants for coping stone caps or clay roofing tiles

All applicable sections of these rules shall be followed in conjunction with this section except sections 1-81(p), 1-91, and 1-112(d, e, g, and h).

- (a) The work area shall be prepared as follows:
 - (1) The entire surface to be abated and ground-level perimeter shall be considered the work area unless partitions and warning tape are used to define the work area, except that if the horizontal surface below the surface to be abated is not the ground (e.g., surface to be abated is inside parapet wall on roof), the horizontal surface underneath the abatement shall be considered the work area, not the ground.
 - (2) A restricted area shall be established using warning tape extending at least 25 feet from the affected areas of the building or to the nearest vertical obstruction or the curb.
 - (3) The restricted area may be entered only by certified workers or authorized visitors.
 - (4) Before plasticizing, the restricted area shall be inspected for ACM debris and, if necessary, pre-cleaned using HEPA vacuums and wet methods.
 - (5) All openings to the building or structure's interior which are within 25 feet of the affected ACM shall be closed and made airtight.
 - (6) Scaffolding erected to access the ACM shall be constructed, maintained, and used in accordance with applicable federal, state, and city laws.
 - (7) Elevated platforms being used to access the affected ACM shall be plasticized with two layers of fire-retardant 6-mil plastic, which shall extend up from the platform to at least the height of the mid-rail on three sides, and shall be attached directly to the building just below the surfaces under abatement.
 - (8) The ground-level restricted area shall be cleared of all moveable objects and plasticized with two sheets of fire-retardant 6-mil plastic, which shall be extended one foot up the side of the building. The plasticized area shall be twenty-five feet wide, or to the curb. This plastic shall be cleaned, replaced, and disposed of as asbestos waste at the end of each shift.
 - (9) Sidewalk bridges in the restricted area shall be covered with two layers of fire-retardant 6-mil plastic, placed over and secured to the bridge, spread across the full width, draped over the side to ground level, and extended to a width of at least thirty feet.
- (b) A worker/waste decontamination system shall be constructed within the restricted area.

(c) Cleanup Procedure

- (1) The stripped substrate shall be HEPA vacuumed and wet-wiped.
- (2) A visual clearance inspection shall be conducted by the asbestos handler supervisor and project monitor after the work area dries, to ensure the absence of ACM residue or debris in the work area

- (3) After the inspection is completed, the warning tapes and barriers may be removed.
- (4) The clearance inspection shall be documented in the log and the project air sampling log.
- (d) Air monitoring shall be conducted in accordance with the relevant provisions of subchapter D of these rules.
- (e) Abatement shall not be performed under this section during adverse weather conditions (e.g. precipitation, high winds, ambient temperatures below 32 degrees Fahrenheit, etc.).
- (f) Power tools used to drill, cut into, or otherwise disturb ACM shall be equipped with HEPA-filtered local exhaust ventilation and operated to prevent potential fiber release.
- **§1-110 Controlled Demolition with Asbestos in Place.** (a) A building or structure may be demolished with asbestos in place only if the building is in imminent danger of collapse as set forth in section 28-215.1 of Title 28 of the Administrative Code and/ or 56 NYCRR 11.5(c).
 - (b) A copy of the condemnation letter shall be provided to DEP.
 - (c) The demolition shall be performed in accordance with section 28-215.1 of Title 28 of the Administrative Code and/or 56 NYCRR 11.5 (c).

Part 5 Clean-up Procedures

- §1-111 Preliminary Clean-up Procedures §1-112 Additional Clean-up Procedures (Final)
- **§1-111 Preliminary Clean-up Procedures.** The following clean-up requirements shall be followed during the conduct of abatement activities on asbestos projects:
 - (a) (1) All waste generated shall be bagged, wrapped or containerized immediately upon removal. The personal and waste decontamination enclosure systems and floor and scaffold surfaces shall be HEPA vacuumed and wet cleaned at the end of each work shift at a minimum
 - (2) Visible accumulations of asbestos-containing waste material shall be containerized utilizing non-metallic dust pans and non-metallic squeegees or HEPA vacuums.
 - (3) Metal shovels shall not be used to pick up or move accumulated asbestoscontaining waste material or any other debris in the vicinity of isolation or surface barriers.

- (b) The waste decontamination enclosure system shall be wet cleaned twice using wet cleaning methods upon completion of waste removal. When the worker decontamination enclosure shower room alternates as a waste container wash room, the shower room shall be washed immediately with cloths or mops saturated with a detergent solution prior to wet cleaning.
- (c) The worker decontamination enclosure system shall be wet cleaned/HEPA vacuumed, as appropriate, after each shift change and meal break.
- (d) Excessive water accumulation or flooding in the work area shall require work to stop until the water is collected and disposed of properly.
- **§1-112 Additional Clean-up Procedures (Final).** Additional clean-up procedures shall be performed in the order set forth below prior to commencement of clearance air monitoring.
- (a) After removal of visible accumulations of asbestos-containing waste material, a HEPA vacuuming shall be performed on all surfaces. To pick up excess water and gross saturated debris, a wet-dry shop HEPA vacuum, dedicated to asbestos abatement, may be used.
 - (b) All surfaces in the work area shall be wet cleaned (first cleaning).
- (c) A thin coat of lockdown encapsulant shall be applied to all surfaces in the work area which were not the subject of removal or abatement, including the cleaned layer of the surface barriers, but excepting sprinklers, standpipes, and other active elements of the fire suppression system.
- (d) After the first cleaning, the work area shall be vacated for 12 hours to allow fibers to settle.
- (e) The cleaned and encapsulated layer of the surface barriers shall be removed from the walls and floors.
- (f) All objects and surfaces in the work area shall be HEPA vacuumed and wet cleaned a second time.
 - (g) After the second cleaning, the work area shall be vacated for 4 hours.
- (h) The remaining plastic barriers shall be removed from the walls and floors. All objects and surfaces in the work shall be HEPA vacuumed and wet cleaned a third time.
- (i) As a prerequisite to commencement of clearance air monitoring, a thorough visual inspection shall verify the absence of asbestos-containing waste material (e.g. dust).
- (j) All containerized waste shall be removed from the work area through the decontamination enclosures and the holding area.

- (k) All tools and equipment shall be removed from the work area and decontaminated in the waste decontamination enclosure system. Cloths, mops, and other cleaning aids shall be disposed of as asbestos-containing waste material.
- (l) After successful clearance air monitoring (see §1-31 et seq.), the isolation barriers shall be removed in conjunction with the use of a HEPA vacuum.
- (m) Within 21 days of the completion of all steps set forth above, including successful clearance air monitoring, a project monitor's report shall be submitted to DEP on a DEP-approved form. This report shall be based on an inspection performed after the completion of all steps listed in this section, and shall not be based on the visual inspection performed prior to the commencement of clearance air monitoring. The project monitor who prepares the report shall be independent of the abatement contractor. If a project is being performed on multiple floors of a building, a separate project monitor's report may be submitted as each floor is completed. Failure to comply with this subdivision shall be the responsibility of the building owner.

Subchapter G

Pre-Demolition Abatement Activity Procedures

- 1. Applicability
- 2. Work Procedures

Part I Applicability

§1-120 Applicability of Regulations to Pre-Demolition Abatement Activities. The following regulations shall apply to pre-demolition abatement activities:

§§1-01 through 1-61	General Regulations
1-82	Worker Decontamination Enclosure System
1-83	Waste Decontamination Enclosure System
1-91 through 1-94	Work Place Procedures
1-102	ACM Disturbance, Handling and Removal Procedures
1-105	Glovebag Procedure
1-106	Tent Procedure
1-107	Foam Procedure for Roof Removal
1-108	Foam/Viscous Liquid Use in Flooring Removal
1-109	Abatement from Vertical Exterior Surfaces
1-120 through 1-128	Pre-Demolition Abatement Activity Procedures

Part II Work Procedures

§ 1-125	Work Area Preparation
§ 1-126	ACM Procedures: Order of Work
§ 1-127	Clean-Up Procedures During Abatement
§ 1-128	Clean-Up Procedures: Preparation for Clearance
	Air Monitoring


- **§ 1-125 Work Area Preparation.** The following work area preparation shall be followed during the conduct of pre-demolition abatement activities:
- (a) Prior to the start of abatement activities, the building owner or designated representative shall post a general notification at all main entrances to the structure. Postings of this notification shall be in English and Spanish, at eye level in a conspicuous well-lit place that can be viewed by the public without obstruction. Information provided in the notification shall include contractor, project location, that the project is regulated by NYC DEP, and the Call Center "311" for government information and services. The notice shall have the following heading: NOTICE OF ASBESTOS ABATEMENT, in a minimum of 2 inches sans serif, gothic or block style lettering, with the balance of the lettering of the notice to be of the same type lettering in a minimum of 1 inch size. The notification shall be posted throughout all abatement activities.
 - (b) The building shall be vacated prior to the start of abatement activities.
- (c) Electric power to all work areas shall be shut down and locked out. Safe temporary power and lighting shall be provided in accordance with all applicable NYC Code(s) and Regulations. Existing light sources (e.g., house lights) shall not be utilized. All power to a work area shall be brought in from outside the area through ground- fault interrupter at the source.
- (d) The worker decontamination enclosure system shall be installed or constructed prior to plasticizing the work area and before disturbing ACM. The waste decontamination enclosure system shall be installed or constructed prior to commencement of abatement. The area in which there systems are located shall require HVAC system isolation and plasticizing of electrical outlets and equipment that are within 6 inches of floor level.
- (e) Heating, Ventilation and Air Conditioning (HVAC) System shall be shut down and locked out. Isolation barriers shall be installed to prevent interior duct work contamination.
 - (f) Abatement shall not commence until work place preparation has been completed.
- (g) Methods that raise dust, such as sweeping or vacuuming with equipment not equipped with HEPA filters, are prohibited.
- (h) Objects which can be removed from the work area prior to abatement without disturbing ACM shall be pre-cleaned using HEPA-filtered vacuum equipment and/or wet cleaning.

- (i) The isolation barriers (i.e. sealing off of all openings, including but not limited to windows, corridors, doorways, barriers, skylights, ducts, grills, diffusers, and any other penetrations of the work areas) shall be installed with 2 layers of fire retardant 6-mil plastic sheeting separately sealed with tape. All seams of HVAC or other system components that pass through the work area shall also be sealed. Chimney effects in stacks, columns, flues, shafts, double- walled enclosures, etc., that impact the work area, shall be eliminated by sealing the accesses with solid material covered with a double layer of 6-mil plastic sealed with tape.
- (j) Cinderblock and porous construction materials shall be covered with one layer of fire retardant 6- mil plastic sheeting, sealed at edges and seams.
 - (k) Flooring within the area shall be water-tight.
- (l) Suspended ceiling tiles and T-grid components in proximity to ACM shall remain in place until the work area has been fully prepared as outlined in this section and electrical and HVAC systems have been shut down. Contaminated suspended ceiling components shall be removed prior to abatement and treated with a penetrating encapsulant.
- (m) Required means of egress, including emergency and fire exits, shall be maintained at all times during abatement activities except as otherwise provided pursuant to section 3303 of the New York City Building Code. Exits shall be checked daily against blockage or impediments to exiting.
- (n) Entrances to the work area that will be used for worker entry or emergency exits shall be locked against unauthorized entry.
 - (o) Elevators running through the work area shall conform to the following:
 - (1) The elevator door in the work area shall be enclosed with conventional 2 x 4 stud framing, covered with 3/8" fire rated plywood sheeting and sealed at all edges and seams. The barrier shall be covered and lapped for 8 inches with two layers of fire retardant 6-mil plastic sheeting adhered individually with edges taped for airtightness.
 - (2) Elevators not remaining in service shall have the fuses removed and the power switch locked in the open position.
 - (3) Elevators that remain in service shall conform to the following additional procedures to minimize the piston effect that results:
 - (i) Elevator control shall be modified to bypass the work area.
 - (ii) A final larger layer of fire retardant 6-mil plastic sheeting is to be taped airtight but with slack forming a larger perimeter diaphragm. Air leakage across the barrier shall be corrected upon discovery, and the elevator shaft shall be checked for airborne asbestos contamination.
 - (iii) This system shall be smoke tested daily.

- (p) Adequate toilet facilities shall be provided in the vicinity of the clean room external to the work place. Where such facilities do not exist, portable service shall be provided.
- **§1-126 ACM Procedures: Order of Work.** No ACM removal shall be performed in a building concurrently with the full demolition of such building or with the removal of one or more stories of such building, except as otherwise provided in these rules pursuant to Sections 1-03 and 1-26. This subsection shall not apply to emergency work being performed pursuant to article 215 of chapter 2 of title 28 of the administrative code.
- **§1-127 Clean-up Procedures during Abatement.** The following clean-up procedures shall be followed during conduct of pre-demolition abatement:
 - (a) (1) All waste generated shall be bagged, wrapped, or containerized immediately upon removal. The personal and waste decontamination enclosure systems shall be HEPA vacuumed and wet cleaned at the end of each work shift at a minimum.
 - (2) Visible accumulations of asbestos-containing waste material may be containerized utilizing rubber dust pans and rubber squeegees or HEPA vacuums. Metal shovels may also be used EXCEPT in the vicinity of isolation or surface barriers which could be perforated by these tools.
- (b) The waste decontamination enclosure system shall be wet cleaned twice using wet cleaning methods upon completion of waste removal. When the worker decontamination enclosure shower room alternates as a waste container wash room, the shower room shall be washed immediately with cloths or mops saturated with a detergent solution prior to wet cleaning.
- (c) The worker decontamination enclosure system shall be wet cleaned/HEPA vacuumed, as appropriate, after each shift change and meal break.
- (d) Excessive water accumulation or flooding in the area shall require work to stop until the water is collected and disposed of properly.
- **§1-128** Clean-up Procedures: Preparation for Clearance Air Monitoring. The following final clean-up procedures for pre-demolition abatement shall be performed prior to commencement of clearance air monitoring:
- (a) All visible accumulations of asbestos-containing waste material shall be removed and containerized. Metal shovels may be used to pick up or move accumulated waste EXCEPT in the vicinity of plastic sheet isolation and surface barriers which could be perforated by these tools. The areas around the plastic sheet isolation barriers shall be cleaned of visible accumulations utilizing rubber dust pans and rubber squeegees. To pick up excess water and gross wet debris, a wet-dry shop HEPA vacuum dedicated to asbestos abatement may be used.
- (b) All containerized waste shall be removed from the work area through the decontamination enclosures and the holding area.

- (c) All surfaces in the work area shall be wet cleaned using rags or mops. After allowing sufficient time for drying of the work area, HEPA vacuums shall be used to thoroughly clean all surfaces after gross clean-up.
- (d) Where porous construction materials or cinder block-like materials have been plasticized for surface barrier containment, the plastic sheeting shall be cleaned as in subdivision (c) above, then sprayed with a lockdown encapsulant and removed when dry.
- (e) All surfaces in the work area which were not the subject of removal or abatement shall be sprayed with a lockdown encapsulant, which upon drying will not dissolve upon rewetting. Sufficient time for drying shall be allowed.
- (f) All tools and equipment shall be removed from the work area and decontaminated in the equipment decontamination enclosure system.
- (g) After successful clearance air monitoring (see §1-31 et seq.) the isolation barriers shall be removed in conjunction with the use of a HEPA vacuum.
- (h) Within 21 days of the completion of all steps set forth above, including successful clearance air monitoring, a project monitor's report shall be submitted to DEP on a DEP-approved form. If a project is being performed on multiple floors of a building, a separate project monitor's report may be filed as each floor is completed.

Large Asbestos Project (Small Asbestos Project Option) Worker Decontamination Enclosure System



Large Asbestos Project (Small Asbestos Project Option) Waste Decontamination Enclosure System





Illustration II

Large Asbestos Project (Small Asbestos Project Option)

Parallel Worker and Waste Decontamination Enclosure Systems









ASBESTOS TECHNICAL REVIEW

A Guide to the New York City Asbestos Regulations

First Edition, October 2009



Department of Environmental Protection

Steven W. Lawitts Acting Commissioner **Department of Buildings**

Robert LiMandri Commissioner New York City Fire Department

Nicholas Scoppetta Fire Commissioner

The Asbestos Technical Review Unit

Contact Information:

Telephone:

(718) 595 - 3048

Email:

ARTSfeedback@dep.nyc.gov

Web:

NYC.gov/dep

DEP Staff:

Krish Radhakrishnan, P.E.

Director

Asbestos Control Program

Steven A. Camaiore, P.E.

Deputy Director

Asbestos Control Program

Carlstien Lutchmedial

Director

Enforcement Unit

Peter Lee Kim

Director

Asbestos Technical Review Unit

DOB Staff:

Marshall A. Kaminer, PE

Borough Commissioner, Staten Island

Bharat Gami, RA

Asbestos Technical Review Unit

TABLE OF CONTENTS

Introduction	1
SECTION 1 Notifying DEP of an Asbestos Project	2
SECTION 2 The New Asbestos Project Notification Form	14
SECTION 3 Maintaining Proper Egress	20



Introduction

In 2009, the City enacted a number of new laws to ensure that asbestos abatement is conducted safely. These laws impact the ways that asbestos projects are filed, approved and inspected, and involve new levels of cooperation among the agencies that oversee asbestos and construction safety: the Department of Environmental Protection (DEP), the Department of Buildings (DOB) and the Fire Department (FDNY).

The purpose of this guide is to explain the new laws and help building owners, builders and abatement contractors working in New York City.

This guide is divided into three sections:

- 1. A review of the entire asbestos abatement process from before filing to after close-out.
- 2. A detailed explanation of the new Asbestos Project Notification (Form ACP7).
- 3. Guidance for contractors about how to maintain proper egress at asbestos abatement/construction sites.

Notifying DEP of an Asbestos Project

The asbestos abatement process has five phases:

- 1. Pre-abatement Activities
- 2. Notifying DEP of an Asbestos Abatement Project
- 3. Project Review
- 4. Conducting Abatement
- 5. Close-out

1. PRE-ABATEMENT ACTIVITIES


The pre-abatement activities begin when you hire a DEP-certified asbestos investigator to survey a building. These investigators are experts at identifying Asbestos Containing Material (ACM) and calculating the square feet and or linear feet of an abatement project. You may conduct an investigation as part of a construction project, or you may just want to know if there is asbestos in your building. Whatever your reason, the investigator's report will determine the amount of ACM.

The asbestos investigator will find that your project is either "Not an Asbestos Project (A)" or an "Asbestos Project (B)."

A. Asbestos Assessment Report (Form ACP5)

If the asbestos investigator finds that less than 10 square feet or 25 linear feet of Asbestos Containing Material (ACM) will be disturbed, the project is considered "Not an Asbestos

Fig. 1: Pre-Abatement Activities



Project." Even though such a project is termed "Not an Asbestos Project," asbestos must still be abated in accordance with all relevant laws. However, there is no need to file any paperwork with DEP for a minor project. The ACP5 could also certify that you're not going to disturb any ACM during your construction job or that the premises is free of any ACM. Once DOB receives the Form ACP5, DOB may proceed with the DOB permitting process.

Note: You must follow all the relevant laws and rules for asbestos abatement even when you remove minor amounts of ACM.

B. Asbestos Project Notification (Form ACP7)

If the asbestos investigator finds that an amount of ACM greater than 10 square feet or 25 linear feet will be disturbed, the job is considered an "Asbestos Project" and you must submit an Asbestos Project Notification (Form ACP7) to DEP. If the asbestos abatement is part of a construction job, DOB will not issue a permit and construction may not begin until you complete the steps outlined in this guidance document and DOB receives a DEP Asbestos Project Completion Form indicating that the abatement is complete.

2. NOTIFYING DEP OF AN ASBESTOS ABATEMENT PROJECT

An asbestos project is defined as the abatement of more than 10 square feet or 25 linear feet of asbestos containing material. Under the law governing asbestos abatement, if you are conducting an asbestos project in New York City, you must notify DEP and follow all its rules and regulations.

The Asbestos Reporting and Tracking System (ARTS)

If you have an "Abatement Project," you will need to fill out an Asbestos Project Notification (Form

ACP7). You can do this by logging on to ARTS, the Asbestos Reporting and Tracking System. ARTS is the new central location for building owners and contractors to manage abatement job notifications. ARTS is accessible from DEP's website (www.nyc.gov/dep) and, in addition to using it to electronically submit an Asbestos Project Notification, you can also use ARTS to request a variance, submit an amendment or print any form submitted to DEP. If you are undertaking an asbestos abatement job that requires a review and permit from the Asbestos Technical Review Unit (A-TRU), you can use ARTS to receive objections and approvals during your permit review.

The online Form ACP7 has been revised, and now features a number of new questions. In addition to questions about the abatement contractor, the asbestos hauler, and the independent air monitor, the new Form ACP7 asks a number of detailed questions about conditions in the abatement work area. You should consult a licensed asbestos abatement contractor to help fill out the form. However, you can begin filling out the Form ACP7 even if you don't know all the information because ARTS allows you to save your applications. That way, even if you can't answer a question, you can save the document and come back to it at another time.

After you submit the Abatement Project Notification online, you are still not ready to begin abatement activities. Every applicant who submits a Form ACP7 must print the ACP7, sign the signature page to attest that everything on the form is truthful, and then obtain signatures from the building owner, the asbestos abatement contractor and the project's independent air monitor. By signing the Form ACP7, the asbestos abatement contractor, building owner or other party is attesting to the accuracy of the information, so they should be sure to read through the application carefully before signing. When all signatures have been obtained, you will be ready to bring the ACP7, including the

signature page and any required feesⁱⁱ to DEP to file your abatement project. DEP will then issue you an "Asbestos Abatement Notice" that must be posted at the workplace.

In some cases, the submission of the Form ACP7 will also involve a review to approve a variance or an Asbestos Work Permit.

Asbestos Variance Application (Form ACP9)

If you believe that you will be unable to comply with all the applicable City and State rules and regulations related to asbestos abatement, you may apply for a variance. You will need to submit an "Asbestos Variance Application" (Form ACP9) along with your Form ACP7. The Form ACP9 can also be completed using ARTS.

Asbestos Work Permit

You will also need to submit additional materials if you need a permit from the Asbestos Technical

Review Unit. The ACP7 has a new section called "Project Details" and your answers to the questions in this section may determine that your project poses certain safety risks. In these cases, the application will need to undergo a review to ensure that you are taking appropriate safety precautions during the abatement. This review, conducted by A-TRU, may sometimes require you to hire a registered architect or professional engineer to create a Work Place Safety Plan to show how you will maintain safety throughout the course of the work. When the review is finished and A-TRU has concluded that the project will meet safety requirements, DEP will issue you an Asbestos Work Permit. That permit must be prominently posted in the entrance of the building where abatement is taking place, with additional copies posted directly outside each permitted asbestos containment area.


As soon as you submit your ACP7 online, an electronic copy of your completed ACP7 will pop up on your computer screen. The first page of



this document will be an instruction sheet. These detailed instructions will tell you, based on your answers on the application, if your project will require an Asbestos Work Permit and what documents you need to submit for your plan review. The instruction page will also show the notification and permit feesⁱⁱⁱ due at the time of submission, which are calculated based on the amount of ACM, if required.

If the instruction sheet indicates that you must submit a Work Place Safety Plan, you must hire a registered architect or professional engineer to help prepare these documents. Then, when you have all the signatures on your signature page and all the accompanying documents you need to submit, you will be ready to bring them to the DEP office.

Fig. 2: Notifying DEP of an Asbestos Project



3. PROJECT REVIEW

The Project Review Section has two parts, 'Inperson Submission' and 'Following Submission':

A. In-person Submission

The submissions counter for the DEP Asbestos Control Program is on the eighth floor of the DEP headquarters, located at 59-17 Junction Boulevard in LeFrak City, Queens.


When you present your signed Form ACP7 and filing fee to the DEP clerk, the signature page will be scanned to confirm that it corresponds to the Form ACP7 that was submitted online.

At this point, if you have the need to make any changes to the start date, end date or abatement method for this abatement project, the clerk will print a Correction Form that can be signed by any of the signatories to the ACP7. The authorized clerk can then make those changes in the ACP7.

Note: An expediter or courier will be considered an agent of a signatory and allowed to sign a Correction Form only if they have a letter signed by an ACP7 signatory authorizing them to sign the Correction Form.

Once the signature sheet has been confirmed, one of four things may occur:

I. If the application doesn't require an Asbestos Work Permit or a variance, the DEP clerk will provide you with a stamped copy of the Form ACP7, which includes the TRU tracking number (this number is used by DEP to identify the ACP7 and all accompanying documentation with the particular job) and a copy of the Asbestos Abatement Notice. The Asbestos Abatement Notice must be posted centrally in the entranceway or lobby of the building where abatement is taking place and you must begin abating asbestos by the start



date on the Notice.

II. If the abatement job requires an Asbestos Work Permit for some (but not all) of the asbestos work areas listed in the ACP7, you must provide the DEP clerk with the documentation required for the A-TRU review. The clerk will then provide you with a stamped copy of the Form ACP7, printed with a TRU tracking number, a receipt confirming DEP's receipt of the supporting documents for A-TRU review and a copy of the Asbestos Abatement Notice. The Asbestos Abatement Notice must be posted at the workplace. You must begin abating asbestos in the work areas where A-TRU review is not required by the start date on the Notice. Once the A-TRU review is finished and you have an Asbestos Work Permit, you may begin work in the areas where the permit is required. (If you did not bring the correct documentation for A-TRU review, the receipt will note that A-TRU review remains pending until you provide the documents.)


- III. If the abatement job requires an Asbestos Work Permit for all the asbestos work areas listed in the ACP7, the DEP clerk will collect the documentation required for the A-TRU review. The clerk will then provide you with a receipt confirming DEP's receipt of the documentation for A-TRU review and a stamped copy of the Form ACP7 with a TRU tracking number added. DEP will not provide you with a copy of the Asbestos Abatement Notice until the Asbestos Work Permit is granted, since there is no work that may commence until after the A-TRU review takes place. (If you did not bring the correct documentation for A-TRU review, DEP will not accept the ACP7.)
- IV. If the abatement job requires a variance, the clerk will direct you to a DEP reviewer for initial variance review. Unlike the fee for the ACP7 and the A-TRU review, the variance fee cannot be determined until the variance application has been reviewed. Therefore, you must meet with a DEP reviewer, who will perform a cursory review of the variance application to determine if the submission is complete for all technical aspects. Once the DEP reviewer is satisfied that the variance submission is completed, he or she will advise the clerk to enter the appropriate fee into the ARTS system and direct you back to the clerk to pay the fee for the variance.

B. Following Submission

- I. If you leave DEP with an Asbestos Abatement Notice, you must post the Asbestos Abatement Notice and work must commence on the start date in any work areas that do not require a variance or A-TRU review.
- II. If all the required documents have been properly submitted, the review period for a variance or Asbestos Work Permit will take approximately two to three weeks. You will receive the results of your Request for

- Variance and/or Asbestos Work Permit via a message sent to your email account advising you to log on to your online ARTS account (or by mail if you have requested it):
- If the Request for Variance and/or Asbestos Work Permit has been approved, a copy of your permit will be sent electronically to your ARTS account. You will enter the start date (which must be at least three days after the date of receipt) and you will be able to print the variance, which must be posted at the workplace, or the Asbestos Work Permit, which must be posted in the entrance of the building where abatement is taking place with additional copies hanging directly outside each permitted asbestos containment area.
- If the Asbestos Technical Review Unit has any objections or questions concerning your variance and/or Asbestos Work Permit, you will be notified via your email (or by mail if you have requested it). You can respond to objections via fax or email, or you can schedule an appointment to speak with the A-TRU reviewers if you want detailed clarification about how to resolve the objections.
- III. If you did not submit all the materials for your Request for Variance or Asbestos Work Permit, it will be noted on your receipt, as well as in an email to you, that review is delayed pending the complete submission of all supporting material. Asbestos Work Permit and/or Variance approval can take up to two or three weeks, but these reviews will not begin until you have submitted all the necessary documentation (even if you have already received your Asbestos Abatement Notice and have already started work on nonvariance, non-A-TRU jobs).

Fig. 3: Project Review



4. CONDUCTING ABATEMENT

A. Inspections

Once abatement has begun, your abatement project may be inspected by DEP. Inspectors ensure that the asbestos abatement and all related work is being conducted safely and according to law.

DEP inspectors will verify that abatement work taking place matches the work described in your submitted drawings and paperwork (including your Form ACP7, Variance Approval and Asbestos Work Permit), and that it conforms to the City rules governing abatement. Therefore, a copy of your Asbestos Abatement Notice must be posted at the workplace, your Asbestos Work Permit must be posted at the building entrance and outside every workplace and Variance Approval must be posted outside every workplace.

If permits, drawings and/or paperwork are missing from the work site, or the DEP inspector finds that your project should have received an Asbestos Work Permit or Variance Approval but didn't, the inspector can order the abatement contractor to cease all abatement work. The

contractors and building owners may face penalties or even criminal prosecution for falsifying the Form ACP7.

Furthermore, DEP Inspectors trained in the fundamentals of Building and Fire Code safety inspections will be checking that abatement sites comply with fire- and life-safety requirements like maintaining egress and fire-protection systems.

B. Amendments


Modification or deviation from the information


provided on any notification submitted to DEP shall immediately be reported to DEP via your ARTS account using a Form ACP8.

If any of the following items change after the ACP7 has been submitted, you must submit a signed ACP8 to DEP:

- 1. Asbestos contractor
- 2. Third party air monitor
- 3. Project start/completion date
- 4. Additional amount of ACM
- 5. Any reduction in amount of ACM
- Extend or reinstate the Asbestos Work Permit

Fig. 4: Amendment





If any of the following items change after the ACP7 has been submitted, you must submit the changes via your ARTS account only:


- 7. Project cancelled or postponed
- 8. Asbestos work schedule
- 9. Abatement procedures
- 10. Type of abatement
- 11. Asbestos Hauler

To register changes, enter your ARTS account and find the TRU number for the relevant project in the 'Processed' section on the homepage, and then click 'Make Changes.' You will be guided to a list of the details of your abatement project as they appear on your Form ACP7. Make whatever changes you need and then click 'Submit.' If you are making changes to items 1-6, ARTS will generate an Amendment Form (Form ACP8), which must be printed, signed and submitted to DEP with applicable fees, either by mail or in-person. Once DEP has received and approved the Form ACP8, it will advise you via your email that an approved version is in your ARTS account (or by mail, if requested) and the Form ACP8

should be posted at the work place next to the Asbestos Abatement Notice. If you are making changes to items 7-11, which do not necessitate the submission of a signed ACP8 to DEP, ARTS will immediately register the changes that you have entered and you may proceed with the abatement project.

However, you will have to file a new Form ACP7 if the changes that you are making will include any of the following:

- A change to the project details that will require an Asbestos Work Permit in a work area not previously covered; or
- A change to the project details that will require answering "Yes" about a new A-TRU criterion (questions 27-30 on the Form ACP7) that had previously been marked "No" (even in an area that is already permitted).



5. CLOSE-OUT

In the past, the DOB issued permits for jobs as soon as it had received a copy of the ACP5, the ASB4, or an ACP7 indicating that the applicant was making plans to abate the asbestos. Under the new policy, the Form ACP7 is no longer a prerequisite for the issuance of a DOB permit. All abatement projects must be completed before a DOB permit will be issued. Once abatement has been successfully completed, DEP will issue an Asbestos Project Completion Form or an Asbestos Project Conditional Close-Out Form, either of which can be presented to DOB in order to obtain a DOB permit.

DEP issues an Asbestos Project Completion Form once all components of the asbestos abatement project have been completed. If the abatement project did not require an Asbestos Work Permit and only received an Asbestos Abatement Notice, then the Abatement Project Close-Out will be issued once DEP receives a Project Monitor's Report. The Project Monitor is a certified professional who will monitor the abatement and review the results of the air monitoring. When abatement has been completed, the Project Monitor will file a Project Monitor's Report with DEP.

If the asbestos abatement project has received an Asbestos Work Permit from the Asbestos Technical Review Unit, then DEP will not issue the Asbestos Project Completion Form until it receives confirmation that all of the building work that was authorized by the Asbestos Work Permit has been carried out properly. This confirmation must be provided by a registered architect or professional engineer, or another licensed professional qualified to grant that particular sign-off (e.g., a master plumber in a case where plumbing has been affected by the abatement) who will file an A-TR1 Form.

The A-TR1 Form may be used to report a number of things. If the abatement involved the removal of elements of the fire safety system like sprinkler systems, standpipes or exit doors, the appropriate inspector (e.g., architects,

engineers, licensed plumbers, suppression contractors) will conduct a Special the Inspection at time that the building element is replaced to inspect and certify that the necessary work was completed as per all Building Code requirements. This Special Inspection will be noted on the A-TR1 Form that is submitted at completion of the project.

In situations where no Special Inspection is required, an A-TR1 Form is still required

to close out an Asbestos Work Permitted job. The registered architect or professional engineer will conduct a Final Inspection to confirm that the building has been returned to its original state. The registered architect or professional engineer will submit the A-TR1 Form and any relevant construction documents detailing the restoration of the building elements that were removed during the abatement.

Once DEP receives and reviews the appropriate documents, you will be notified of its approval via email (or by mail if you requested it). You will be able to log into the ARTS system and print your approved Asbestos Project Completion Form. You may then submit this form to DOB as proof that you have finished abatement, allowing the issuance of DOB construction permits.

If the work area is being left in a non-compliant state because a DOB-approved alteration or

demolition job will occur abatement, following the registered architect or professional engineer must certify that you have not exceeded your scope of work and begun construction your demolition and that the approved alteration scope encompasses the asbestos project work area. In this case, once DEP reviews and accepts the A-TR1 Form, it will issue an Asbestos Project Conditional Close-Out Form that will authorize DOB to issue building permits but will not close out the Asbestos Work Permit. You will have to keep the Asbestos Work Permit posted until the DOB permits have been

to keep the Asbestos Work Permit posted until the DOB permits have been pulled. Once the permits have been pulled. DEP will receive notice from DOB and the Asbestos Work Permit will be automatically closed out. If the Asbestos Work Permit, which is valid for one year, expires before the necessary DOB permits have been issued and the Asbestos Work Permit has not been renewed, DEP will issue violations for not properly closing out the abatement project. You will have to apply to have the Asbestos Work Permit reinstated in order to complete the close-out process.




Fig. 6: Items 1-9 in Section 3 of the A-TR1 relate to Special Inspections. Item 10 is the Final Inspection required to close out all permitted jobs.

The New Asbestos Project Notification Form

A detailed explanation of the new Asbestos Project Notification Form available on ARTS:

- 1. Asbestos Job Status
- 2. Form ACP7 Explained

1. ASBESTOS JOB STATUS

Once you log on to the ARTS system, you can see a list featuring the status of all your asbestos jobs. The status might be:

Work In Progress - These are applications that you are in the process of filling out.

Pending - These applications have been submitted to DEP's database and are pending until you come in with your signature sheet and any supporting documents. Opening these documents for editing will cause them to be automatically moved back into the "Work In Progress" folder.

Submitted - These applications have been submitted to DEP along with all necessary signatures and supporting documents. This category includes abatement jobs that are approved and may already be in progress. Once at this stage, your submitted paperwork can no longer be edited.

2. FORM ACP7 EXPLAINED

Online, the Form ACP7 has been divided into nine sections:

Section 1: Facility - Requires the location of the property where asbestos abatement will take place and some very basic characteristics about the property.

Sections 2 - 6: Contact Information - Requires contact information for all parties involved with the abatement project, including the applicant information (Section 2), the building owner (Section 3), the asbestos abatement contractor (Section 4), the third-party air monitor (Section 5) and the asbestos hauler (Section 6). In the section requesting information about the asbestos hauler (Section 6), you must list the disposal sites where the asbestos will be discarded.

Section 7: Project Information - This section asks basic questions about the asbestos abatement operation, including the abatement work schedule, the size of the abatement area and the type of abatement to be used. This section also asks if the building is government-owned.

Section 8: Abatement Locations - In this section, you must list each location within the building where you will be conducting abatement. You must provide the location of the abatement area and the amount (e.g., square feet or linear feet) of ACM to be abated. In this section you must note if any

Form ACP7 Outline

Section 1 Facility

Section 2
Contact Information:
Applicant

Section 3
Contact Information:
Building Owner

Section 4
Contact Information:
Asbestos Abatement Contractor

Section 5
Contact Information:
Third Party Air Monitor

Section 6
Contact Information:
Asbestos Hauler

Section 7
Project Information

Section 8

Abatement Locations

Section 9
Project Details


of the locations will require a variance.

Section 9: Project Details - While all the other sections in the online ACP7 can be filled out in any order, this section cannot be filled out until Section 8 has been completed and all the asbestos locations have been entered.


This section consists of three groups of very detailed questions. They are presented here with some guidance to help you answer them accurately:



The first group of questions in this section asks whether any of the building's fire protection systems (e.g., fire alarm or sprinkler system) will be turned off as a result of the abatement work.




If you indicate that any of these conditions will occur you must notify the FDNY Borough Communications Office, informing them of the date and time those conditions will be created and follow any instructions you receive from FDNY (this may include the posting of a fire guard).



The second group of questions determines whether the abatement work will result in blocked or compromised egress or whether any components of the fire protection system are going to be removed as part of the abatement.


If you indicate that any of these conditions will occur, the project will need a permit issued by A-TRU, which will require a Work Place Safety Plan in order to conduct its technical review. A Work Place




Safety Plan consists of work plans drawn up by a registered architect or professional engineer. It must include a floor plan indicating the location of the asbestos abatement containment area(s) - including personnel and waste decontamination enclosure system(s) - signed by a licensed project designer and any narratives that explain the means, methods, and sequencing of any additional safety measures to be in place for the duration of the permit.

The third group of questions determines whether or not abatement work entails removal of passive fire protection fire-(e.g., resistance rated walls, sprayed on fireproofing, or smoke dampers).

If you indicate that any of these conditions will occur, the project will require a permit from A-TRU. However, instead



of a full Work Place Safety Plan, you will only need to submit floor plans of all abatement containment areas in the building, all applicable construction documents, and all documents detailing how the work area is to be returned to its original condition. During the close-out, these projects are like any other Asbestos Work Permitted jobs and a Statement of Responsibility (Form A-TR1) from a registered architect or professional engineer must be submitted after the work has been finished in order to ensure the correct restoration of the work area after the abatement has been completed.





3 Maintaining Proper Egress


An introduction to principles of egress and egress during abatement:

- 1. What is Egress?
- 2. Egress During Abatement
- 3. Mitigation Steps
- 4. A-TRU Review and Permit
- 5. Inspections


1. WHAT IS EGRESS?

A means of egress, as defined in DEP rules, is "a continuous and unobstructed path of vertical and horizontal egress travel from any occupied portion of a building, structure or premises to a public way."

Under the ACP Rules, required means of egress, including emergency and fire exits, shall be maintained at all times during abatement activities, except as otherwise provided under Section 3303 of the New York City Building Code.




The requirements for egress in the DEP rules, as well as in the Building Code and Fire Code, are intended to ensure that safe passage is always maintained within buildings undergoing abatements so that, in the case of an emergency, building occupants and asbestos handlers can evacuate and first responders can safely conduct rescue operations.



There are many components to maintaining proper egress. In preparing an abatement worksite, revised § 1-81 of the rules stipulates several

new requirements relating to the maintenance of exit ways and exit lighting, including:

 Posting a floor plan in the building's lobby showing the location of all fire exits [§ 1-81(b)].



- Maintaining exit signs in the work area [§ 1-81(t)].
- Replacing any emergency lighting blocked by abatement-related materials with battery-operated exit signs, exit lights and/ or photoluminescent path markings [§ 1-81(l)].
- Exits shall not be obstructed; however, the exit shall not be considered obstructed if the barrier is limited to two layers of fire retardant 6-mil plastic and marked as an exit by photoluminescent paint or signage. Additionally, cutting tools must be attached to the work area side of the plastic to enable workers to escape in the event of an emergency [§ 1-81(o)(4)].
- Means of egress are not allowed to be obstructed by hardwall barriers unless an alternative means of egress is provided to the satisfaction of the A-TRU plan examiners [§ 1-81(o)(5)].

Along with maintaining egress in the work area generally, the DEP rules require maintenance of all exits from work areas in accordance with Section 1027 of the New York City Fire Code. Among those requirements:

- All doors and other devices must be maintained in good working order [FC 1027.3.1].
- All passageways that are part of the egress must be kept free from furniture or storage that would create an obstruction [FC 1027.4 and 1027.4.1].
- In the winter, maintaining egress includes preventing snow and ice from accumulating in front of exits [FC 1027.3.3].

Additionally, § 1-94(f) of the DEP rules requires abatement contractors to document daily inspections of emergency exits in their log book. Section 1-94(g) of the rules requires abatement work to cease if blocked exits are discovered during inspection.




Diagram indicating abatement areas that obstruct egress.

2. EGRESS DURING ABATEMENT

In the course of an abatement job, a number of legitimate reasons to obstruct egress may arise. Many of these are referred to in the 'Project Details' section of the new Form ACP7, where they appear in the form of questions. An asbestos abatement project may involve any of the following:

- Obstruction of an exit door leading to an exit stair or to the exterior of the building.
- 2. Obstruction of an exterior fire escape or access to that fire escape.
- 3. Obstruction of a fire-rated corridor leading to an exit door.
- 4. Removal of handrails in an exit stair or ramp.

Each of these represents a scenario where the abatement containment unit is situated in a place that will prevent asbestos abatement workers and/or building occupants from safely exiting the premises or first responders from entering the premises in the case of an emergency. The ACP7 refers to other situations where egress is impacted by the impairment of systems that help guide building inhabitants out of the building. These include:

- Removal or dismantling of any exit sign or any component of the exit lighting, including photoluminescent exit path markings.
- Disengagement or obstruction of any component of exit signage or exit lighting system, including photoluminescent exit path markings.

3. MITIGATION STEPS

You can take several mitigating measures to help prevent the obstruction of egress during abatement:

- In a hallway or corridor (i.e., an exit access), egress is not considered to be blocked as long as a 36" wide path is maintained for the entire length of that hallway or corridor.
- 2. A doorway leading to an exit or a window leading to a fire escape (i.e., an exit) is not considered to be obstructed if the exit is only sealed with two layers of 6 mil fire retardant polyurethane sheeting in front of the doorway or window. However, the doorway or window should be clearly marked as an exit and a clearly visible knife or blade that can be used to cut through the polyurethane in case of an emergency needs to be attached next to the sheeting.
- If exit signs, exit lighting or photoluminescent exit-path markings will be turned off, dismantled or obstructed





during the abatement, egress will not be considered to be impacted as long as they are replaced with battery-equipped temporary substitutes.

4. A-TRU REVIEW AND PERMIT

If egress must be obstructed or impacted during the course of your asbestos abatement project and the aforementioned mitigation steps are not an option, you must record this on your Asbestos Project Notification (Form ACP7). Then, you will need an A-TRU review and an Asbestos Work Permit before abatement may begin in the location where means of egress will be obstructed (abatement may begin in other work areas where egress is not affected once the Abatement Project Notification (ACP7) has been submitted and the Asbestos Abatement Notice has been issued).

For the purpose of the A-TRU review, you will need to provide the Asbestos Technical Review Unit with a Work Place Safety Plan consisting of:



- Floor plan(s), signed by a licensed project designer, indicating the locations of all abatement containment areas in the building, including personnel and waste decontamination enclosure system(s);
- 2. Floor plan(s) produced by a registered architect or professional engineer indicating the locations of any obstructed required exits and all temporary mitigating measures to be undertaken for the duration of the Asbestos Work Permit. These plans may also include alternate egress path(s) that will satisfy the applicable code requirements for maximum travel distances, the minimum number of exits per floor, exit widths and required signage and lighting. This is in keeping with 2008 Building Code Section BC 3303.11, which provides an exception for the maintenance of regular means of egress where there are approved temporary means of egress systems and facilities;
- A Tenant Protection Plan as required by Chapter 1 of Title 28 of the Administrative Code where the abatement work is in a building where any dwelling unit is occupied for the duration of the Asbestos Work Permit;
- 4. Description in narrative form of any measures to be taken to mitigate compromised fire protection systems or means of egress. Such descriptions may include surveillance by a fire watch and an emergency action plan which sets forth the circumstances and procedures for the sheltering in place, in-building relocation, partial evacuation or evacuation of building occupants in response to an emergency.

5. INSPECTIONS

Once abatement operations begin, the asbestos handler supervisor must check exits daily to ensure that there are no exterior blockages or impediments to exiting. If any blockages or impediments are identified, work must stop until the blockage has been removed. The asbestos handler supervisor should maintain a record of these inspections in their logbook.



TIPS TO HELP PREPARE FOR A-TRU

- Be aware of which building materials are going to be used.
- Be aware of where the asbestos containment unit is going to be situated relative to fire safety devices.
- Be aware of how the building is going to be used during the course of the asbestos abatement.
- Develop plans for different configuration options for the abatement containment units.

ENDNOTES

¹Under normal circumstances, the DOB will require that any asbestos in an area where construction or demolition is to occur must be completely abated before they will issue a DOB permit.

¹¹ Fees for asbestos project notifications, which have not been changed, are calculated based on the amount of ACM being abated:

More than 25 but less than 100 linear feet or more than 10 but less than 50 square feet	\$200
More than 100 but less than 260 linear feet or more than 50 but less than 160 square feet	\$400
More than 260 but less than 1000 linear feet or more than 160 but less than 1000 square feet	\$800
1000 linear feet or more or 1000 square feet or more	\$1,200

iii Additional fees for Asbestos Work Permits (A-TRU Review) are calculated based on the amount of ACM being abated:

25 to 99 linear feet or 10 to 49 square feet of ACM	. \$100
100 to 259 linear feet or 50 to 159 square feet of ACM	. \$300
Large projects up to 1000 linear/square feet of ACM	. \$500
1,000 to 4,999 linear/square feet of ACM	. \$700
5,000 to 9,999 linear/square feet of ACM	. \$1,100
10,000 or more linear/square feet of ACM	. \$1,300

^{1V} Fees for the Asbestos Variance Application are calculated based on the amount of ACM to be abated and the number of sub-sections for which the variance is requested:

First sub-section (per category) Each additional sub-section	If total amount of ACM is less than 5,000 ft.	5,000 ft. or more
First sub-section (per category)	\$400	\$600
Each additional sub-section	\$200	\$300
Maximum fee	\$1,200	\$1,800

^vThe following are Fire Code requirements regarding maintenance of the means of egress, which have been incorporated into the DEP rules and apply to asbestos abatement sites.

SECTION FC 1027 - MAINTENANCE OF THE MEANS OF EGRESS

1027.1 General. The means of egress for buildings, structures or premises, or parts thereof, shall be maintained in accordance with the construction codes, including the Building Code and this section.

1027.2 Prohibition. It shall be unlawful to obstruct or impede access to any required means of egress, including any exit, exit access or exit discharge.

1027.3 Unobstructed and unimpeded egress required. All required means of egress, including each exit, exit access and exit discharge, shall be continuously maintained free from obstructions and impediments to immediate use in the event of fire or other emergency.

1027.3.1 Door hardware. Door hardware and other devices and physical components of the means of egress shall be maintained in good working order at all times.

1027.3.2 Security devices. It shall be unlawful for a security device to emit any substance that could obscure a means of egress in any building, structure or premises. Security devices affecting means of egress shall be subject to the approval of the Commissioner of Buildings in consultation with the commissioner.

1027.3.3 Snow and ice. All required means of egress shall be maintained free from the accumulation of snow and ice.

1027.3.4 Overcrowding. Premises shall not be caused, allowed or maintained in such a manner as to become overcrowded, such that the number of persons present on the premises and/or their location thereon obstructs or impedes access to any means of egress.

1027.4 Furnishings and decorations. Furnishings, decorations or other objects shall not be placed so as to obstruct exits, access thereto, egress therefrom, or visibility thereof. Hangings and draperies shall not be placed over exit doors or otherwise be located to conceal or obstruct an exit except as authorized by the commissioner. Mirrors shall not be placed on exit doors. Mirrors shall not be placed in or adjacent to any exit in such a manner to confuse the direction of exit.

1027.4.1 Corridor storage. It shall be unlawful to store combustible materials or combustible waste in corridors except as authorized by this code or by the commissioner.

1027.5 Existing window gates and other restrictions. Bars, grilles, grates or similar devices installed on windows and other openings onto fire escapes prior to the effective date of this code shall be in accordance with the applicable laws, rules and regulations in effect at the time of installation, and Section 1025.4

1027.6 Maintenance of window gates and other restrictions. Bars, grilles, grates or similar devices placed over emergency escape and rescue openings, and windows or other openings onto fire escapes shall be maintained in good working order.



NYCDEP Water and Sewer



Application for Permit for Tap, Plug, Wet Connection, Repair/Relay of Water Service Line Please Print Applicant must be a Licensed Plumber



Work Site Street Address:			Borough:	Blo	ck:	_ Lo	ot(s):
City, State, Zip Code:							
Check One: Tap Plug Tap and Pl	Wo	et Connec epair/Rela					
Name of Street on which Tap/W	_		l Circle One) → (ST	T) (AVE)	(RD) (DR)	ОТ <u>Н</u>	(FR)
Tap or Wet Connection to be In	nstalled on <u>North</u> <u>South</u> (Circle	h East W		street.			<u>LEHV</u>
Size of City Water Main	Detail Dist	ribution	Map No		e of other (vate Wate		n(s)
Size of Private Water Main	Type of Ser	rvice <u>Dor</u>	mestic Fire Spri	inkler St Circle On		<u>Combi</u>	ned
Size of Internal Water Main	Approx. Le	ngth of S	Gervice	Office C.	! <i>e)</i>		
Tap/Wet Connection Size	Plug(s) (hov	w many?)				
~ . ~.	How Many	Sprinkle	er Heads?				
	_	_	nit No				
Rated Capacity of Pumps (gpm)	_	-			nkler:		
DOB New Building # or Alterat	tion#		P	Building S	Size:		
Cross Connection Control Appr	roval (yes or no)	_	Schedule B at	attached (yes or no)		
Cross Connection Control Exen	ention (vec or no)		Is Plug in Sar as existing ta			١	
Describe Tap Work (Install? Pla	_		_	_		' —	
Describe Tap Work (Induan, 11)	ag: Iveray: Ivepair.	ale://iii	ture or mepair.	lilei com	IIIIEII06		
Connections			ers for this Proper Size	Other	(1)		# or Meter #
(a)		(3)		•	(0)		
(4)		(4)		•	(4)		
Describe the property use. Chec [] Industrial [] Retail [] Hospital [] School [] Dry Cleaner [] Other	[] Residential		Medical/Dental Factory	I I	arehouse estaurant	[]	Car Wash Laundry
Destroyed	ocation of Tap/W.C. to be Destroyed	Tap/V	Tumber corresponding W.C. to be Destroyed		account Num Tap/W.C.		responding to Destroyed
1				— —			
2							
3							
4				——			
The undersigned plumber being the dul supplying this or the former building slip,							
Plumber's Name (Print):		J	License Number:	: _			
Signature:			Plumber's CIS Ac	.ccount N	o.:		
Business Address			Application Date:	e: _			
City/State/Zip Code:							
BWSO		$\overline{\neg}$ $\overline{}$		\overline{B}	CS		
Approximate Date of Work:		\Pr	emises Account #				
Approved By:		Per	rmit Type:	_ Num	ber:		
Approval Date:		Fee	e: Da	ate Issue	d:		

HIGHWAY PERMIT NUMBER	BLOCK

Form No. WPC-11 Rev. E (02-04)
[WHITE]

THIS IS NOT AN APPLICATION TO OPEN STREET OR SIDEWALK

THE CITY OF NEW YORK DEPARTMENT OF ENVIRONMENTAL PROTECTION BUREAU OF WATER & SEWER OPERATIONS DIVISION OF PERMITTING & CONNECTIONS

BOROUGH OF
APPLICATION FOR PERMIT
TO PLUG SINGLE/MULTIPLE PREMISE(S) SEWER HOUSE CONNECTION(S)
APPLICATION IS HEREBY MADE FOR PERMISSION TO PLUG THE FOLLOWING SEWER HOUSE CONNECTIONS
WHICH ARE CONNECTED TO THE SANITARY STORM COMBINED SEWER LOCATED IN (Check one of the above)
(STREET NAME)
BETWEEN AND CONSENT FROM OWNER(S) OF
THE BUILDING(S) FURNISHED
BETWEEN AND
THE OWNER OR BUILDER OF THE BUILDING(S)
THE ADDRESS OF THE OWNER IS
HOUSE No. LOT No. CONNECTION SIZE(S) & TYPES LOCATION PERMIT NUMBER
*Indicate side of street, [N, S, E, or W], and the distance from the building line on the corner of either intersecting street to the location of the connection where work is to be done.
IT IS UNDERSTOOD AND AGREED THAT THE WORK PROPOSED SHALL BE EXECUTED IN A GOOD AND WORKMAN-LIK MANNER AND TO THE SATISFACTION OF THE COMMISSIONER OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION I ACCORDANCE WITH THE PROVISIONS OF THE ADMINISTRATIVE CODE OF THE CITY OF NEW YORK AND ANY AMENDMENT THERETO, AND ANY APPLICABLE RULES AND REGULATIONS.
NOTE: PLUMBER TO AFFIX SEAL.
NAME OF THE LICENSED PLUMBER [Print]
SIGNATURE OF LICENSED PLUMBER
ADDRESS OF LICENSED PLUMBER
PLUMBER'S LICENSE NUMBER
BUREAU Comments and Approval Stamp
PERMIT FEE \$ DATE:/ 1. Number of premises indicated: 2. Total number of connection indicated:
1. Number of premises indicated: 2. Total number of connection indicated: TO THE PLUMBER: PLUG TO BE MADE AT CURB-SIDEWALK SIDE UNLESS OTHERWISE NOTE
TO THE PLUMBER. TEGO TO BE MADE AT GOOD-OIDEWALK GIDE GREEGE OTHERWISE NOTE
NOTE: APPROVAL VALID FOR THIRTY (30) DAYS.
FILL IN PERMIT NUMBERS ABOVE.
DATE: CLERKBUREAU OF CUSTOMER SERVICE
NO PERMIT(S) OF ANY TYPE WILL BE ISSUED FROM THE BUREAU OF CUSTOMER SERVICE UNTIL ALL OPEN CHARGES

NO PERMIT(S) OF ANY TYPE WILL BE ISSUED FROM THE BUREAU OF CUSTOMER SERVICE UNTIL ALL OPEN CHARGES HAVE BEEN PAID AND ALL KNOWN VIOLATIONS AGAINST THE PREMISES HAVE BEEN REMOVED TO THE SATISFACTION OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION.

NYCDOB-Forms





APPLICATION FOR INSPECTION PRIOR TO DEMOLITION BEST USE ONLY

(AND PRE-DEMOLITION REPORT)

DEMOLITION #

Application must be typewritten.

Bullaings	Applicati	on must be ty	ypewritten.			
Applicant, please complete all info	rmation requested belo	OW: (For mech	nanical demolition re	quests comple	te form BES	ST-4 as well.)
Number of structures at this address	you intend to demolish (a separate a	pplication is req	uired for ea	<u></u> ch):	
Name:	Company:					
E-mail:	Phone:		Fax	:		
Application date:	Bronx	Brooklyn	Manhattan	Queens	St	aten Island
Structure type (check only one):	☐House ☐Garage ☐	Shed □Cor	nmercial Buildin	g Other:		
Building address:		Le	egalizing a comp	oleted demo	lition?	Yes □No
Cross streets:	Bl	IN:	Block:		Lot:	
All AKA's ("Also-Known-As", if applic	able):					
BIS job # for demolition (DM) filing:	Other r	elated BIS jo	bb #s (if applicab	ole):		
Distance from nearest street corner (in feet): Mecha	nical demolit	ion requested?	□No □	Full [Partial
BEST must be notified in writing	g 24 hours prior to the o	commencen	nent of any full	demolition	(see BC	105.6.1).
PLOT DIAGRAM (MUST INDICA	TE ZONE OF SAFET	Y ON DIAG	RAM)			A 1
TEOT BIAGRAM (MOOT INDIO)	THE ZONE OF ONE	1 011 011	i () (ivi)			N
						A
						T
						t of the diagram
				m	iust agree v	vith the arrow
A survey may be submitted in addition	on to or in lieu of a plot di	agram as Ior	ng as the zone o	t satety is in	idicated.	
DO NO	OT WRITE BELOW THIS	LINE: OFF	ICIAL USE ONL	_Y		
Date of report:		Number of	stories:	Height of b	ouilding:	
Occupancy: Is building vacant? Y	es 🗆 No	Sidewalk sh	ned required?	□ Yes □] No	
If yes, has a sidewalk shed been ere	cted? ☐ Yes ☐ No	If yes, prov	ide permit numb	er:		
Does the building have fire escapes	or other exits used jointly	with an adjo	ining or abutting	g building?	□ Yes	□ No
Will the removal of the fire escape or	other exit affect the adjo	ining buildin	g? □ Yes □	1 No		
Does the building have party walls or	<u>_</u>		<u> </u>	□ No		
If yes, please describe:	oog a aajo.		,. = .55			
Has the demolition of the building co	mmenced? Yes	□ No	If yes, answe	r the follow	vina aue	
Has work been stopped? ☐ Ye			olice been notifie		☐ Yes	□ No
• • • • • • • • • • • • • • • • • • • •					<u>п 162</u>	
Has an ECB violation been issued?	□ Yes □ No	ii yes, provi	ide ECB violatio	n number:		
Comments:						
Inspection Result:	Pass		☐ Fail			
Inspected by:	Signature:		Badge	#	Date:	
Supervisor:	Signature:		Badge	#	Date:	
Administrative Comments:						



BEST Appointment Request Form
(A SEPARATE FORM MUST BE SUBMITTED FOR EACH JOB)
Submit typewritten form to BESTappt@buildings.nyc.gov

1	REQUESTOR (Required)			
	Name			
	Business Phone Ce	ell Phone		
	Email			
2	LOCATION INFORMATION (Required)			
	Address			
	Job# BII	N #		
	Community Board # Block #	LOT#		
3	APPOINTMENT REQUEST (Required)			
	☐ Pre-Demolition Inspection			
	Onsite Plans		□ YES	□ NO
	TR1 Statement of Responsibility		□ YES	□ NO
	Is the requested appointment a follow-up to previous objection	ons issued?	☐ YES	□ NO
			lf yes, indicate action taken i	e the corrective
		•	action taken i	n occuon 4.
	☐ Demolition Sign-off Inspection	ı	—	
	Onsite Plans			∐ NO
	TR1 Sign-off		⊔ YES	□ NO
	☐ Stop Work Order Rescind			
	Partial or Full Stop Work Order		☐ Partial	☐ Full
	Stop Work Order complaint number			
	Violation Number(s)			
	Are copies of the violation on site?		□ YES	□ NO
	Has all corrective action been taken to correct the violation(s)?!	☐ YES	□ NO
			lf yes, indicate action taken i	e the correctiven Section 4
	☐ DOB Violation Dismissal		zotrom tantom n	
	Violation Number(s)			
	Has all corrective action been taken to correct the violation(s)		□ ves	□ NO
	rias all corrective action been taken to correct the violation(s)			e the corrective
		ć	action taken i	n Section 4.
	☐ Sidewalk Shed Removal ☐ Partial ☐ Full			
	Has all exterior work been completed?		☐ YES	□ NO
	Have all temporary devices, equipment and tools been remove	ved from setback?l	☐ YES	□ NO
	Are windows and curtain walls completed?		☐ YES	□ NO
	Other than the sidewalk shed, has all exterior temporary con- equipment been removed?	struction	☐ YES	□ NO

	☐ Removal from Site Safety (Site Safety Projects ONLY)	
	Has all exterior work been completed?	□ NO
	Have all devices, equipment and tools been removed from roof setback? ☐ YES	□ NO
	Are windows and curtain walls completed?	□ NO
	Has all exterior temporary construction equipment been removed?	□ NO
	Has the sidewalk shed been removed?	□ NO
	□ Other	
4	COMMENTS	



APPLICATION FOR BEST RECOMMENDATION FOR MECHANICAL MEANS DEMOLITION

BEST USE ONLYDEMOLITION #

Application must be typewritten.

Structure and Location Information	:									
Number of structures at this address y	ou intend to demolis	h (a separate	application is req	uired for each	າ):					
Name:	Company:									
E-mail:	Phone:		Fax	:						
Application date:	Bronx	Brooklyn	Manhattan	Queens	☐ Staten Island					
Structure type (check only one):										
Building address:										
Cross streets:		BIN:	Block:		Lot:					
All AKA's ("Also-Known-As", if applica	ıble):									
BIS job # for demolition (DM) filing:		Other related	BIS job #s:							
Distance from nearest street corner (ii	n feet):									
Mechanical Means Information:										
Description of mechanical equipment	proposed for demolit	ion:								
Requesting full mechanical demolit	ion 🔲 Reque	esting partial m	echanical demoli	tion						
 A plot plan must accompany this request. It must show: the size of the lot, the size, location and height of all structures on the lot of adjacent structures the structures which are to be demolished and the structures or portions thereof which are to be demolished by mechanical means the construction classification of the building to be demolished the mechanical means to be used(type of machinery) and proposed location of it the safety zone the location of the sidewalk shed, fences and other protective construction the width of the adjoining street 										
Agreement and Signature:										
 A construction fence will be elequipment will be permitted we demolition is in use. No part of Request, Letter of Permission All Building Department regulation All hand demolition will be condemolition 	 A construction fence will be erected along the perimeter of job site. No persons other than the operator of the equipment will be permitted within the safety zone of demolition while the mechanical means method of demolition is in use. No part of the equipment, when in use will extend beyond the permitted boundaries. Letter of Request, Letter of Permission and Plot Plan must be available on the premises during course of demolition. All Building Department regulations will be followed when performing the demolition in accordance with Chapter 19 Article 6, section 27-1039d. All hand demolition will be completed and inspected by B.E.S.T. prior to commencement of any Mechanical 									
Print Name:		Title) <u>:</u>							
Company: Signature:				Date:						
BEST Use Only	Appro	ved	Disapprove	d						
Reviewed by:	Signature:		Badg	je #	Date:					
Supervisor:	e #	Date:								
Comments:										

DS1 INSTRUCTIONS

Purpose of form:

This form is required when submitting demolition submittal plans - required by BC 3306.5 on full demolition jobs and Alteration jobs that contain partial demolition work. The form must be submitted together with the plans prior to requesting a permit. The form must be completed by an appropriate professional.

Be sure to attach the appropriate job number sticker and write its related document number in the boxes at the upper right hand corner of the form.

If there are changes made to existing demolition submittal plans or to the information contained in a previously submitted DS1, submit an updated DS1 to supersede the older version.

1 Location Information

Enter the basic address information where the work will take place. Indicate which floor(s) will be affected by the work.

2 Preparer Information

Enter all details regarding the professional that is preparing the demolition submittal plans.

Indicate the relationship of the preparer to the job. For example, if the preparer is a PW1 applicant that also designed the architectural plans, check off the "PW1 Applicant" check box.

3 Demolition Certification by Preparer

The preparer must certify all facts about the submission in this section. Indicate if this is an initial DS1 (submitted for the first time), or if this DS1 is being submitted to supersede a previously submitted DS1(s). Enter the scan code(s) of the DS1(s) being superseded by this DS1. The scan code is an alpha-numeric code that begins with 'SC', and it can be found on the top right section of the scanned DS1 form.

- 3A Indicate the type of demolition that will occur on the site Full Demolition (DM) or Partial Demolition (ALT).
- **3B** Indicate the characteristic of demolition work that will take place on the work site. Check off all check-boxes as applicable. Enter the types of mechanical demolition equipment that will be utilized on the site a general description of each type of equipment is sufficient.

Note: authorized preparers (i.e. P.E., R.A., or both) for each type of demolition are indicated in brackets.

3C If this DS1 form is being submitted as a result of changes made to previously submitted plans, enter the scan code of the accompanying Al1 form(s) submitted with the revised plans.


The scan code is an alpha-numeric code that begins with 'SC', and it can be found on the top right section of the Al1 form.

3D Check the check-box to certify the preparer statement. The preparer's signature and seal are required for all certification forms.



DS1: Demolition Submittal Certification Form

Must be typewritten.




Demolition drawings must be submitted along with this form.

		BIS Document No., required:							
1	Location Information Required for all certifications.								
	House No(s) Street Name								
	Borough Floor(s)								
2	Preparer Information Required for all certifications.								
	Check all that apply: PW1 Applicant P.E./R.A. Other Than PW1 Applicant								
	Last Name First Name	Middle Initial							
	Business Name	Business Telephone							
	Business Address	Business Fax							
	City State Zip	Mobile Telephone							
	License Type P.E. R.A. Other:	License Number							
3	Demolition Description and Certification Required prior to permit. Subs	equent revisions must be submitted to the Department.							
	ndicate Submittal Type:	nittal(s) - indicate scan code(s) of DS1 being superseded below							
	Scan Code(s):								
	3A Demolition Type: Full Demolition (DM) Partial Demolition (Al	teration)							
	3B Demolition work will involve, per BC 3306.5 (authorized preparers indicated	in parenthesis): Check all that apply							
	Non-mechanical demolition means and methods <i>only</i> (P.E. or R.A. only) -								
	Use of hand-held mechanical equipment (P.E. or R.A. only)	Work on interior of building							
	Use of other than hand-held mechanical equipment (P.E. or R.A. only)	Work on exterior of building							
		Raising and/or moving of a building							
	General description of the type(s) of mechanical demolition equipment used:	3 3 3 3 3 3 3							
	25 2555 part of the type(e) of meetining aemonitor equipment used.								
	3C If superseding a previous plan submittal, indicate scan code(s) of the Al1: (//	lote: any revisions/additions/deletions to the original plan submis-							
	sion must be accompanied by an Al1 form detailing all the plan changes)	isto. a.i, istroiche additione deletions to the original plan submis-							
	3D Statement by demolition document preparer:	Name (please print)							
	I have prepared the attached demolition submittal documents in accordance with BC 3306 and certify that they are in compliance.								
	I hereby state that all of the above information is correct and complete to the best of my knowledge. Falsification of any statement is a misdemeanor and is	Signature Date							
	punishable by a fine or imprisonment, or both. It is unlawful to give to a city								
	employee, or for a city employee to accept, any benefit, monetary or otherwise, either as a gratuity for properly performing the job or in exchange for special	/							
	consideration. Violation is punishable by imprisonment or fine or both.								
		P.E./R.A. Seal (apply seal, then sign and date over seal)							



PW1: Plan / Work Application

Must be typewritten.



				•				
1	Location Information Re	equired for all applications.						
	House No(s)	Street Name						
	Borough	Block	Lot	BIN	C.B. No.			
	Work on Floor(s)			Α	Apt. / Condo No(s)			
2	Applicant Information R	Required for all applications. Fa	ax, mobile telep	phone and e-mail addres	s are optional information.			
	Last Name	Firs	t Name		Middle Initial			
	Business Name			Bu	siness Telephone			
	Business Address				Business Fax			
	City	State	Zip		Mobile Telephone			
	E-Mail				License Number			
	Choose one: P.E.	R.A. Sign Hanger	R.L.A.	Other:				
2	Filing Pontocentative C	amplete only if different forms	anlicant are - in	ad in soction 2. Face	hila nhana and a mail are critical infe			
3	-			eu III Section 2. Fax, mo	bile phone, and e-mail are optional info.			
	Last Name	Firs	t Name		Middle Initial			
	Business Name			siness Telephone				
	Business Address	04-1	7 :		Business Fax Mahila Talanhana			
	City	State	Zip	Mobile Telephone				
	E-Mail			Registration Number				
4	Filing Status Required for	r all applications. Choose one	and provide sp	ecified associated inforn	nation.			
	Initial Filing 5, 7, 11, 12A, 25		to Approval A		Reinstatement 24-26			
	Choose only one:	☐ Ar	mend Existing F	Filing 4A	☐Withdrawal 26			
	☐ Standard Plan Examination			g 6-7, 8A (Alt-2 only), 1	•			
	☐ Professional Certification I☐ Professional Certification o			endment (PAA) $4A, 6, 2$ fees? \square Yes \square No	24-25 ☐ Entire Job4A Indicate existing document number			
		-	-) Applicant 4A, 25-26	affected by filing:			
5	Job/Project Types Change	se one and provide specified a	ssociated infor	mation				
		on Type 1 required Altera			C-E, & Full Demolition 6B, 8D, 9A &			
	to meet New Building requir	rements (28-101.4.5) ^{14,} ²⁰), 22		9C-D, 9K, 13D-E, 14, 21A, 22			
	6A-E, 8B-C, 8F, 9-10, 12, 13C	C-F. 14. 18-20. 22 & ☐Altera	tion Type 3 5	A, 6B-F, 8C, 9-10, 13C-E	^{E, 20,}			
	PW1A, PD1	22 □New E	Buildina 6A-F	8F, 9A, 9C-K, 10, 12 &	☐ Condominium ☐ Improved 17			
	Alteration Type 1, OT: "No V	Nork" 8C, 8F, 9-10 & 13A-E	5. 14, 18-20, PV		5A Directive 14 acceptance requested?			
	12, 13C-F, 14, 18-19, 22, PW	11A PD1	5A, 6B-D, 9A, 9	*	□Yes □No			
6	Work Types Select all that	t apply but no more than allowe	ed by job and fi	ing type. "OT" required	on all NB and Alteration 1 initial applications.			
6A	□BL - Boiler <i>PW1C</i>	☐ FS - Fuel Storage PW1		Plumbing <i>PW1B</i>	6E □ CC - Curb Cut 16			
	□ FA - Fire Alarm	☐ FP - Fire Suppression		Standpipe <i>PW1B</i>	☐ OT/LAN - Landscape			
25	☐ FB - Fuel Burning <i>PW1C</i>	☐ MH - Mechanical		Sprinkler PW1B	6F OT/ANT - Antenna			
ρB	☐ EQ - Construction Equipment 15	6C ☐ OT/GC - General Construction	רוס⊓ ⊓סס □	Other, describe:	☐ OT/BPP - Builders Pavement Plan 8D☐ OT/FPP - Fire Protection Plan			
	<u> Е</u> чаршон <i>10</i>	Jonatiuotion			☐ OT/PPP - Fire Protection Plan ☐ OT/MAR - Marquee 8E, 26B			

PW1

7	Pla	ns/Construc	ction	n Documents	Sul	bmitted	l Plan	s are	required	d for	r most appl	lications.								
Are	e pla	ns being subm	itted	with this PW1?	,	Yes	☐ No	0	If yes, d	lo th	ne plans inc	clude:	☐ FO —	– Fou	ındati	on	□ EN -	— En	ergy Ana	alysis
8	Add	ditional Info	rma	tion																
8A	WT	Cost	WT	Cost	WT	Cost		8B I	ls a build	ding	g enlargeme	ent prop	osed?				Job Cos	t \$		
								1	□ No en	nlarg	gement is p	oroposed	b	8D S	Street	Fron				linear ft.
									□Yes	12, 1	PD1		İ		Heigh			ft. Wi		ft
					,,,	,,,,,,	,,,,,,		☐ Hoi			□ Verti		8F -	Total I	3uildi	ing Squa	are Fo	ootage:	
								3	Additi	iona	al Construct	tion Floc	-	-						sq. ft.
_													sq. ft.							
9	Add	ditional Con	side	erations, Lim	itati	ons or	Restr	ictio	ns											
			ed un	nder which build	ing c	ode?	201	14	2008			Prior to	o 1968	-	_	-		-		
	Yes					.n.e				Yes	No		1			:4				
9B				ired to meet Ne (28-101.4.5) <i>If</i> j							☐ Chang	-			_	nts				
											☐ Chang	-				nt -	rtific-1	of -	OLIDO:	
00	 	☐ Alteration☐ Façade Al		major change to	o exi	ເວ					_	-	onsistent mber of s			ııı CE	uncate	OI OC	.cupancy	
9C		=		tion nment <i>If yes, pl</i>	ot di	agram /-	axcent	DM	L		☐ Chang		INDEL OT S	sione	,o					
				nment <i>it yes, pi</i> Development (☐ Infili Z	-			Yes	Nο	Work Ir	JClud.	es.	
				lousing (Inclusion		-		3 /			_	ty Housir	าต		. 53	.			d I-joists	
				Occupancy (SR	-			1				-	b/Project	t					old-forme	d steel
		_		Lot Merger / R			_		7			led in LN	-	-					steel joist	
9D		Landmark		J-: / . .	ı- r		,	<i>, ,</i>					ess violat	tions					,	
•		Little "E" o) Site						_		s—max.		-	_					
		Unmappe													-					
		Requestin	ıg leç	galization of wo											-		N			
		·	•								_ For-	to com	dy water i	00-1	=	LL	Numbe	er.	Ye	ar
		□ Other (ple	ase	specify on line	μισνί	uea Dela	νv).			Ш			oly with Lo –max. 2)		=					
		☐ CRFN(s)	Res	trictive Declarat	ion /	Easeme	ent (ma	ıx. 4):	•	_		_		_	_					_
_				ing Exhibit (I, II,						_										
9E		BSA Cale	ndar	Numbers (max	'. 5):					_						_				
9F				Numbers (max																
9G				lighting fixture								CC §404	and §50)5]						
9H				modular constr					•						91	Hig	nh Rise 1	Геат	tracking	#:
				modular constr																
9J				r review require			•													
9K				permanent rem				<u>'</u>			• •									
9L				partial demolitie				§28-	·101.5, o	or th	e raising/m	noving of	τ a buildiı	ng <i>It</i>	yes, .	21B				
		□ Structural □	stab	pility affected by	prop	osed wo	ork													
10	NY	CECC Comp	olian	1CE New York Cit	ty Ene	ergy Conse	ervation	Code												
	To th	ne best of my k	now	rledge, belief an	d pro	ofession	al judgr	ment,	all work	(un	der this ap	plication	ı is in cor	mplia	nce w	ith th	e NYCE	CC*		
		Code Complia	ance	Path (choose c	ne):	\square N	YCECC	2			□ASHRAE	:								
_		Energy Analys		,			abular /				RESchec		□ COMo						ling (EN	
Ш	To th			rledge, belief an llowing <i>(choose</i>			al judgr	ment,	, all work	k un	der this ap	plication	n is exem	npt fro	om the	e NY(CECC* i	n acc	cordance	with
		The work is a	n alte	eration of a Stat	te or	Nationa			_											
				work is entirely i				_				_								
				of work involves S, EQ, CC, OT									ing work	type	es:					
				o, ⊑Q, CC, O⊺. roval amendme								•	Sanata	atem:	ant of	0000	antion o	n otto	ached dra	awings

PAGE 2

11 Job Description	11/	A Related DOB Job Numbers
	1.	1B Primary application job no.
12 Zoning Characteristics		
12A District(s)	12D Street legal width:	ft.
Overlay(s)	12B Street legal width: Street Status: Public	Private
Special Dist.(s)	If the zoning lot includes tax lots, list all tax lots	
Map Number		
12C Proposed: Use* Zoning Floor Area District FAR sq. ft.	_ Proposed Lot Details: Lot Type: ☐ Corner ☐ Interior ☐ ☐	Proposed Yard Details: Through Check here if no yards: or
sq. it.	Lot Type Cornerinterior	% Front Yard
sq. ft.	Lot Area	sq. ft. Rear Yard
sq. ft.	Lot Width	ft. Rear Yard Equivalent
sq. ft.	Proposed Other Details:	Side Yard 1
sq. ft.	, Enclosed Parking?∐Ye	es No Side Yard 2
Proposed Totals sq. ft.	If yes, no. of parking spaces:	
Existing Total sq. ft.	Perimeter Wall Height	ft.
*Use can be one of the following: residential, commercial, n	<u> </u>	t only one use per line.
13 Building Characteristics *Main use/dominant occupa	ncy per AC §28-101.5. **Use 2014 Cod	de equivalents only. +Residential w/other us
13A Primary structural system, <i>choose one:</i> Masonry Wood		te (Precast) Cold-Formed) ☐Steel (Encased in Concre
13B Existing		g Type: 1, 2, or 3 Family Other
Structural Occupancy/Risk Cat.	Mixed	use building? [‡] Yes No
Seismic Design Cat. 2014 Code Designations?	2014 Code Designations? 13E	Existing Proposed
13C Occupancy Classification*	⊠Yes** Build	ding Height ft.
Construction Classification	□Yes □No Build	ling Stories
Multiple Dwelling Classification		elling Units
13F Building was originally erected pursuant to		008
The earliest Code with which this building or any part of it	is required to comply:201420	008 1968 Prior to 1968
14 Fill Choose one.		
□ Not Applicable □ On-Site □ Off-Site	Under 300 cubic yards	
15 Construction Equipment		16 Curb Cut Description
Chute Sidewalk Shed	Construction Material:	Size of cut (with splays):
Fence Size: linear ft.	BSA/MEA Approval No.	Distance to nearest corner:
Supported Scaffold Other:	,	to street:
17 Tax Lot Characteristics		18 Fire Protection Equipment
Original tax lots being merged or reapportioned (if applicable	e):	Existing Propos
- Indicate the sound marged of reapportunited (if applicable	-,. 	Yes No Yes N
		_ Fire Alarm
Tentative tax lot numbers (new tax lots only):		Fire Suppression ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐
		Standpipe


PW1 PAGE 4

19	Open Space	s											
		Existing	Proposed			Existing	Proposed						
	Plaza Area	sq. ft.	sq. ft.		Arcade Area	sq. ft.	sq. ft.						
	Parking Area	sq. ft.	sq. ft.		Parking Spaces								
	Loading Berths	sq. ft.	sq. ft.		Loading Berths								
20	20 Site Characteristics 20A Flood Hazard Area Information												
	Yes No												
21	Demolition [Details *Mechanical ed	quipment other than handh	eld devices t	o be used for demo	lition or removal of debris	(BC §3306.4).						
21A	Yes No	filing is for a secondary	structure? If yes, specify	structure he	na demolished:								
	☐ ☐ Mecha	nical means* from out o	f building? If yes, mech n building? If yes, de	nanical mean	· —	entire structure or	part of structure						
21B		ition work affects the ext cope of work involves rai	terior building envelope sing/moving of a building										
22	Asbestos Ak	patement Compliand	e Choose one.										
	The scope of th DEP ACP-5 Co The scope of w	ne work is not an asbest ontrol No. ork is exempt from the a	estos abatement as defined os project as defined in the asbestos requirement as de ucted pursuant to plans sut	e regulations	of the NYC DEP.	DEP Control # is required	f. 5 RCNY 1-23(b))						
23	Sign												
		Type: ☐ Illuminated 23A g ☐ Non-Illuminated round ☐ Roof 23B ☐ V	Estimated Cost: \$ Total Square Feet: Height above Curb: Vall Height above Roof:	ft.	Yes No	ted type: Direct For the sign projects beyond billed for annual permit?	ouilding line, is owner						
	Yes No	ound	Tall Troight above 135	11.		Is roof sign tight, closed							
	☐ ☐ Is sig	in inside building line? gned for changeable cop an OAC have an intere	If no, sign projects by: _ by? If no, 23C st in this sign or location?			ording. If extensive, provi							
	F		f an arterial highway? If ye	•	23D Distanc	e from Arterial Highway:	ft.						
	☐ ☐ Within	n 200' and within view o	f a park 1/2 acre or more?	If yes, 23E		e from Park 1/2 acre or n	nore: ft.						
	If ans	swer is "ves" to either of	the above two questions <u>a</u>	nd this is an	23F OAC Si	gn Number:							
			umber is required in section		23G OAC R	egistration Number:							
24	Comments	Place additional comme	nts on an Al-1 form. See (Guide for pro	per incorporation o	f professional certification	statements.						

PV	۷1						PAGE 5						
25	Αp	plic	ant's Statements and Signatures Required for all a	pplications.									
	Falsification of any statement is a misdemeanor and is punishable by a fine or imprisonment, or both. It is unlawful to give to a city employee, or for a city employee to a benefit, monetary or otherwise, either as a gratuity for properly performing the job or in exchange for special consideration. Yiolation is punishable by imprisonment or fit I understand that if I am found after hearing to have knowingly or negligently made a false statement or to have knowingly or negligently falsified or allowed to be falsified certificate, form, signed statement, application, report or certification of the correction of a violation required under the provisions of this code or of a rule of any agency, barred from filling further applications or documents with the Department. I prepared or supervised the preparation of the construction documents and work shown thereon comply with the provisions of the NYC Administrative Code applicable laws and rules, \((\(\cdot \) (\(\cdot \) check here if) except as set forth in the accompanying documents. I acknowledge that I have read and complied with all instructions per this application and supplementary schedules submitted. Cluster Development Statement (if applicable): I hereby state that all specifications relating to this job are in those previously filed under the group lead job number, except as specified herein.												
			New Building and Alteration 1 applications filed under the 2008 or 201 y: does this building qualify for high-rise designation?		Name (print):								
			14 initial applications only: I certify that the construction documents submiction documents related to this application do not require a new or amended		Sign and Date:		<u> </u>						
	Occi	upanc	y as there is no change in use, exits, or occupancy. Yes No		P.E. / R.A. Seal (app	oly seal, then sign and date o	over seal)						
26	Property Owner's Statements and Signatures												
	bene unde certii barre perm issue	efit, merstan ficate, ed from hitted e a let ve aut	on of any statement is a misdemeanor and is punishable by a fine or impriso onetary or otherwise, either as a gratuity for properly performing the job or in d that if I am found after hearing to have knowingly or negligently made a fal form, signed statement, application, report or certification of the correction on filing further applications or documents with the Department. Furthermore work is complete, and that a satisfactory report of final inspection be submitter of completion or certificate of occupancy within the time prescribed by law horized the applicant to file this application for the work specified herein	n exchange for spe lse statement or to of a violation requi , I understand that ted, along with all w. Owner Indi	ecial consideration. Vio have knowingly or nered under the provision I am responsible for in required submittal docuvidual Part	lation is punishable by impris gligently falsified or allowed t as of this code or of a rule of nsuring that a final inspection uments, so that the NYC Dep tnership	conment or fine or both, o be falsified any any agency, I may be be performed when the artment of Buildings may						
			ure amendments. I will not knowingly authorize any work that is not in e with all applicable laws, rules, and regulations.			er Government NY	• •						
		No				Co-Op Tenant-shareho a non-profit organizatior							
			Fee Exemption Request (Non-Profit Owned and Operated) In accordance with Administrative Code §28-112.1, Exception 1, I certify		ease print):	a non-pront organization	1: 103 100						
			that the deed holder is a corporation or association organized and operated exclusively for the purposes indicated in such section, and that	Relationship	. ,								
			the property is used exclusively by such entity for such purposed. Fee Exemption Request (NYCHA/HHC, NYC Agency, or Other	Business Nar	ne/Agency:								
			Government Owned and Operated) The building or any part thereof to be constructed, renovated, altered or demolished is owned and operated	Stre	et Address:								
			exclusively for the purposes of the NYC Agency, NYC Authority, NYS Agency, Federal Government or any other government entity. ★		City:	State:	Zip:						
			Owner's Certifications Regarding Occupied Housing The site of the building to be altered or demolished, or the site of the new	Telephor	ne Number:	Fax:	<u> </u>						
			building to be constructed, contains one or more occupied dwelling units that will remain occupied during construction. These occupied dwelling	E-Ma	ail Address:								
			units have been clearly identified on the submitted construction documents.	Signature and	d Date								
			The site of the building to be altered or demolished, or the site of the new	$\stackrel{\circ}{=}$									
			subject to rent control or rent stabilization under Chapters 3 and 4 of Title	26A Cond	o/Co-Op Board	See note in bottom le	ft corner of page.						
			26 of the New York City Administrative Code. <i>If yes, select one of the following:</i>	Name (p	lease print):								
			The owner is not required to notify the New York State Homes and Community Renewal (NYSHCR) of the owner's intention to file		Title:								
			because the nature and scope of the work proposed, pursuant to NYSHCR regulations, does not require notification.	Stre	eet Address:	01.1	7 .						
			The owner has notified the New York State Homes and Community	Talamba	City:	State:	Zip:						
			Renewal (NYSHCR) of its intention to file such construction documents/apply for such permit and has complied with all		ne Number:	Fax:							
			requirements imposed by the regulations of such agency as preconditions for such [filing/application].		ail Address:								
			Provide date NYSHCR notified:	Signature an	d Date								
			Owner's Certification for Directive 14 Applications (if applicable) I have read and am fully aware of the applicant's statement that the	26B Less	ee Responsible	for Annual Sign or	Marquee Permit						
			construction documents submitted and all construction documents related to this application will not require a new or amended Certificate of	Name (p	lease print):								
			Occupancy as there is no change in use, exits, or occupancy and the work is not inconsistent with the current certificate of occupancy.	Relationsh	ip to Owner:								
			Furthermore, I understand that I am responsible for retaining a qualified design professional to perform a final inspection when the permitted work	Business Na	me/Agency:								
			is complete and this professional must submit a satisfactory final inspection report to the NYC Department of Buildings within the time	Stre	eet Address:								
	Note	e fo-	following inspection prescribed by Department rule. Section 26A: Section required if unit owner signed Section 26. Signature		City:	State:	Zip:						
	requ	ired fo	or authorized representative of Condo or Co-Op board.	Telepho	ne Number:	Fax:							
	*	For fe	e waivers, please see the PW1 User Guide	E-M	ail Address:								



PW1B: Schedule B Plumbing, Sprinkler, Standpipe Must be typewritten.



	Page	1 of		•	
1 Location Information	n Required for all applications.				
House No(s)	Street Name				
Borough	Block	Lot	BIN	CB No.	
Work on Floor(s)					
2 Work Type Informati	on Required for all applications	Select all that	apply.	Filing compone	ents/fixtures? ☐Yes ☐No
☐Plumbing - PL	□Sprin	kler - SP		☐Standpipe - SD)
Cost: \$	Cost	\$		Cost: \$	
Total sprinkler heads in 8		sprinkler heads			
To remove violation(s): 1	To re	move violation(s): 1)	To remove viol	lation(s): 1)
2			2)		2)
3 Drainage Informatio	n				
Storm Drainage Discharg				nage Discharges into: selec	
Storm Sewer Cor	mbined Sewer Private Disp	osal	Sanitary Sew	ver Combined Sewer	Private Disposal
4 Sewer Work Select a	ll that apply.				
☐HCP-1/HCP-2	☐Site (Connection		☐Septic Tank	
5 Cap / Remove / Repl	ace / Relocate Components	If this section i	s completed, coi	mponents are required.	
6 Gas and Gas Equipr	nent Data				
Gas piping involved? □ Total	Yes \(\sum \text{No} \) No Describe gas Location(s), floor/apt list all to	ns fired equipmen hat apply:		me (please print)	
Meters total:					
Risers total:			Sig	nature	Date
Gas Usage: ☐Heat ☐HVAC ☐Other:	□ Dryer □ Water Heater □ Cooking □ Fire Place	☐Tankless Coil ☐Boiler Pilot for	Oil Burner		
7 Applicant's Stateme	nts and Signatures Requi	ired for all applic	ations.		/
both. It is unlawful to give to monetary or otherwise, eithe	t is a misdemeanor and is punishable a city employee, or for a city employer r as a gratuity for properly performing on is punishable by imprisonment or fi	e to accept, any be the job or in excha	nefit, nge for	F / R A Seal (apply seal the	en sign and date over seell

System (work type Capital Programs Capital Pr	_											AGE			UF		
System (work type) BA Sprinkler (SP) Must not be off domestic. Figure Sprinkler (SP) Must not be off domestic. Figure Sprinkler (PL)** Figure Sprinkler (PL)** Figure Sprinkler (PL)** Figure Standpipe (SD) Figure Standpipe (SD) Figure Sprinkler (PL)** Figure Standpipe (SD) Figure Sprinkler (PL)** Figure Standpipe (SD) Figure Sprinkler (PL)** Figure Sprinkler (PL)* Figure Sprinkl	8	Eq	uipment Information	n For new work only.													
System (Work type) BA Sprinker (SP) Must not be off domestic. Must not be off domestic. Fine Prince Populary (SP) Fine Po			· · · · · · · · · · · · · · · · · · ·	ı	F! -	or-	in el! - ·	la :	of :		100:	- t-	or =! /	w #\/n =	or = !	in-	
BA Sprinkler (SP) P Sprinker Paping - Day Must not be off of Programmer Paping - Day Must not be off of Programmer Paping - Day BE Sprinkler (PL)** F Sinnese FDC F Sinnese FDC F Sprinkler Heads over 999 BB Sprinkler (PL)** F Sprinkler Heads over 999 BC Fire Standpipe (SD) P Sprinkler Heads (hitry or less) BC Fire Standpipe (SD) P Sprinkler Heads (hitry or less) F Fire Pump F Source Control Valve F Hose Control Valve F Hose Control Valve F Hose Control Valve F Hose Control Valve F Source Paping B Sewer (Jector Nalve) F Source Paping F Source			System (work type)		FIO	ors	indica	e no.	of prop	osea co	mpor	ients	ana/o	r "X" t	or pip	ing	
Must not be off domestic. Figerolites Priging - Wet E	_	_															
Must not be off domestic. E Booster Pump - SP F Roor/Rear Control Valve F Summose PFOC F Sprinker Heads F Summose PFOC F Sprinker Heads (then yor less) BB Sprinker (PL)** F Sprinker Heads (then yor less) BC Fire Standpipe (SD) F Sprinker Heads (then yor less) F Summose PFOC F Sprinker Meads (then yor less) F Summose PFOC F Summose PFOC BD Water/San. (PL) P Santasy Piping (Sol & Vening) P Water Service Piping E Sewer Ejection Pump E Summose PFOC BD Water/San. (PL) P Santasy Piping (Sol & Vening) P Water Service Piping E Sewer Ejection Pump E Summose PFOC B Summose PFO	8	Α	Sprinkler (SP)														
E Bosses Pump - SP			Must mad be off														
F Foorfillager Control Valve F Summose PDC F Summose PDC F Symholer Heads F Summose PDC F Symholer Heads F Summose PDC F Symholer Heads (hirty or less) F Summose PDC F Summose PDC F Summose PDC F Summose PDC F Fine Pump F Foorfillager Control Valve F Hoose Cabiner/Rack-Valve F Hoose Cabiner/Rack-Valve F Summose PDC F Hoorfillager Control Valve F Hoorfillager Control Valve F Summose PDC F DC F Control Valve F Hoorfillager Control Valve F DC F DC F Control Valve F Hoorfillager Control Valve F DC F Control Valve F Hoorfillager Control Valve F DC F Control Valve F Hoorfillager Control Valve F DC F Control Valve F Hoorfillager Control Valve F DC F Control Valve F Hoorfillager Control Valve F DC F Control Valve F Hoorfillager Control Valve F DC F Control Valve F Hoorfillager Control Valve F DC F Control Valve F Hoorfillager Control Valve F Hoorfillager Control F Hoorfillager																	
F Somese FECE			domestic.														
F Sprinkler Hoads F Sprinkler Hoads F Sprinkler Hoads over 999 F Sprinkler Hoads (kinty or less) F F S																	
BB Sprinkler (PL)** F Sprinkler Heads (with yor less) BC Fire Standpipe (SD) P Standpipe Piping E' Special Service Fire Pump F Fiscor/Riser Control Valve F Hose Cabinet/Rack/Valve F Hose Makee F Hose																	
BB Sprinkler (PL)** F Sprinker Heads (thirty or less) RC Fire Standpipe (SD) Fire Pump Fire Fump Fire Fu																	
8C Fire Standpipe (SD) P: Standpipe Pipmg E: Special Service Fire Pump F: Floor/Risor Control Valve F: Hose Cabinet/Rack/Valve F: Hose Cabinet/Rack/Valve F: Hose Cabinet/Rack/Valve F: Sanitary Pipmig (Soil & Venting) P: Sanitary Pipmig (Soil & Venting) P: Vater Service Pipmig F: Sanitary Pipmig (Soil & Venting) P: Vater Service Pipmig F: Submeters F: Submeters F: Baltitubst/Whitpoolshot Tub/Sauna F: Biblet F: Contient/Cooler F: Dishwasher F: Dish				F Sprinkler Heads over 999													
E Fire Pump E Special Service Fire Pump F Floor/Riser Control Valve F Floor Cabinet Fack/Valve F Floor Cabinet Fack/Valve F Floor Cabinet Fack/Valve F Salmase FDC Salmase FDC P Water Piping P Water Piping E Submeters E Submeters F Bashtub-Whitipoots-Hot Tub/Sauna F Bidet F Continet Cooler F Domestic Water Tank/Pump F Poor Water Fank/Pump F Poor Water Fank/Pump F Poor Water Fank/Pump F Poor Water Fank/Pump F Rank/ Gardage Disposal F Lavatory (Common Wash Basin) F Lavatory (Common Wash Basin) F RAPZ/Backflow Preventer (Primary) F RAPZ/Backflow Preventer (Primary) F RAPZ/Backflow Preventer (Primary) F RAPZ/Backflow Preventer (Primary) F Sink - Non Residential F Stall Shower F Tankles Coil F Toilet (Water Closet) F Julinal F Stall Shower F Tankles Coil F Toilet (Water Closet) F Julinal F Water Heater (Non-Gas) BE Storm (PL) P Storm Dranage Piping E Newaryard Drain F Detertion Tank F Detertion	8	В	Sprinkler (PL)**														
E' Special Service Fire Pump F Roor/Riser Control Valve F Hose Cabine/FRack/Valve F Summers FDC Simmers FDC Simmers FDC P Sanitary Piping (Soil & Venting) P Water Spring P Water Service Piping E Server Epetich Pump E Simbush Vinited Piping E Simmers FDC F Contine For Pump E Simmers FDC F Contine For Pump E Simmers FDC F Contine For Pump F Discharge FDC F Discharge	8	С	Fire Standpipe (SD)	P* Standpipe Piping													
F Hose Cabins Pack Valve F Hose Cabins Pack Valve F Hose Cabins Pack Valve F Siames FDC F Siames FDC F Santary Pling (Sold & Venting) P Water Fining F Water Plining F Water Plining F Water Santour Plining F Santary Plining F Santary Plining F Siames FDC F Santary Plining F Siames FDC F Santary Plining F Siames F B Bathubar Whiripools Hot Tub/Sauna F Blatet F Chiller/Cooler F Dishwasher F Domestic Water Tank/Pump F Dinking Fountain F Floor Oranin F Gresse Trap/Oil Separator/GRD F Ice Maker F In-sink Garbago Disposal F Lavatory (Common Wash Basin) F Lavatory (Somom Wash Basin) F Lavatory (Somom Wash Basin) F FRZ58ackflow Preventer (Frimary) F RRZ58ackflow Preventer (Secondary) F Sink - Non Residential F Siali Shower F Tankless Coil F Siak - Residential F Siali Shower F Tankless Coil F Totel (Water Closet) F Totel Cooking Equipment (residential F Dry Water Heater (Non-Cas) F Read Drain F Read D				E* Fire Pump													
F Hose Cabinet/Rack/Valve F Samese FDC 8D Water/San, (PL)				E* Special Service Fire Pump													
F Samers FDC P Santary Piping (Soli & Venting) P Water Service Piping E Save Section Pump E Destroy Section Pump E Destroy Water Service Piping F Confliet Cooler F Destroy Water Tark/Pump F Destroy Foot Water Tark/Pump F Porting Fountain F Floor Oratin F Floor Oratin F In sink Garrage Disposal F Lavatory (Common Wash Basin) F Lavatory (Save Section Pump) F Pool F RPZ Fack Section Preventer (Primary) F Sink - Non Residential F Silla Shower F Tarkiess Coil F Totlet (Water Closet) F Totlet (Water Closet) F Totlet (Water Closet) F Totlet (Water Closet) F Water Heater Non Cas) F Section Propries F Cooking Equipment (residential) F Cookin				F Floor/Riser Control Valve													
BD Water/San. (PL) P Santary Piping (Soil & Venting) P Water Piping P Water Piping E Sever Ejection Piping E Sever Ejection Piping E Sever Ejection Piping E Southerers F Battrubs/WhitpoolsHot Tub/Sauna F Biddet F Chiler/Cooler F Dishwasher F Donnesic Water Tank/Pump F Dinking Fountain F Floor Drain F Gresse Trap/Oil Separator/GRD F loe Maker F lin-sink Carbage Disposal F Lavatory (Common Wash Basin) F Lavatory (Common Wash Basin) F RPZ/Backflow Preventer (Primary) F				F Hose Cabinet/Rack/Valve													
P Water Service Piging P Water Service Piging E Sewer Ejection Pump E Submeters F Submeters F Sathtubs/Whiripools/Hot Tub/Sauna F Sided F Chiller/Cooler F Dishwasher F Domestic Water Tank/Pump F Dinnking Fountain F Floor Drain F Floor Drain F In-sink Garbage Disposal F Lavatory (Common Wash Basin) F Lavatory (Common Wash Basin) F Lavatory (Common Wash Basin) F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Primary) F Sink - Non Residential F Sink - Residential F Sink - Residential F Sink - Non Sesidential F Sink - Non Sesidential F Sink - Sink Sesidential F Sink				F Siamese FDC													
P Water Service Piging P Water Service Piging E Sewer Ejection Pump E Submeters F Submeters F Sathtubs/Whiripools/Hot Tub/Sauna F Sided F Chiller/Cooler F Dishwasher F Domestic Water Tank/Pump F Dinnking Fountain F Floor Drain F Floor Drain F In-sink Garbage Disposal F Lavatory (Common Wash Basin) F Lavatory (Common Wash Basin) F Lavatory (Common Wash Basin) F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Primary) F Sink - Non Residential F Sink - Residential F Sink - Residential F Sink - Non Sesidential F Sink - Non Sesidential F Sink - Sink Sesidential F Sink	8	D	Water/San. (PL)	P* Sanitary Piping (Soil & Venting)													
E Sewer Ejection Pump E Submeters F Bathtube/Whiripools/Hot Tub/Sauna F Bidet F Chiller/Cooler F Dishwasher F Dinking Countain F Domsit Water Tark/Pump F Floor Drain F Gress Trap/Oil Separator/GRD F Ite Maker F In-sink Carbage Disposal F Lavalory (Common Wash Basin) F Laundry - Standpipe F Pool F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Primary) F Sink - Non Residential F Sink -			,														
E Sewer Ejection Pump E Submetters F Bathtube/Whirlpoots/Hot Tub/Sauna F Sidet F Chiller/Cooler F Chiller/Cooler F Dishwasher F Domestic Water Tank/Pump F Drinking Fountain F Floor Drain F Grease Trap/Oil Separator/GRD F Ice Maker F In-sink Garbage Disposal F Lavatory (Common Wash Basin) F Laundry - Standpipe F Pool F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Secondary) F RRZ/Backflow Preventer (Secondary) F Sink - Non Residential F Sink - Residentia											1						
E Submeters F Bathtubs/Whirlpools/Hot Tub/Sauna F Bidet F Chiller/Cooler F Dishwasher F Domestic Water Tank/Pump F Drinking Fountain F Floor Drain F In-sink Garbage Disposal F Lavatory (Common Wash Basin) F Laundry - Standpipe F Pool F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Secondary) F Sink - Non Residential F Silal Shower F Tankless Coil F Tankless Coil F Toilet (Water Closet) F Urnail F Washing Machine F Washing Machine F Washing Machine F Detention Tank F Detention				, 5													
F BathubaWhiripools/Hot Tub/Sauna F Bidet F Chiller/Cooler F Dishwasher F Domestic Water Tank/Pump F Drinking Fountain F Floor Drain F Floor Drain F Grease Trap/Oil Separator/GRD F Ilee Maker F Ile-sink Carbage Disposal F Lavadory (Common Wash Basin) F Laundry - Standpipe F Pool F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Secondary) F Sink - Non Residential F Sink - Residential F Water Heater (Non-Cas) 8E Storm (PL) P Storm Drainage Piping E Sump Pump F Area' Yard Drain F Detention Tank F Detention Tank F Dry Well/Retention F Roof Drain F Cooking Equipment (residential) F Cooking Equipment (residential) F Gas Boller (<ssk 6="" dryer="" f="" family)="" gas="" heater="" heater<="" non-comm.="" td="" water=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></ssk>																	
F Biddet F ChiterCooler F Dishwasher F Foor Drain F Floor Drain																	
F Chillen/Cooler F Dishwasher				-													
F Disthwesher F Domestic Water Tank/Pump F Disthing Fountain F Floor Drain F Floor Maker F In-sink Garbage Disposal F Lavatory (Common Wash Basin) F Laundry - Standpipe F Pool F RPZ/Eackflow Preventer (Primary) F RPZ/Eackflow Preventer (Primary) F RPZ/Eackflow Preventer (Secondary) F Sink - Non Residential F Sink - Sesidential F Sink - Sesidential F Sink - Residential F Sink - Residential F F Tankless Coil F Tankless Coil F Toilet (Water Closet) F Uninal F Water Heater (Non-Gas) F Water Heater (Non-Gas) F Water Heater (Non-Gas) F Water Heater (Non-Gas) F F Area/Yard Drain F Area/Yard Drain F Detention Tank F Detention Tank F Dremp F Area/Yard Drain F Detention Tank F Dremp F Gas Bouster Pump F Gas Bouster Pump F Gas Bouster Pump F Gas Bouster Pump F Gas Burner F Gas Water Heater F Medical (PL) P Medical Gas Piping F Medical (PL) P Medical Gas Piping F Medical Pump F Medical Gas Piping F Medical Pump F Medic																	
F Domestic Water Tank/Pump F Drinking Fountain F Drinking Fountain F Floor Drain F Grease Trap/Ol Separator/GRD F In-sink Garbage Disposal F Lavatory (Common Wash Basin) F Lavatory (Common Wash Basin) F Lavatory (Standpipe F Pool F Fool F F F F F F F F F																	
F Dinking Fountain F Floor Drain F Floor Drain F Grasse Trap/Oil Separator/GRD F Ico Maker F In-sink Garbage Disposal F ILavatory (Common Wash Basin) F ILavatory (Common Wash Basin) F ILavatory (Sommon Wash Basin) F In-sink Garbage Disposal F ILavatory (Common Wash Basin) F In-sink Garbage Disposal F In-sink																	
F Floor Drain																	
F Grease Trap/Oil Separator/GRD F Ice Maker F In-sink Garbage Disposal F ILavatory (Common Wash Basin) F ILavatory (Common Wash Basin) F ILavatory (Common Wash Basin) F In-sink Garbage Disposal I																	
F																	
In-sink Garbage Disposal																	
F Lavatory (Common Wash Basin) F Laundry - Standpipe																	
F Laundry - Standpipe F Pool F P																	
F Pool F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Secondary) F RPZ/Backflow Preventer (Secondary) F Sink - Non Residential F Sink - Residential F Sink - Residential F Sink - Residential F Stall Shower F Tankless Coil F Toilet (Water Closet) F Urinal F Washing Machine F Washing Machine F Washing Machine F Water Heater (Non-Gas) F Storm Orainage Piping F Sump Pump F Area/Yard Drain F Detention Tank F Dry Well/Retention F Detention Tank F Dry Well/Retention F Detention Tank F Dry Well/Retention F Roof Drain F E Emergency Shut-off Valve F F Gas Piping F Cooking Equipment (non-residential) F Cooking Equipment (residential) F Gas Burner F Gas Dryer F Gas Burner F Gas Mater F Gas Mater Heater F F Medical Gas Piping F Medical Gas Pipin																	
F RPZ/Backflow Preventer (Primary) F RPZ/Backflow Preventer (Secondary) F RPZ/Backflow Pre																	
F RPZ/Backflow Preventer (Secondary) F Sink - Non Residential F Sink - Residential F Sitall Shower F Sitall Sho																	
F Sink - Non Residential																	
F Sink - Residential																	
F Stall Shower F Tankless Coil F Toilet (Water Closet) F Toilet (Water Closet) F Toilet (Water Closet) F Urinal F Washing Machine F Water Heater (Non-Gas) F Water Heater (Non-Gas) F Storm Drainage Piping F Storm Drainage Piping F Storm Drainage Piping F Area/Yard Drain F Detention Tank F Dry Well/Retention F Roof Drain F Roof Drain F Roof Drain F Gas Piping F Cooking Equipment (non-residential) F Cooking Equipment (residential) F Gas Boiler (<350K, non-comm, <6 family) F Gas Burner F Gas Burner F Gas Meter F																	
F Tankless Coil F Toilet (Water Closet) F Urinal F Washing Machine F Water Heater (Non-Gas) F Storm Drainage Piping F Area/Yard Drain F Detention Tank F Dry Well/Retention F Roof Drain F Cas Piping F Gas Piping F Gas Piping F Cooking Equipment (non-residential) F Cooking Equipment (residential) F Gas Purper F G				F Sink - Residential													
F Toilet (Water Closet) F Urinal F Washing Machine F Water Heater (Non-Gas) F Sump Pump F Area/Yard Drain F Detention Tank F Detention Tank F Dry Well/Retention F Roof Drain F Roof Drain F Roof Drain F Roof Drain F Emergency Shut-off Valve F Fries Suppression Shut-off Valve F Fries Suppression Shut-off Valve F Gas Booster Pump F Cooking Equipment (non-residential) F Cooking Equipment (residential) F Gas Boiler (<350K, non-comm,<6 family) F Gas Burner F Gas Dryer F Gas Meter F Gas Water Heater F Gas Water Heater F Gas Water Heater F Gas Wedical (PL) P* Medical Gas Piping F Medica				F Stall Shower													
F Urinal F Washing Machine F Washing Machine F Water Heater (Non-Gas) F Water Heater (Non-Gas) F Water Heater (Non-Gas) F Storm Orainage Piping F Area/Yard Drain F Detention Tank F Dry Well/Retention F Roof Drain F Roof Drain F Gas Piping F Gas Piping F Gas Piping F Gas Piping F Gas Boiler (Solin Shut-off Valve F Gas Boiler (Solin Round Found Fou				F Tankless Coil													
F Washing Machine				F Toilet (Water Closet)													
F Water Heater (Non-Gas)				F Urinal													
P* Storm Drainage Piping E Sump Pump E Area/Yard Drain E Detention Tank E Detention Tank E Detention E Roof Drain E Emergency Shut-off Valve E Emergency Shut-off Valve E Emergency Shut-off Valve E Gas Booster Pump E Cooking Equipment (non-residential) E Cooking Equipment (residential) E Gas Boiler (<350K, non-comm,<6 family) F Gas Burner F Gas Dryer E Gas Meter F Gas Meter F Gas Water Heater E				F Washing Machine													
E Sump Pump F Area/Yard Drain F Detention Tank F Dry Well/Retention F Roof Drain 8F Gas (PL) P* Gas Piping E Emergency Shut-off Valve E* Fire Suppression Shut-off Valve E Gas Booster Pump F Cooking Equipment (non-residential) F Cooking Equipment (residential) F Gas Burner F Gas Burner F Gas Burner F Gas Burner F Gas Surnace F Gas Medical (PL) 8G Medical (PL) P* Medical Gas Piping				F Water Heater (Non-Gas)													
E Sump Pump F Area/Yard Drain F Detention Tank F Dry Well/Retention F Roof Drain 8F Gas (PL) P* Gas Piping E Emergency Shut-off Valve E* Fire Suppression Shut-off Valve E Gas Booster Pump F Cooking Equipment (non-residential) F Cooking Equipment (residential) F Gas Burner F Gas Burner F Gas Burner F Gas Burner F Gas Surnace F Gas Medical (PL) 8G Medical (PL) P* Medical Gas Piping	8	E	Storm (PL)														
F Detention Tank			` '														
F Detention Tank																	
F Dry Well/Retention																	
F Roof Drain											1						
8F Gas (PL) P* Gas Piping				-													
E Emergency Shut-off Valve E* Fire Suppression Shut-off Valve E Gas Booster Pump F Cooking Equipment (non-residential) F Cooking Equipment (residential) F Gas Boiler (<350K, non-comm,<6 family) F Gas Burner F Gas Dryer F Gas Furnace F Gas Meter F Gas Water Heater 8G Medical (PL) Emergency Shut-off Valve	8	F	Gas (PL)								1						
E* Fire Suppression Shut-off Valve E Gas Booster Pump F Cooking Equipment (non-residential) F Cooking Equipment (residential) F Gas Boiler (<350K, non-comm,<6 family) F Gas Burner F Gas Dryer F Gas Furnace F Gas Meter F Gas Water Heater 8G Medical (PL) * Medical Gas Piping	C	•	550 (i L)	. Journal of the state of the s							1						
E Gas Booster Pump F Cooking Equipment (non-residential) F Cooking Equipment (residential) F Gas Boiler (<350K, non-comm,<6 family) F Gas Burner F Gas Dryer F Gas Furnace F Gas Meter F Gas Water Heater 8G Medical (PL) P* Medical Gas Piping											1						
F Cooking Equipment (non-residential) F Cooking Equipment (residential) F Gas Boiler (<350K, non-comm,<6 family) F Gas Burner F Gas Dryer F Gas Furnace F Gas Meter F Gas Water Heater 8G Medical (PL) P* Medical Gas Piping											1						
F Cooking Equipment (residential) F Gas Boiler (<350K, non-comm,<6 family) F Gas Burner F Gas Dryer F Gas Furnace F Gas Meter F Gas Water Heater 8G Medical (PL) P* Medical Gas Piping											1						
F Gas Boiler (<350K, non-comm,<6 family) F Gas Burner F Gas Dryer F Gas Furnace F Gas Meter F Gas Water Heater 8G Medical (PL) P* Medical Gas Piping									 		1						
F Gas Burner F Gas Dryer F Gas Furnace F Gas Meter F Gas Water Heater 8G Medical (PL) P* Medical Gas Piping																	
F Gas Dryer											1						
F Gas Furnace																	
F Gas Meter											1						
F Gas Water Heater 8G Medical (PL) P* Medical Gas Piping											1						
8G Medical (PL) P* Medical Gas Piping																	
	_	_															
E Assorted Medical Equipment	8	G	Medical (PL)	, , , , , , , , , , , , , , , , , , ,													
				E Assorted Medical Equipment													


^{**} Must be off domestic.

^{*} Indicates test *may* be required.



PW2: Work Permit Application

Must be typewritten.



			BIS Document No., required:
1 Reason For Filing Requi	red for all applicatio	ns.	
Initial Permit Complete all se	ctions. Expected v	ork start date:	Renewal Permit with changes Complete all sections.
No Work Permit			Renewal Permit without changes 1, 3, 4, 7 - 12
2 Location Information Re	equired for all applic	ations.	
House No(s)	Street Name		
Borough	Block	Lot	BIN C.B. No.
Work on Floor(s)			Apt. / Condo No(s)
3 Type of Permit Choose o	ne and complete an	y appropriate sub-choices	or other information.
Filed as NB (28-101.4-5)	Curb Cut Demolition and Rem	<u>—</u>	Plumbing 3C 3A Electrical application no. for shed lighting: Sign
Construction Equipment	Fire Suppression Sy Foundation / Earthw	a.o. otorago	Sprinkler 3C 3B Related fence job no. Standpipe 3C 3C Secondary permit description (if applies):
	Area of site (sq. ft):	New Building 3E	
□ Oth arri	Earthwork Only		
Yes No Are you pe area of the	rforming a vertical on the adding more than ing?	of or more of the Yes Yes Yes Yes Yes Yes Yes Yes Yes Ye	building? If yes, 8
4 Applicant / Contractor /	Required for all appl	cations. (* Indicates option	nal.)
Last Name		First Name	Middle Initial
Business Name			Business Telephone
Business Address	Cta	ato Zio	*Business Fax
City *E-Mail	Sta	ite Zip	*Mobile Telephone Taxpayer ID
General Contractor Fire Suppression Contractor Master Plumber Oil Burner Installer Sign Hanger	4A, 4B 4A 4C,4D 4B 4C,4D 4C 4C,4D 4D	Provide registration or tra Does work require a HIC License Number: Is applicant responsible for If no, describe work responses	license? No If yes, HIC license number: or all work on this application? Yes No
Professional Engineer Registered Architect Homeowner DOB approval required.	4C, 6 4C, 6		v



5	Filing Representative Complete if different	from applicant spec	ified in section 3. (*	Indicates	optional.)		
	Last Name	First Nam	ne		Middle Initial		
-	Business Name				Business Telephone		
-	Business Address				*Business Fax		
-	City	State Z	ip		*Mobile Telephone		
-	*E-Mail			F	Registration Number		
6	Insurance P.E. / R.A. only (* indicates requ	ired for all permits)					
	Liability Insurance (NB permits only)	Workers' Compensa	tion Insurance*	Disabi	ility Insurance *		
7	Construction Superintendent, Site Safe	ty Coordinator, S	ite Safety Manag	er Requi	ired if applicable. (* Inc	dicates optional.)	
ı	, the applicant / contractor, hereby declare the s	cope of work filed un	der this permit appli	cation red	quires: (choose one)		
	☐ Construction Superintende	nt 🔲	Site Safety Coordi	inator		Site Safety Manager	
-	Last Name	First Name			Middle Initial		
-	Business Name				Telephone		
-	Address				*Fax		
-	City Sta	te Zip			*Mobile Telephone		
-	*E-Mail			R	legistration Number		
	I, the undersigned, will perform, on behalf of the Coordinator, or Site Safety Manager (identified	Contractor, all of the above) as set forth in	e functions required the Department of B	quired of a Construction Superintendent, or Site Safety ent of Buildings rules and regulations.			
	Name (print)	Notarization State of New York,	County of:		Notary Seal		
-	Signature	Sworn to or affirme	d under penalty of p	erjury			
		day of		20			
=	Date	Notary Signature					
-							
8	Demolition Subcontractor Required if app	olicable. (* Indicates	optional.)				
	☐ Yes ☐ No Is the applicant/contractor na	med in section four p	performing the demo	lition wor	k for this permit? If no,	complete this section.	
÷	Last Name	First Name			Middle Initial		
-	Business Name				Telephone		
-	Address				*Fax		
-	City Sta	te Zip			*Mobile Telephone		
-	*E-Mail	<u> </u>		R	Registration Number		
-	I, the undersigned, will perform, on behalf of the Department of Buildings rules and regulations.	Contractor, all of the	e functions required	of a Dem	olition Subcontractor a	s set forth in the	
	Name (print)	Notarization State of New York,	County of:		Notary Seal		
-	Signature	Sworn to or affirme	d under penalty of p	erjury			
		day of		20			
	Date	Notary Signature					

PW₂ PAGE 3 Concrete Information Choose and complete any appropriate sub-choices. Are you requesting to exclude concrete work at Does your approved work include 2,000 cubic 9B Yes No 9A ☐ Yes ☐ No this time from this permit? If no, 9B yards or more of concrete? If yes, 10 and 11 Concrete Subcontractor Required if applicable. (* Indicates optional.) Is the applicant/contractor named in section four performing the concrete work for this permit? If no, complete this section. ☐Yes ☐ No Last Name First Name Middle Initial **Business Name** Telephone Address *Fax Zip City State *Mobile Telephone *E-Mail Registration Number I, the undersigned, will perform, on behalf of the Contractor, all of the functions required of a Concrete Subcontractor as set forth in the Department of Buildings rules and regulations. Name (print) Notarization Notary Seal State of New York, County of: Sworn to or affirmed under penalty of perjury Signature day of 20 Date **Notary Signature** Concrete Safety Manager Required if applicable. (* Indicates optional.) Middle Initial Last Name First Name **Business Name** Telephone Address *Fax City State Zip *Mobile Telephone *E-Mail Registration Number I, the undersigned, will perform, on behalf of the Contractor, all of the functions required of a Concrete Safety Manager (identified above) as set forth in the Department of Buildings rules and regulations. **Notary Seal** Name (print) Notarization State of New York, County of: Signature Sworn to or affirmed under penalty of perjury day of Date Notary Signature Applicant / Contractor Statements and Signatures Required for all applications. The information in this application is correct and complete to the best of my knowledge and I assume responsibility for all statements on this form. I understand that if I am found after hearing to have knowingly or negligently made a false statement on this or any other document submitted to the Department, I may be subject to fine, imprisonment, and/or barred from filing further documents with the Department. I also understand it is unlawful to give to a city employee, or for a city employee to accept, any benefit, monetary or otherwise, either as a gratuity for properly performing the job or in exchange for special consideration. I will comply with all applicable laws, rules and regulations including all insurance requirements, and, in addition. · I hereby state if a Construction Superintendent, Site Safety Coordinator, Site Safety Manager, Demolition Subcontractor, Concrete Subcontractor, or Concrete Safety Manager is required for this application I have hereby advised the individual listed herein he or she is designated as such and hereby certify he or she is registered and in good standing with the NYC Department of Buildings. · I hereby state this renewal application with no change to Applicant, Filing Representative, Construction Superintendent, Site Safety Coordinator, Site Safety Manager, Subcontractors, Concrete Safety Manager or insurance is for the work as originally filed or as officially amended. In accordance with §28-104.8 of the Administrative Code, I hereby declare I am authorized by the owner of the above-referenced premises to make this application for a permit to perform the work described herein. In accordance with Rule 101-16, I will post the permit in a conspicuous and visible location. Check here if the work authorized by this permit does NOT require adjacent property insurance Notarization (required if not licensee) Licensee Seal or Notary Seal Name (print) State of New York, County of: Signature Sworn to or affirmed under penalty of perjury

day of

Notary Signature


Date

20



PW3: Cost Affidavit

Must be typewritten.



1	Reason For Filing F	Required for all appli	cations.						
	Reason for filing cost a Initial Filing 2-7 Prior to Approval Actions Post Approval Amendme To obtain Sign-off 2-3, 8	s <i>1A,</i> 2-7 ent (PAA) <i>1A, 2-</i> 7	Estimate Estimate Estimate	formation provided ed cost of construction ed cost of construction ed cost of construction construction cost of construction	on on on	_	1A Indicate ex affected by	-	nt number
2	Location Information								
	House No(s)	Street N	lame						
	Borough		Block	Lot	BIN		C.B. No).	
3	Cost Details Require	d for all applications	ì.						
	Cost estimates shall include and labor; work shall include ances. Indirect costs, includi reflected in the unit costs sh can show detailed estimates "No" must be specified for Categories of Work (M. Yes No	e all construction eleme ng but not limited to ger own. If in the opinion of s to meet the approval of r each "Category of W ust match all applicable	ents including neral conditions of the Departions of the Departions fork" listed	g, but not limited to, co ons, insurance, and an ment, the valuation is u trment. The initial, ame below.	nstruction equal allowance for p nderestimated	ipment, wall and profit and overhed on the applicati	d floor finishes, bead shall be adde ion, the permit should be valuation shall be	uilt-in cabinets, d to direct work all be denied, un	and kitchen appli- costs and shall be less the applicant
	Boiler (BL) Fire Alarm (FA) Fuel Burning (F Fuel Storage (F Fire Suppressio Mechanical (MF Plumbing (PL)	B) [S) [n (FP)	Spr Sigi	ndpipe (SD) inkler (SP) ns (SG) er (OT) Antenna (OT/ANT) Fire Protection Plan (C Marquee (OT/MAR) (Describe)	ot/FPP)		General Cons Partial Dem Non-Structu Structural V Interior Rer Exterior Re (Describe)	nolition ural Demolition Vork novation novation	
	Category of Work*	Description of Wo	rk			Area/Units	Unit Cost (\$)	Total Cost (\$)	Work Category Total Cost (\$)
							TOTAL .	JOB COST: \$	


*List ALL Categories of Work specified "Yes" above. Use more than one line for Categories of Work that involve multiple unit costs. See PW3 Form Instructions for a sample of completed Section 3 Cost Details.

PW3

Design Applicant Info	rmation					
Last Name		Firs	st Name		Middle Initial	
Business Name		Business	s Phone		Business Fax	
Business Address					Mobile Phone	
City	State		Zip		E-Mail	
License Number	Choose One:	□P.E.	R.A.	Sign Hanger	Other (specify)	
Owner/Lease Holder I	nformation					
Last Name		Fire	st Name		Middle Initial	
Business Name		Business	s Phone		Business Fax	
Business Address					Mobile Phone	
City	State		Zip		E-Mail	
Design Applicant's St	atements and Signatu	res				
ment or to have knowingly or neglig the provisions of this code or of a ru Name (print)	ently falsified or allowed to be falsi le of any agency, I may be barred f	fied any certificate, rom filing further ap	form, signed st	atement, application, rep cuments with the Depart	port or certification of the correction of a violation of the correction of the correction of a violation of the correction of	ation required under
				P.E. / R.A.	Seal (apply seal, then sign and d	ate over seal)
Owner's/Lease Holder	's Statements and Sig	natures No	tary <u>only</u> r	equired when su	bmitting to obtain sign-off.	
imprisonment, or both. I also under the job or in exchange for special of	stand it is unlawful to give to a city onsideration. Violation is punishab ly or negligently falsified or allowe code or of a rule of any agency, I r	employee, or for a le by imprisonment d to be falsified a nay be barred from rization	city employee to or fine or both on certificate, for filling further ap	o accept, any benefit, m I understand that if I a rm, signed statement, a	any statement is a misdemeanor and is pun onetary or otherwise, either as a gratuity for im found after hearing to have knowingly or pplication, report or certification of the corr with the Department. Notary Seal	properly performing negligently made a
Signature		e of New York, C on to or affirmed	,	of periury		
Cignataro		day of	arraer periarry	20		
Date	Nota	ry Public Signati	Ire	20		
Duto	11010	Ty i ubilo olgilati				
Internal Use Only						
Internal Use Only Work Area	PW3 Cost Details Valid	ation		Comments (M	ay include cost guidance.)	Initials
////		ation Revised Cost	Needed	Comments (M	ay include cost guidance.)	Initials
Work Area	PW3 Cost Details Valid			Comments (M	ay include cost guidance.)	Initials




PW4: Application for Certificate of Compliance for Equipment



Must be typewritten. **Filing Status** Job Number Type of Equipment Required for all applications. Heating System Ventilation System Air Conditioning System Refrigeration (Not including boilers) Location Information Required for all applications. House No. Street Name Apt/Condo No(s) Borough Block Lot BIN CB No. Work on Floor Applicant Information Required for all applications. First Name Middle Initial **Business Name Business Telephone Business Address Business Fax** State Zip Mobile Telephone City E-Mail \square R.A. □P.E Other License Number Equipment Specifications Instructions for section (complete all). Item-Manufacturer/Trade Name No. of Floor **Certification Number for Listing** Capacity: Items BTUs/CFM Statement and Signatures Required for all applications. The owner certifies that he authorizes the applicant to perform the proposed work in accordance with plans and specifications approved under said application. Falsification of Name (please print) any statement is a misdemeanor and is punishable by a fine or imprisonment, or both. It is unlawful to give to a city employee, or for a city employee to accept, any benefit, monetary or otherwise, either as a gratuity for properly performing the job or in exchange for special consideration. Violation is punishable by imprisonment or both. Signature Date Owner Name Title Signature Date I hereby certify that the work indicated above has been done in a manner required by the Rules and Regulations of the Department of Buildings except where reported adversely. Name: P.E. / R.A. Seal (apply seal, then sign and date over Inspector's Signature: Date Signed Off: INTERNAL USE ONLY Examined and Recommended for Approval Yes Approved Yes No Examiner **Borough Commissioner** Signature Date Signature Date



PW7: Certificate of Occupancy / Letter of Completion Folder Review Request




Must be typewritten

1	Location Informatio	n				
7	House No(s)	Street Name		Work Pr	roposed on Floor No(s)	
	Borough	Block	Lot	BIN	CB No.	
2	Requestor Informati	ion				
	Individuals Relationship	to Job (example: applicant, own	er filing represen	tative)		
	Last Name		First Name		Middle Initial	
	Business Name				Business Telephone	
	Business Address	21.1			Business Fax	
	City E-Mail	State	Zip		Mobile Telephone License Number	
	E-IVIAII				License Number	
3	Type of Request Ch	oose one .				
	, ,	irective 14 or Non-Directive 14)				
	TCO - Temporary Certification be issued) 3A	ficate of Occupancy (Borough Co	ommissioner's Of	ffice may be required.	All requirements must be fulfilled before	fore a TCO will
	Renewal of TCO - Tem		(Borough Commi	issioner's Office appro	oval may be required. All requirement	s must be
_	fulfilled before a TCO w Final Certificate of Occi	, .				
Ш		dress, block/lot, metes and bour	nde only (28-118 :	16 2)		
	I Change of au	uress, blockriot, metes and bour	lus offiy (20-110.	10.2)		
4	Comments If addition	nal space is required, write "see n	A1-1" here and so	ubmit a completed A1	-1 form with this request.	
5	Statements and Sig	natures				
	Administrative Building Code ar		r both. It is unlawful to	give to a city employee, or	of any statement is a misdemeanor under § 26 for a city employee to accept, any benefit, mone ment or fine, or both.	
	Requestor Signature				Date	
///.	Borough Commissio	ner's Office TCO Authoriza	tion Do not write	te in this section		
	Comments:	ner 3 Office 100 Authoriza	ILIOIT DO NOT WITE	te iii tiiis section.	<u> </u>	
	Comments.					
1						
l	Authorized Name (please	e print)		Approve	ed Disapproved	
Ī	Authorization Signature (if approved only)		Date		
///	Disapproval Reasons	Review request cannot be prod	cessed for the following	lowing reasons:		
					□ Audit Conditions Danding / La	h an Hald
	Fees unpaid	☐ Open ECB/DOB Violation	` '	omplete PAA	☐ Audit Conditions Pending / Jo	
	· .	. ,	☐ Plumbing	☐ Electrical	Other:	
	☐ Missing Required iten					
		mplete: Form(s)		Section(s)/Reason(s		
	Other:					



TR1: Technical Report Statement of Responsibility



This form must be typewritten

1	Location Information Required for all applic	cations.				
	House No(s) Street Name					
	Work on Floor(s)					
2	Applicant Information Required for all appl	lications.				
	Choose all that apply: Design Applicant 3A,	4A, 5 S	pecial Inspections Ap	plicant 3B-D, 6-9	Progress Inspections Ap	plicant 4B-D, 6-9
	Last Name		First Name		Middle Initial	
			1 list Name			
	Business Name				Business Telephone	
	Business Address				Business Fax	
	City	State	Zip		Mobile Telephone	
	License Type choose one: P.E.	R.A.	Other:		License Number	
					Special Inspection	
					Agency Number	
3	Special Inspection Categories Required for	or all applica	ations, continued on p	page 2; indicates	report required.	
3A	← Identification of Requirement			3B Identification of Responsibilities	3C Certificate of Complete	3D Withdraw Responsibilities
Υ	N Special Inspections		Code/Section	Initial & Date	Inspections / Tests Initial & Date	Initial & Date
	Structural Steel – Welding		BC 1704.3.1			
	Structural Steel – Details		BC 1704.3.2			
	Structural Steel – High Strength Bolting		BC 1704.3.3			
	Structural Cold-Formed Steel		BC 1704.3.4			
	Concrete – Cast-In-Place		BC 1704.4			
	Concrete – Precast		BC 1704.4			
	Concrete – Prestressed		BC 1704.4			
	Masonry		BC 1704.5			
=	Wood – Installation of High-Load Diaphragms		BC 1704.6.1			
=+	Wood – Installation of Metal-Plate-Connected Trusses		BC 1704.6.2			
= :	Wood – Installation of Prefabricated I-Joists		BC 1704.6.3			
	Subgrade Inspection		BC 1704.7.1			
	Subsurface Conditions – Fill Placement & In-Place		BC 1704.7.2			
П	☐ Density ☐ Subsurface Investigations (Borings/Test Pits)	TR4	BC 1704.7.3 BC 1704.7.4			
H	Deep Foundation Elements	TR5	BC 1704.8			
		TR5H	BC 1704.8.5			
	Vertical Masonry Foundation Elements		BC 1704.9			
	Wall Panels, Curtain Walls, and Veneers		BC 1704.10			
-	Sprayed fire-resistant materials		BC 1704.11			
= :	Mastic and Intumescent Fire-resistant Coatings		BC 1704.12			
	Exterior Insulation and Finish Systems (EIFS)		BC 1704.13			
= :	☐ Alternative Materials - OTCR Buildings Bulletin # ☐ Smoke Control Systems		BC 1704.14 BC 1704.15			
= :	Mechanical Systems		BC 1704.16			
=	Fuel-Oil Storage and Fuel-Oil Piping Systems		BC 1704.17			
= -	High-Pressure Steam Piping (Welding)		BC 1704.18			
==:	☐ High Temperature Hot Water Piping (Welding)		BC 1704.18			
	High-Pressure Fuel-Gas Piping (Welding)		BC 1704.19			
	Structural Stability – Existing Buildings		BC 1704.20.1			
	Excavations—Sheeting, Shoring, and Bracing		BC 1704.20.2			
	Underpinning		BC 1704.20.3 BC 1814			
	Mechanical Demolition		BC 1704 20 4			



TR1: Technical Report Statement of Responsibility

This form must be typewritten

3	Special Inspection Categories (continu	ued) Required for all applications,	continued on page 2	2; Indicates report requir	red.		
3A	← Identification of Requirement		3B Identification of Responsibilities	3C Certificate of Complete Inspections / Tests	3D Withdraw Responsibilities		
Υ	N Special Inspections	Code/Section	Initial & Date	Initial & Date	Initial & Date		
	Raising and Moving of a Building	BC 1704.20.5					
	Soil Percolation Test - Private On-Site Storm Water Drainage Disposal Systems, and Detention Facilities	BC 1704.21.1.2					
	Private On-Site Storm Water Drainage Disposal Systems, and Detention Facilities Installation	BC 1704.21.2					
	Individual On-Site Private Sewage Disposal Systems	BC 1704.22					
	Soil Percolation Test - Individual On-Site Private Sewage Disposal Systems	BC 1704.22					
	Sprinkler Systems	BC 1704.23					
	Standpipe Systems	BC 1704.24					
П	Heating Systems	BC 1704.25					
=	Chimneys	BC 1704.26					
	☐ Fire-resistant Penetrations and Joints	BC 1704.27					
_	Aluminum Welding	BC 1704.28					
	☐ Flood Zone Compliance (attach FEMA elevation/dry	BC 1704.29					
ш	floodproofing certificate where applicable)	BC G105					
	Luminous Egress Path Markings	■ TR7 BC 1704.30 BC 1024.8					
\equiv	☐ Emergency and Standby Power Systems (Generators						
_	Post-installed Anchors (BB# 2014-018, 2014-019)	BC 1704.32					
=	Seismic Isolation Systems	BC 1707.8					
	Concrete Design Mix	■ TR3 BC 1905.3					
	Condition Design with	BC 1913.5	Subm	it TR3 to complete this it	em		
	Concrete Sampling and Testing	■ TR2 BC 1905.6 BC 1913.10	Subm	it TR2 to complete this it	em		
	4 Progress Inspection Categories Required for all applications.						
4	Progress Inspection Categories Require	ed for all applications.	report required.				
4 4A		ed for all applications.	4B Identification of	4C Certificate of Complete	4D Withdraw		
	<u> </u>	ed for all applications. Indicates Code/Section	4B Identification of Responsibilities	Inspections / Tests	Responsibilities		
	← Identification of Requirement		4B Identification of				
Y	← Identification of Requirement N Progress Inspections	Code/Section	4B Identification of Responsibilities	Inspections / Tests	Responsibilities		
Y	← Identification of Requirement N Progress Inspections Preliminary	Code/Section 28-116.2.1, BC 110.2	4B Identification of Responsibilities	Inspections / Tests	Responsibilities		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1	4B Identification of Responsibilities	Inspections / Tests	Responsibilities		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation Lowest Floor Elevation	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3	4B Identification of Responsibilities Initial & Date	Inspections / Tests	Responsibilities Initial & Date		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation Lowest Floor Elevation Structural Wood Frame	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3	4B Identification of Responsibilities Initial & Date	Inspections / Tests Initial & Date	Responsibilities Initial & Date		
Y	← Identification of Requirement N Progress Inspections □ Preliminary □ Footing and Foundation □ Lowest Floor Elevation □ Structural Wood Frame □ Energy Code Compliance Inspections	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 BC 110.3.5 BC 110.3.4 28-116.2.2	4B Identification of Responsibilities Initial & Date	Inspections / Tests Initial & Date	Responsibilities Initial & Date		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation Lowest Floor Elevation Structural Wood Frame Energy Code Compliance Inspections Fire-Resistance Rated Construction Public Assembly Emergency Lighting	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5,	4B Identification of Responsibilities Initial & Date	Inspections / Tests Initial & Date	Responsibilities Initial & Date		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation Lowest Floor Elevation Structural Wood Frame Energy Code Compliance Inspections Fire-Resistance Rated Construction Public Assembly Emergency Lighting Final* Dire	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10	4B Identification of Responsibilities Initial & Date	Inspections / Tests Initial & Date	Responsibilities Initial & Date		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation Lowest Floor Elevation Structural Wood Frame Energy Code Compliance Inspections Fire-Resistance Rated Construction Public Assembly Emergency Lighting Final* Directions Column 4C, indicate date when the actual final inspections	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 R8 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed	4B Identification of Responsibilities Initial & Date Subm	Inspections / Tests Initial & Date Initial & Date	Responsibilities Initial & Date		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation Lowest Floor Elevation Structural Wood Frame Energy Code Compliance Inspections Fire-Resistance Rated Construction Public Assembly Emergency Lighting Final* Dire	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 R8 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed	4B Identification of Responsibilities Initial & Date Subm	Inspections / Tests Initial & Date Initial & Date	Responsibilities Initial & Date		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation Lowest Floor Elevation Structural Wood Frame Energy Code Compliance Inspections Fire-Resistance Rated Construction Public Assembly Emergency Lighting Final* Directions Column 4C, indicate date when the actual final inspections	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 R8 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed	4B Identification of Responsibilities Initial & Date Subm	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation Lowest Floor Elevation Structural Wood Frame Energy Code Compliance Inspections Fire-Resistance Rated Construction Public Assembly Emergency Lighting Final* Directions Column 4C, indicate date when the actual final inspections	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 R8 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed	4B Identification of Responsibilities Initial & Date Subm	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation Lowest Floor Elevation Structural Wood Frame Energy Code Compliance Inspections Fire-Resistance Rated Construction Public Assembly Emergency Lighting Final* Direction of Requirement Development of Requirement Design Applicant's Statements and Signature Designature	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed Gnatures P.E./R.A. responsible in	4B Identification of Responsibilities Initial & Date Subm	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		
Y		Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed Gnatures P.E./R.A. responsible in	4B Identification of Responsibilities Initial & Date Subm	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		
Y	← Identification of Requirement N Progress Inspections Preliminary Footing and Foundation Lowest Floor Elevation Structural Wood Frame Energy Code Compliance Inspections Fire-Resistance Rated Construction Public Assembly Emergency Lighting Final* Direction of Requirement Development of Requirement Design Applicant's Statements and Signature Designature	Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed Gnatures P.E./R.A. responsible in	4B Identification of Responsibilities Initial & Date Subm	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		
Y		Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed Gnatures P.E./R.A. responsible in	4B Identification of Responsibilities Initial & Date Subm For plans, choose both Name (please	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		
Y		Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 R8 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed gnatures P.E./R.A. responsible in progress inspections and tests	4B Identification of Responsibilities Initial & Date Subm For plans, choose both Name (please Signature	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		
Y		Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 R8 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed gnatures P.E./R.A. responsible in progress inspections and tests	4B Identification of Responsibilities Initial & Date Subm For plans, choose both Name (please Signature	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		
Y		Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 R8 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed gnatures P.E./R.A. responsible in progress inspections and tests	4B Identification of Responsibilities Initial & Date Subm For plans, choose both Name (please Signature	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		
Y		Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 R8 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed gnatures P.E./R.A. responsible in progress inspections and tests	4B Identification of Responsibilities Initial & Date Subm For plans, choose both Name (please Signature	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		
Y		Code/Section 28-116.2.1, BC 110.2 BC 110.3.1 BC 110.3.2 BC 110.3.3 R8 BC 110.3.5 BC 110.3.4 28-116.2.2 28-116.2.4.2, BC 110.5, ctive 14 of 1975, and 1 RCNY §101-10 ion was performed gnatures P.E./R.A. responsible in progress inspections and tests	4B Identification of Responsibilities Initial & Date Submi	Inspections / Tests Initial & Date Initial & Date It TR8 to complete this it	Responsibilities Initial & Date		

TR1 PAGE 3

Owner's Statement and Signature for Progress/Special Inspector Required when inspection applicant identifies responsibilities.

I have reviewed the information provided herein and, to the best of my knowledge and belief, attest to its accuracy. I approve the identification of the responsible inspector. Falsification of any statement is a misdemeanor and is punishable by a fine or imprisonment, or both. It is unlawful to give to a city employee, or for a city employee to accept, any benefit, monetary or otherwise, either as a gratuity for properly performing the job or in exchange for special consideration. Violation is punishable by a fine or imprisonment, or both. I understand that if I am found after hearing to have knowingly or negligently made a false statement or to have knowingly or negligently falsified or allowed to be falsified any certificate, form, signed statement, application, report or certification of the correction of a violation required under the provisions of this code or of a rule of

	any agency, I may be barred from filing further applications or documents with the Department.	
	Name (print) Title	
	Signature Date	
7	7 Inspection Applicant's Identification of Responsibilities	
	Check all that apply below:	
	For the special inspections indicated above in section 3, I certify that I am the principal/director of the special inspection ag responsibility for conducting the inspections. I further certify that I have read the applicable sections of the New York City Co connection with special inspections as well as 1 RCNY 101-06 Rule, which specifies the qualifications required for each insp agency meets those qualifications for each and every special inspection for which I/we take responsibility. I agree that both comply with all provisions of the New York City Construction Codes and the Rule. I am aware of the additional sanctions imp by §28-211.1.2 of the Administrative Code.	onstruction Codes in section and that this I and the agency will
	For the progress inspections indicated above in section 4, except energy code inspections on the TR8 form, and/or concre indicated in section 3, I assume the responsibility and I personally, or where permitted by the New York City Construction Copersonnel under my direct supervision, will perform the required inspections and tests on such forms and in such matter as the requires or requests. I am aware of the additional sanctions imposed on false filings by §28-211.1.2 of the Administrative Construction	odes, qualified he Department
	Final Inspection: I will make final inspection of the construction work, including those inspections during its progress necessary to my certifical inspection that all work substantially conforms to approved construction documents and applicable laws and rules. I will confi performance of progress inspections and other inspections has been documented before I report the work complete. As pres 101-10, I will perform the final inspection within 1 year from the expiration of the last valid permit of the work.	irm that the
	Upon completion of the work and within 30 days of my final inspection, I will file a certification attesting to the fact that all wor completed in accordance with the approved construction documents, laws and rules, except as reported otherwise.	k was performed and
	I understand that my failure to file a certification of completion or to notify the Department of my withdrawal of respone year from expiration of the last valid permit may result in the loss of my privileges to file under Directives 2 and issuance of a violation, or both. I am aware of the additional sanctions imposed on false filings by §28-211.1.2 of the Code.	l 14 of 1975 or
	Change of Applicant: I am a newly designated individual responsible for the items specified herein and I hereby state that:	
	None of the inspections/tests indicated herein have been performed to date by the previously designated individual.	
	Some of the inspections/tests indicated herein have been performed by the previously designated individual, as indicated in the attached report.	
	I am aware of the additional sanctions imposed on false filings by §28-211.1.2 of the Administrative Code. Name (please print)	
	Signature Date	
	P.E. / R.A. Seal (apply seal, then sign and date over seal)	
8	8 Inspection Applicant's Certification of Partial Completion 9 Inspection Applicant's Certification of	f Full Completion
•	I have completed the items specified herein and certify that all work performed substantially conforms to approved construction documents and has been performed in accordance with applicable provisions of the New York City Construction codes and other designated rules and regulations.	accordance with Construction Codes

attached report.

☐ Withdrawal of Applicant: I am withdrawing responsibility for the items of special/progress inspections and/or tests indicated herein and herewith submit the results or status of the work performed

I am aware of the additional sanctions imposed on false filings by §28-211.1.2 of the Administrative Code.

Name (please print)

Signature

P.E. / R.A. Seal (apply seal, then sign and date over seal)

I am aware of the additional sanctions imposed on false filings by §28-211.1.2 of the Administrative Code.

Name (please print)

Signature

Date

P.E. / R.A. Seal (apply seal, then sign and date over seal)

Date

NYCDOT





Department of Transportation

APPLICATION FOR ROADWAY/SIDEWALK PERMIT(S)

* See reverse for instructions on how t SECTION A: Applicant Information	o complete this form.		Rev. 9/15/10
•	2. Permittee Name:		
4. Tel #:()			
SECTION B: Work Information	O. L. Wall.		
6. Borough: MN BK	ON OBX OSI	7. OCMC File:	
-	b. Sidewalk		
	On Street:		
	n Above:		
·			
12. Between:	(Cross Street #1)	and(Cross Street #2)
13. For the Purpose of:			
14. Number of Openings:	15. Area Size:(In Square Feet	16. Frontage Length:	(In Linear Feet)
	(in Square Feet		
SECTION C: Type of Permit Requested (16. Work Ella Bate.	
STREET OF	PENING PERMITS	BUILDING OPERAT	
0100 OPEN SIDEWALK TO INSTAL		0201 PLACE MATERIAL ON STREET 0202 CROSSING SIDEWALK	
0113 REPAIR WATER		0203 PLACE CRANE OR SHOVEL ON	-
☐ 0114 REPAIR SEWER ☐ 0115 REPAIR WATER/SEWER		0204 PLACE EQUIPMENT OTHER TO 0205 PLACE SHANTY OR TRAILER (HAN CRANE OR SHOVEL ON STREET ON STREET
0116 FUEL OIL LINE	ALTERATION.	0208 TEMPORARY PEDESTRIAN WA	
0117 VAULT CONSTRUCTION OR 0118 RESET, REPAIR OR REPLAC		0211 OCCUPANCY OF ROADWAY A 0214 PLACE CONTAINER ON STREE	
0119 PAVE STREET 0126 TEST PITS, CORES OR BOR	NGS.	0215 OCCUPANCY OF SIDEWALK A 0221 TEMPORARY CONSTRUCTION	
0127 CONDUIT CONSTRUCTION (CABLE, TELECOMM. AND FRANCHISE)	CANOPY P	
0132 INSTALL FENCE SIDEWALK CON:	STRUCTION PERMITS	0701 CANOPY FOR HOTEL 0702 CANOPY FOR RESTAURANT	
0401 REPAIR SIDEWALK		0703 CANOPY FOR RESIDENCE	
0402 CONSTRUCT NEW SIDEWAL 0403 REPLACE SIDEWALK	.K	0704 CANOPY FOR MISCELLANEOU 0705 CANOPY FOR SIDEWALK CAF	
0405 CONSTRUCT NEW SIDEWAL	K - BUILDERS PAVEMENT	Other Type of Permit	
SECTION D: Work Zone Sketch (Include	On Street, both Cross Streets, North Arrow, Si	dewalk/Roadway widths and proposed Work	Zone)
BUILDING LINE CURB LINE	<u> </u>	SHOW NORTH	BUILDING LINE CURB LINE
CURB LINE	*	<u> </u>	BUILDING LINE
SECTION E: Permit Stipulations (For Of			2 "
Permit Type Fee	Permit Stipu	JIAUUNS	Permit Number
1.			
2.			
3.			
4.			
5.			
Special Stipulations:			
Additional Faces Increase	Tunnalis su	Other (Charita)	
Additional Fees: Inspection:	Tunneling:	Other (Specify):	
OCMC Approval by:		Date:	/ /
	ECTION F: Acknowledgements and Agreement		ant
The	e permit to be granted is subject to the follo e applicant agrees to comply with all laws a permit shall be issued unless all applicable	nd rules of the Department and any other	applicable laws and rules.
10	. Submitted by:	20. Tel #:(, <u> </u>
Date Date	(Please P	,	
/ / / 21	. Signed by:	22 Date	1
, , , , , , , , , , , , , , , , , , , ,	(Authorized Representa		

INSTRUCTIONS FOR COMPLETING ROADWAY/SIDEWALK PERMIT APPLICATION PROPERLY

 $To ensure the proper processing of your application, please print all information {\it CLEARLY}.$

SECTION A: Applicant Information

- 1. <u>Permittee ID#:</u> Provide the unique 5 digit identification number the Permittee received when he/she registered their company with the Department of Transportation. Permits will not be issued without a Permittee ID Number.
- 2. <u>Permittee Name</u>: Provide the name of the company to whom the permits will be issued and to whom the above Permittee ID# is assigned.
- 3. Address: Provide the Permittee's business mailing address.
- 4. <u>Tel #:</u> Provide the Permittee's daytime telephone number.
- 5. <u>E-mail</u>: Provide the Permittee's e-mail address.

SECTION B: Work Information

- 6. <u>Borough</u>: Check the Borough in which the proposed work will be performed (MN-Manhattan, BK-Brooklyn, QN-Queens, BX-Bronx, SI-Staten Island).
- 7. OCMC File: If one exists, provide the OCMC file number pertaining to the proposed work (e.g. MEC-08-001).
- 8. Type of Pavement:
 - a. Roadway: If working in the roadway, provide the surface material of the roadway where the proposed work will occur (e.g. Asphalt)
 b. Sidewalk: If working in the sidewalk, provide the surface material of the sidewalk where the proposed work will occur (e.g. Concrete)
- 9. DOB#: Provide any applicable Department of Buildings permit numbers.
- 10. House No.: Provide the house number of the building where the proposed work will occur.
- 11. On Street: Provide the name of the street where the proposed work will occur.
 - 11a. Street Work On, If Different From Above: Provide the name of the street where the physical proposed work will occur if it is not occurring on the same street to which the address applies. (e.g.: Work being performed for 55 Water Street, but excavation is on Old Slip).
- 12. Between: and : Provide the names of the two streets with which the On Street intersects (Cross Streets).
- 13. For the Purpose of: Provide the reason why you are applying for permits (e.g.: New Bldg. Construction, Repair Defective Sidewalk, etc.).
- 14. Number of Openings: Provide the number of proposed open excavations to be made.
- 15. Area Size: Provide the total square footage of the proposed work area.
- 16. <u>Frontage Length</u>: Provide the total linear footage of all proposed work. Provide total building's frontage length if performing new building or building alteration work.
- 17. <u>Work Start Date</u>: Provide the date when the proposed work is expected to commence. (May be changed by NYC DOT to reflect permit restrictions)
- 18. <u>Work End Date</u>: Provide the anticipated completion date of the proposed work. (May be changed by NYC DOT to reflect permit restrictions)


SECTION C: Type of Permit Requested

Check all permit types that you wish to apply for today based on your proposed work

SECTION D: Work Zone Sketch

Provide a diagram of the proposed work location for which you are requesting a permit. Show all pertinent information including On Street, both Cross Streets, North Arrow, Sidewalk/Roadway widths and location of excavations or placement of construction equipment/material, etc. NOTE: If completing this form online, On Street, Cross Streets, North Arrow and Sidewalk/Roadway widths may be filled in, however the work zone sketch must be hand-drawn after printing this form.

EXAMPLE:



SECTION E: Permit Stipulations (For Official Use Only)

This area is for OCMC Project Managers' use only. This is where you will see what permit stipulations will be issued and printed on the approved permit(s). DO NOT WRITE IN THIS AREA.

SECTION F: Acknowledgements and Agreements by Authorized Representative of the Applicant

- 19. Submitted By: Print the name of the person who is submitting this application for review and approval.
- 20. <u>Tel #</u>: Provide a valid daytime telephone number of the person submitting this application.
- 21. <u>Signed By</u>: The person submitting this application must be an authorized representative of the applicant and must provide his/her original signature.
- 22. Date: Provide the date of application submittal.